

# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 72.3 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 103  
**PROJECT No:** 72138  
**DATE:** 14/12/2010  
**SHEET 1 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
72	0.05	ASPHALT - 50mm																A/E			11,17,22 N = 39
	0.4	FILLING (ROADBASE) - grey blue metal gravel filling																A/E			
1		SANDSTONE - extremely low strength, extremely weathered, orange and grey sandstone																A/E			
71																		S			
	1.61																				PL(A) = 0.6  PL(A) = 0.9  PL(A) = 1.3  PL(A) = 1.8  PL(A) = 1.8  PL(A) = 1.6  PL(A) = 1.1  PL(A) = 1.5
2	1.95	SANDSTONE - very low to low strength, highly weathered, slightly fractured, orange, medium grained sandstone																			
70	2.4	SANDSTONE - medium strength, fresh and moderately weathered, slightly fractured, light grey, medium grained sandstone with distinct laminations																C	96		
3		SANDSTONE - high strength, slightly and moderately weathered then fresh, slightly fractured and unbroken, light orange and light grey, medium grained sandstone																			
69	3.3	- siltstone laminations from 3.3 to 4.0m																			
4																					
68																					
5																					
67																					
6																					
66																					
7																					
65																					
8																					
64																					
9																					
63																					

**RIG:** DT 100

**DRILLER:** SY

**LOGGED:** PGH

**CASING:** HW to 1.50m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.50m; NMLC-Coring to 14.08m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Standpipe installed to 14.0m; Groundwater measured at 4.3m on 20/12/10, 4.7 on 22/12/10 and 4.6m on 11/1/11

**SURVEY DATUM:**

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U <sub>t</sub>	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	Δ	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)



**Douglas Partners**  
 Geotechnics | Environment | Groundwater

# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 72.3 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 103  
**PROJECT No:** 72138  
**DATE:** 14/12/2010  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		Ex-Low	Low	Medium	High	Ex-High			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
62		SANDSTONE - high strength, slightly and moderately weathered then fresh, slightly fractured and unbroken, light orange and light grey, medium grained sandstone (continued)																			PL(A) = 2
11																		C	100		PL(A) = 1.4
12																					PL(A) = 1.5
13																		C	100		PL(A) = 1.5
14	14.08	Bore discontinued at 14.08m																			
15																					
16																					
17																					
18																					
19																					

**RIG:** DT 100

**DRILLER:** SY

**LOGGED:** PGH

**CASING:** HW to 1.50m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.50m; NMLC-Coring to 14.08m


**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** Standpipe installed to 14.0m; Groundwater measured at 4.3m on 20/12/10, 4.7 on 22/12/10 and 4.6m on 11/1/11

**SURVEY DATUM:**

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test ts(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test ts(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	Δ	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)





DOUGLAS PARTNERS PTY LTD

MACQUARIE VILLAGE

BORE 103 PROJECT 72138 14 DECEMBER 2010



# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 73.6 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 104  
**PROJECT No:** 72138  
**DATE:** 20/12/2010  
**SHEET 1 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering				Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing				
			EW	HW	MW	SW		FS	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %
73	0.05	ASPHALT - 50mm thick															A/E			Note: Unless otherwise stated, rock is fractured along rough planar bedding planes dipping between 0°- 10°	10,16,21 N = 37
	0.3	FILLING - roadbase gravel filling															A/E				
		SANDSTONE - extremely low strength, red grey sandstone with clay															A/E				
																	S				
72	1.6	CLAY - apparently very stiff, grey clay with some sand																		3.45m: Cs, 9mm	PL(A) = 0.9  PL(A) = 1.9 PL(A) = 1.3
	2.1	SANDSTONE - medium to high strength, highly and moderately weathered, fractured, grey and purple red, medium to coarse grained sandstone with distinct laminations															C	100	71		
	3.1	SANDSTONE - medium to high strength, highly and moderately weathered, fractured then slightly fractured, grey and purple red, medium to coarse grained sandstone																			
	3.46	SANDSTONE - high strength, highly and slightly weathered then fresh, slightly fractured and unbroken, red purple then light grey, medium to coarse sandstone																			
71																				5.68m: Cs, 20mm	PL(A) = 1.5  PL(A) = 1.4
																	C	100	91		
70																				6.65m: J85°, pl, ro, fe	PL(A) = 1
69																				7.72m: J82°, pl, ro, cln	PL(A) = 0.1  PL(A) = 1
68																				7.30-7.35m: very low strength, black carbonaceous band	PL(A) = 1.4
67																				7.30-7.35m: very low strength, black carbonaceous band	PL(A) = 1.4
66																				7.30-7.35m: very low strength, black carbonaceous band	PL(A) = 1.4
65																				7.30-7.35m: very low strength, black carbonaceous band	PL(A) = 1.4
64																				7.30-7.35m: very low strength, black carbonaceous band	PL(A) = 1.4

**RIG:** DT 100

**DRILLER:** SS

**LOGGED:** PGH

**CASING:**

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary (water) to 1.5m; NMLC-Coring to 14.70m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:**

**SURVEY DATUM:**

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	D	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 73.6 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 104  
**PROJECT No:** 72138  
**DATE:** 20/12/2010  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing							
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium				High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %
63	11	SANDSTONE - high strength, highly and slightly weathered then fresh, slightly fractured and unbroken, red purple then light grey, medium to coarse sandstone (continued)																						PL(A) = 1.1
62	12																	C	100	99				PL(A) = 2.2
61	13	12.72-12.74m: very low strength, laminite band																						PL(A) = 3.2
60	14																	C	100	100				PL(A) = 2.2
59	14.7	Bore discontinued at 14.7m																						
58	15																							
57	16																							
56	17																							
55	18																							
54	19																							

**RIG:** DT 100

**DRILLER:** SS

**LOGGED:** PGH

**CASING:**

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; Rotary (water) to 1.5m; NMLC-Coring to 14.70m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:**

**SURVEY DATUM:**

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)



DOUGLAS PARTNERS PTY LTD

MACQUARIE VILLAGE

BORE 104 PROJECT 72138 14 DECEMBER 2010



DOUGLAS PARTNERS PTY LTD

MACQUARIE VILLAGE


BORE 104 PROJECT 72138 14 DECEMBER 2010



DOUGLAS PARTNERS PTY LTD

MACQUARIE VILLAGE

BORE 104 PROJECT 72138 14 DECEMBER 2010





# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 73.9 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 105  
**PROJECT No:** 72138  
**DATE:** 14/12/2010  
**SHEET 1 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing				
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium			High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
	0.04	ASPHALT																A/E			
	0.2	FILLING - crushed sandstone gravel filling with some sand																A/E			
		CLAY - red and grey clay																A/E			
73	1.0	SHALY CLAY - hard, grey shaly clay with some high strength ironstone bands																			
72																					
	2.44	LAMINITE - high strength, highly to slightly weathered, slightly fractured, light grey and red, medium to coarse grained sandstone																C	100	51	PL(A) = 1.5
71																					PL(A) = 1.6
3																					
	3.6	SANDSTONE - high strength, slightly weathered and fresh, slightly fractured, light grey, medium to coarse grained sandstone																			PL(A) = 1.3
70																					
69	5																	C	100	93	PL(A) = 1.5
68	6																				PL(A) = 1.4
67	7	- siltstone laminations from 6.7m to 7.8m																			PL(A) = 2.7
66	8																	C	100	100	PL(A) = 1.5
65	9																				PL(A) = 3
64																					

**RIG:** Scout

**DRILLER:** RKE

**LOGGED:** PGH

**CASING:** HW to 1.0m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; NMLC-Coring to 15.0m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:**

**SURVEY DATUM:**

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 73.9 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 105  
**PROJECT No:** 72138  
**DATE:** 14/12/2010  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)	Discontinuities		Sampling & In Situ Testing			
			EW	HW	MW	SW	FS		Ex Low	Low	Medium	High	Very High			B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments
63	11	SANDSTONE - high strength, slightly weathered and fresh, slightly fractured, light grey, medium to coarse grained sandstone (continued)																			PL(A) = 1.7
62	12																	C	100	100	PL(A) = 1.6
61	13																				PL(A) = 1.6
60	14																	C	100	100	PL(A) = 2 PL(A) = 1.9
59	15.0	Bore discontinued at 15.0m																			
58	16																				
57	17																				
56	18																				
55	19																				
54																					

**RIG:** Scout

**DRILLER:** RKE

**LOGGED:** PGH

**CASING:** HW to 1.0m


**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; NMLC-Coring to 15.0m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:**

**SURVEY DATUM:**

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		gp	Pocket penetrometer (kPa)
		S	Standard penetrometer test
		V	Shear vane (kPa)






DOUGLAS PARTNERS PTY LTD

MACQUARIE VILLAGE

BORE 105 PROJECT 72138 14 DECEMBER 2010



# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 73.2 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 106  
**PROJECT No:** 72138  
**DATE:** 16/12/2010  
**SHEET 1 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength						Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing					
			EW	HW	MW	SW	FS		Ex Low	Very Low	Low	Medium	High	Very High				Ex-High	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %
73	0.05	ASPHALT																					
	0.2	FILLING - crushed sandstone filling with some sand																					
	0.7	CLAY - red grey clay																					
1	1.0	LAMINITE - extremely low strength, extremely and highly weathered laminite																					
	1.88	LAMINITE - extremely low and very low strength, extremely and highly weathered, slightly fractured, grey laminite with clay bands																					
2		LAMINITE - medium to high strength, moderately to highly then slightly weathered, slightly fractured, purple-red and grey, medium to coarse grained laminite																					
3																							
72	3.61	SANDSTONE - high strength, moderately to highly weathered, slightly fractured, purple-red and grey, medium to coarse grained sandstone																					
71																							
70																							
69																							
68																							
67																							
66	6.81	SANDSTONE - medium to high and high strength, moderately and slightly weathered, slightly fractured, orange and light grey, medium to coarse grained sandstone with indistinct cross-beds																					
65																							
64																							

**RIG:** Scout

**DRILLER:** KKE

**LOGGED:** PGH

**CASING:** HW to 1.0m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; NMLC-Coring to 15.0m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** 30% Water loss at 7.30m

**SURVEY DATUM:**

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Stamford Property Services Pty Ltd  
**PROJECT:** Macquarie Village  
**LOCATION:** 110-114 Herring Road, Macquarie Park

**SURFACE LEVEL:** 73.2 AHD  
**EASTING:**  
**NORTHING:**  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 106  
**PROJECT No:** 72138  
**DATE:** 16/12/2010  
**SHEET 2 OF 2**

RL	Depth (m)	Description of Strata	Degree of Weathering				Graphic Log	Rock Strength				Water	Fracture Spacing (m)	Discontinuities	Sampling & In Situ Testing						
			EW	HW	MW	SW		FS	FR	Ex Low	Very Low			Low	Medium	High	Very High	Ex High	B - Bedding S - Shear	J - Joint F - Fault	Type
63		SANDSTONE - medium to high and high strength, moderately and slightly weathered, slightly fractured, orange and light grey, medium to coarse grained sandstone with indistinct cross-beds <i>(continued)</i>													10m: J85°, pl, ro, fe					PL(A) = 1.2	
11																10.72m: J80°, pl, ro, he 10.87m: J85°, pl, ro, he 11.04m: J75°, pl, ro, fe 11.15m: J85°, pl, ro, fe					
62		SANDSTONE - high strength, slightly weathered and fresh, slightly fractured, light orange and grey, medium to coarse grained sandstone													11.45m: J80°, pl, ro, fe	C	100	100		PL(A) = 1	
11.45																					PL(A) = 1.1
12																12.14m: B, cly					
61																					
13																12.95m: J80°, pl, ro, fe					PL(A) = 1
60		Bore discontinued at 15.0m																			
14																13.8m: B, cly	C	100	100		
59																					
15	15.0																C	100	100		PL(A) = 1
58																					
16																					
57																					
17																					
56																					
18																					
55																					
19																					
54																					

**RIG:** Scout

**DRILLER:** KKE

**LOGGED:** PGH

**CASING:** HW to 1.0m

**TYPE OF BORING:** Solid flight auger (TC-bit) to 1.0m; NMLC-Coring to 15.0m

**WATER OBSERVATIONS:** No free groundwater observed whilst augering

**REMARKS:** 30% Water loss at 7.30m

**SURVEY DATUM:**

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	Δ	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)