

Mt Kuring-Gai 12/9-15 Gundah Rd Mt Kuring-Gai NSW 2080 T: (02) 8438 0300

1/140 Industrial Rd Oak Flats NSW 2529 T: (02) 4257 4458 F: (02) 8438 0310 F: (02) 4257 4463

Wollongong

E: admin@netgeo.com.au W: www.netgeo.com.au ABN: 35 069 211 561

### **TCG PLANNING** PROPOSED LIFE CITY WOLLONGONG **WARWICK STREET BERKELEY LIMITED STAGE 2 CONTAMINATION INVESTIGATION** REPORT G09/1100-B **JANUARY 2014**



Mt Kuring-Gai 12/9-15 Gundah Rd Mt Kuring-Gai NSW 2080 T: (02) 8438 0300 F: (02) 8438 0310 Wollongong 1/140 Industrial Rd Oak Flats NSW 2529 T: (02) 4257 4458 F: (02) 4257 4463

E: admin@netgeo.com.au W: www.netgeo.com.au ABN: 35 069 211 561

G09/1100-B VDS:RS 28 January, 2014

TCG Planning 5-174/182 Gipps Road GWYNNEVILLE NSW 2500

Attention: Elaine Treglown

Dear Sir

Re: Proposed Life City Wollongong, Warwick Street, Berkeley: Limited

Stage 2 Contamination Assessment.

Please find enclosed our report for a Limited Stage 2 Contamination Assessment of above site.

The report includes site history review based on Clearsafe Environmental Solutions Phase 1 Contamination Assessment (Project 1357-01-LC dated November, 2012), subsurface investigation results and analytical test results for samples recovered during the investigation. Report recommendations cover an assessment of risk of site contamination in relation to the proposed development.

The report was prepared in accordance with NSW Government Office of Environment & Heritage (OEH) Guidelines for Consultants Reporting on Contaminated Sites.

This report should be read in conjunction with the attached General Notes. Please contact the undersigned should you have any queries.

For and on behalf of Network Geotechnics Pty Ltd

V W de Silva BScEng, MEng, SMIE Aust, CPEng, NPER Principal Geotechnical Engineer

#### **EXECUTIVE SUMMARY**

Network Geotechnics Pty Ltd (NG) was commissioned by Delbest Pty Ltd C/- TCG Planning to undertake a Limited Stage 2 Contamination Assessment for proposed Life City Wollongong development, Warwick Street, Berkeley, NSW.

It is understood that Clearsafe carried out the Preliminary Environmental Assessment (Phase 1) Report no. 1357-01-LC dated 20 November 2012. Clearsafe Phase 1 Report has raised some concerns about the site contamination due to the agriculture activities and illegal dumping of asbestos materials in areas of the site.

The purpose of NG Limited Stage 2 Contamination investigation was to identify above areas and to carry out sufficient contamination testing to assess the level of the contaminants. The recorded results were compared with National Environmental Policy Measures (NEPM) Health Based Investigation Levels (HIL) for Residential use with garden/accessible soil (Column 1).

No physical structures were observed during fieldwork and site was mainly covered with thick grass. Shrub and small to large trees were spread around. Fill was encountered in some of the contamination and geotechnical boreholes to a maximum depth of 1.7m below the existing surface level.

Fieldwork for limited Stage 2 contamination analysis was carried out on 19 November, 2013 by NG which included collection of soil samples from thirteen boreholes (BH10 to BH22) and testing of discrete soil samples for a range of contaminants including metals, TPH, BTEX, polyaromatic hydrocarbons and pesticides. In addition to above thirteen boreholes, some soil samples for contamination tests were collected from the geotechnical boreholes (BH1 to BH9) as well. Fieldwork for the geotechnical investigation was carried out on 21 and 29 November, 2013.

None of the samples tested indicated results higher than the National Environmental Policy Measures (NEPM) Health Based Investigation Levels (HIL) for Residential use with garden/accessible soil (Column 1).

Based on the results of the investigation we assess that the risk of site contamination to be low and the site to be suitable for the proposed development.

Any localised contamination that may be uncovered may be managed during earthworks.

#### **TABLE OF CONTENTS**

	EVECUTIVE CUMMADY	PAGE
1.0	EXECUTIVE SUMMARY	3
1.0	INTRODUCTION	5
1.1	General	5
1.2	Methodology	5
2.0	SITE IDENTIFICATION	6
3.0	SITE HISTORY	6
3.1	Zoning Land Use	6
3.2		6
3.3	Council Rezoning and Relevant Development Records	6
3.4	Notices under Protection of Environment Operations Act	6
3.5	WorkCover Search	7
3.6	Groundwater Bore Search	7
3.7	Aerial Photographs	7
3.8	Product Spill and Loss History	7
3.9	Potential for Contamination	7
4.0	SITE CONDITION & SURROUNDING ENVIRONMENT	7
4.1	Topography	7
4.2	Flood Potential	8
4.3	Geology & Hydrogeology	8
5.0	SAMPLING & ANALYSIS PLAN	11
5.1	Sampling Objectives	11
5.2	Data Quality Objectives	12
5.3	Sampling & Testing	13
6.0	QUALITY ASSURANCE & QUALITY CONTROL	13
6.1	Field Quality Assurance & Quality Control	13
6.2	Laboratory Quality Assurance & Quality Control	14
7.0	SITE ASSESSMENT CRITERIA	14
8.0	RESULTS & DISCUSSION	17
8.1	Boreholes & Visual Assessment	17
9.0	DISCUSSION & SITE CHARACTERISATION	17
9.1	Soils	17
9.1.1	Metals	17
9.1.2	Total Petroleum Hydrocarbon/BTEX	18
9.1.3	Polynuclear Aromatic Hydrocarbon	18
9.1.4	Organochlorine and Organophosphate Pesticides	18
9.1.5	Asbestos	18
9.2	Acid Sulphate Soil	18
9.2.1	Indicators of AASS & PASS	18
9.2.2	Assessment Criteria	18
9.2.3	Screening Tests	19
9.2.4	Results of Laboratory Testing	19
10.0	SITE CHARACTERISATION	20
11.0	WASTE DISPOSAL	20
12.0	CONCLUSIONS & RECOMMENDATIONS	21
General Note	s	
APPENDIX A	Borehole Logs and Terms & Symbols (23 Sheets)	
APPENDIX B	Laboratory Tests Results	
DRAWING No	o. W07/1971-1 Site Plan	

#### 1.0 INTRODUCTION

#### 1.1 General

Network Geotechnics Pty Ltd (NG) was commissioned by TCG Planning to undertake Limited Stage 2 Contamination Assessments for a proposed Life City of Wollongong, Warwick Street, Berkeley, NSW. The investigation was carried out in accordance with NG revised proposal (Ref: G09/1100 dated 04 September 2013).

It is understood that Clearsafe carried out a Preliminary Environmental Assessment (Phase 1) Report no. 1357-01-LC dated 20 November 2012.

This current report includes a summary of site history review, subsurface investigation results and analytical test results for samples recovered during the investigation.

It is understood the proposed development would include:

- Stage 1: Medical Centre and child care centre
- Stage 2: Medical Accommodation
- Stage 3: Hospital Building
- Stage 4: Seniors Independent Living Units
- Stage 5: Seniors Residential Care Facility
- Stage 6: Holistic Health Care Course

Based on the review of Preliminary Contamination Assessment Reports by Clearsafe and the DA drawings, it appears that the site may have contained some contamination due to past activities which include agriculture use and illegal dumping of material at some locations. The proposed development construction may involve reworking of uncontrolled fill and making site stable by construction of retaining walls and drainage.

The objectives of the investigation was to undertake a historical data review, desk study and carry out limited sampling and testing and provide preliminary recommendations on the suitability of the site for a proposed residential development.

#### 1.2 Methodology

The following scope of work was agreed with the client for the Limited Stage 2 contamination assessment:

Limited Stage 2 contamination assessment based on 13 hand augur holes (BH10 to BH22). In addition contamination samples were also collected from nine geotechnical boreholes (BH1 to BH9).

Most of the potential contamination would be in the fill and upper layers of the site. Total numbers of boreholes drilled on site were 22.

The following procedures were used for soil sampling:

- Geotechnical boreholes (BH1 to BH9) were drilled using a truck mounted drilling rig with solid flight augers. Contamination soil samples were collected within 0.0m to 1.7m from all boreholes.
- Soil samples were collected from 0.0-1.0m depth from thirteen (BH10 to BH22) hand augur boreholes.

- Soil samples were tested for metals, pesticides, hydrocarbon and asbestos.
- Quality assurance and Quality Control testing.

#### 2.0 SITE IDENTIFICATION

The proposed site is located at southern end of Warwick Street, Berkley and is bordered by:

- F6 Freeway to the west
- Residential properties to the north, east and south

The site has access from Warwick street and is shown on Locality Map G09/1100-1.

Based on Satellite photographs, the site co-ordinates at Warwick Street access are given below:

Latitude 34° 28′ 06.11″ South Longitude 150° 50′ 24.24″ East

#### 3.0 SITE HISTORY

Clearsafe Phase 1 assessment (Report no. 1357-01-LC dated 20 November 2012) provided a site history based on aerial photographs, council and titles records and a site visit.

#### 3.1 Zoning

The site is currently zoned as 'R2' Low Density Residential and 'E3' Environmental Mangament" under the Wollongong Local Environmental Plan 2009.

#### 3.2 Land Use

A preliminary contamination study carried out by Clearsafe indicated the site has been used as agricultural land up until 1951. From 1951 the agricultured uses has been limited or ceased.

#### 3.3 Council Rezoning and Relevant Development Records

Clearsafe state in their Phase 1 report that the lots covered by the site are zoned Residential "R2" and E3" under Section 149(2) Details of the Wollongong Local Environmental Plan 2009.

Cleasafe conducted a review of available council records. No potential for contamination was recorded in the council files.

#### 3.4 Notices under Protection of Environment Operations Act

Review of records showed that no notices have been issued under the Contaminated Land Management Act 1997 and Protection of the Environment Operation Act 1997.

#### 3.5 WorkCover Search

Clearsafe report (Report no. 1357-01-LC) indicates WorkCover search was not successfully made as authorisation was not obtained from the site owner.

#### 3.6 Groundwater Bore Search

A groundwater bore search was conducted through the national resources database and it has been identified there are no registered groundwater bores within a 650m radius of the current site.

#### 3.7 Aerial Photographs

Reference to Clearsafe Phase 1 contamination assessment indicates that most part of the site remained as undeveloped since 1887. Some part of the site has been used for a agriculture purposes but these activities had been ceased by 1951.

#### 3.8 Product Spill and Loss History

There was no evidence of surface staining as a result of product spill within the proposed site.

#### 3.9 Potential for Contamination

Based on Clearsafe documents reviewed from the Phase 1 investigation and the results of walk over assessment, the following site features may be relevant for assessment of contamination:

- Fill was predominantly encountered in the northern part of the site to maximum depths of 1.5m below the existing grade. Some surface rubbish was noted along the existing top ridgeline vehicular track
- The site has a history of agricultural activities which may be associated with potential contamination.
- Cleasafe noted some building material (bricks, concrete etc) due to illegal dumping on areas in the site. It has a potential to be contaminated with asbestos.

#### 4.0 SITE CONDITION & SURROUNDING ENVIRONMENT

#### 4.1 Topography

The site covered about 8.5 hectares. The topography of the site is a ridgeline that bounded a centre valley. The average site slope is between 5° and 10° dipping toward Princes Motorway.

For site description purpose, we have assumed Princes Motorway abutted the site to the west.

At the time of the investigation, the site surface was covered with thick grasses to a height of up to 0.5m. Shrub and small to large size trees were spread around. During our walkover assessment and locating the borehole locations, the site surface appeared uneven sloping ground due to previous weathering and soil erosion. Several soil erosion gullies were present in the centre of the site, running toward the centre valley.

Two vehicular tracks passes through the site in a north-south direction. One located at the top of the ridgeline (east of the site), the other located near the middle of the site.

Natural silty CLAY and Sandstone bedrock were exposed on the northern part of the site surface near northern end of the top ridgeline vehicular track.

A valley is situated at the centre of the site, which is surrounded by land sloping up to 17° when viewed from the valley floor. The valley floor slopes down to the west at about 3°.

Two stockpiles were observed in the area covered by boreholes BH5, BH6 and BH8. The stockpiles comprised concrete boulders and steel fragments. The location of the stockpiles is shown on our borehole location plans. Some surfaced rubbish was noted along the top ridgeline vehicular track.

Residential houses and local roads bounded the site to the north, east and south. High voltage power lines were located on the southern end of the site.

#### 4.2 Flood Potential

There was no evidence of flooding; however the potential for flooding was not investigated. Council records do not indicate risk of flooding.

#### 4.3 Geology & Hydrogeology

The 1:100,000 Geological Series Sheet of Wollongong-Port Hacking indicates the site to be underlain Illawarra Coal Measures, Cumberland Subgroup Pheasant Nest Formation (Pip) comprising interbedded lithic sandstone, grey siltstone, claystone, carbonaceous claystone, clay, laminate and coal and surrounded by Dapto Latite (Psud) comprising coarse grained Latite. The eastern area of the site is shown to be underlain mid-grey Dolerite.

Subsurface conditions encountered in the NG boreholes and Coffey test pits are discussed for each development stage. Reference should be made to the attached engineering logs for details.

Stage 1 Development: NG's Boreholes 9 to 12

LAYER	DESCRIPTION	DEPTH TO BASE OF LAYER (m)
TOPSOIL	Sandy Silt, low plasticity, dark grey, fine grained sand with roots	0.2 0.5
FILL	Silty CLAY, medium to high plasticity, dark brown, with fine to medium sandstone and ironstone.	0.3 – 0.5
	nonstone.	1.0 - 1.5
RESIDUAL	Silty CLAY, high plasticity, light brown and orange	0.5.0.0
ROCK	Sandstone, fine to medium grained, orange brown	>0.5-2.2
		>5.1

Stage 2 Development: NG's Boreholes 6 and 21, Coffey's TPs 11 and 12

LAYER	DESCRIPTION	DEPTH TO BASE OF LAYER (m)
TOPSOIL	Silty Clay, high plasticity, dark brown, with roots and trace of fine to medium grained ironstone gravel	0.2
FILL	Silty CLAY, medium to high plasticity, dark brown, with fine to medium sandstone and ironstone.	1.0 - 1.5
RESIDUAL	Silty CLAY, medium to high plasticity, light brown and orange, trace of fine to medium grained ironstone gravel	11265
ROCK	Weathered Sandstone, fine to medium grained, brown	1.1-2.65 >4.74

Stage 3 Development: NG's Boreholes 1, 2, 3 and 13, Coffey's TPs 1 and 2

LAYER	DESCRIPTION	DEPTH TO BASE OF LAYER (m)
TOPSOIL	Silty Clay, high plasticity, dark brown, with roots	0.2
FILL	Silty CLAY, medium to high plasticity, dark brown, with fine to medium sand, fine to medium grained sandstone and ironstone and latite cobbles and boulders.	0.2
		0.5 - 1.7
RESIDUAL	Silty CLAY/Sandy CLAY, medium to high plasticity, light brown and orange, trace of fine to medium grained sandstone and ironstone gravel	
ROCK	Weathered Sandstone/Latite, fine to medium grained, brown	1.7-2.6
	granica, brown	>4.4, >4.5

Stage 4 Develo	pment: NG's	Borehole 4,	Coffey's	TP 10

LAYER	DESCRIPTION	DEPTH TO BASE OF LAYER (m)
TOPSOIL	Silty Clay, high plasticity, dark brown, with roots and fine to medium grained ironstone gravel	0.2
RESIDUAL	Silty CLAY, medium to high plasticity, dark brown, with fine to medium sand, fine to medium grained sandstone and ironstone and latite cobbles and boulders.	0.2
	lattice copplies and boulders.	1.65
RESIDUAL	Sandy CLAY, medium plasticity, orange brown, dark brown and red brown, trace of fine to medium grained sand.	
ROCK	Weathered Latite, fine to coarse grained, brown	1.5-3.0
		>1.6, >8

#### Stage 5 Development: NG's Borehole 5

LAYER	DESCRIPTION	DEPTH TO BASE OF LAYER (m)
TOPSOIL	Silty Clay, high plasticity, dark brown, with roots and fine to medium grained ironstone gravel	
RESIDUAL	Silty CLAY, high plasticity, brown, trace of root fibres and with fine grained ironstone gravel	3.4
ROCK	Weathered Latite, fine to coarse grained, brown, with iron indurated band	>4.15

Groundwater monitoring wells were installed into BH3, BH6 and BH8 after completion of core drilling.

Groundwater was measured in BH's 3 and 6 wells at depths of 3.31m and 0.68, respectively after one day of drilling completion. Groundwater was not recorded in BH8 well.

Groundwater measurements carried out on 6/1/14 indicate depth to groundwater in BH3 to be 3.31 m and other wells dry.

#### 5.0 SAMPLING & ANALYSIS PLAN

#### 5.1 Sampling Objectives

The site is assessed to be having a low to moderate risk of potential contamination based on Clearsafe Phase 1 investigation. The site area is about 8.5ha. A total of 22 sampling locations were investigated for contamination assessments in Limited Stage 2 investigation. The contamination boreholes were drilled in the hot spot areas identified by Clearsafe report.

Soil sampling was undertaken during the field investigation and was broadly based on the following objectives:

Most of the potential contamination would be in the fill and upper layers of the site.

The following procedures were used for soil sampling:

- Boreholes (BH1 to BH9) were drilled using a truck mounted drilling rig with solid flight augers. Auger head was decontaminated after each sample.
   Soil samples were collected from a depth ranging from 0.05m to 1.7m from the boreholes.
- Boreholes (BH10 to BH22) were drilled using a hand augur to a depth ranging from 0.3m to 1.0m. Soil samples were collected from a depth ranging from 0.05 to 1.0m.

The soil samples for contamination testing were collected in glass jars sealed, labelled and placed in a large insulated box with ice and transported to the laboratory.

USEPA analytical methods as adopted by Australian Laboratory Service (ALS NATA Registration No 825) were used for testing for the following contaminants of concern (COC):

- Heavy metals including mercury
- Total Petroleum Hydrocarbon (TPH)
- Benzene, Toluene, Ethyl Benzene and Xylene (BTEX)
- Polynuclear Aromatic Hydrocarbon (PAH)
- Asbestos
- OC/OP Pesticides
- pH
- Ec

A total of 49 samples were sent to the laboratory. The first batch comprised 14 samples of which 5 samples suspected of potential hydrocarbon, metals and asbestos contamination were tested as discrete samples. The remaining samples were put on hold in the laboratory. The second batch comprised 35 samples of which one sample was tested as discrete sample for hydrocarbon contamination. 7 discrete samples were composited to 3 composite samples in laboratory to test for metals, pesticides and asbestos. Samples collected included representative samples of fill, some topsoil in former vegetable gardens, some residual soils in contact with the fill and other soils which were assessed to be discoloured.

#### 5.2 Data Quality Objectives

The seven step process for data quality objectives in this investigation included the following:

#### Step 1 Identify the Problem

 Make an assessment of contamination of soils within the site to identify any contamination hot spots based on the Clearsafe Phase 1 assessment and the site condition at the time of investigation, which may affect human health and the environment.

#### Step 2 Identify the Decisions

 Assess whether any contamination on site poses a risk to site occupants under low density residential scenario and the protection of the environment.

#### Step 3 Identify Inputs

- Drill an adequate number of boreholes in areas identified as having a risk of contaminated soil.
- Visually assess all collected samples for site contamination such as odour, colour etc.
- Test a statistically significant number of samples to characterise the area to provide data on average concentration.

#### Step 4 Project Boundaries

Project boundary was taken as the whole area covered by the title.

#### Step 5 Decision Rule

- Analytical methods and detection levels appropriate for contaminated site assessment approved by NSW EPA Guidelines will be used and testing will be carried out by ALS Environmental laboratory.
- Define assessment criteria. For assessment of site contamination National Environmental Protection Measures health based guidelines for residential allotment with accessible garden (NEPM HIL A).
- All parameters exceeding the action criteria are assessed as representing an area where further investigation is needed.

#### Step 6 Error Tolerances

- Limit of reporting adopted by ALS Laboratory were assessed to be relevant. Error tolerances indicated in Laboratory Quality Control reports were adopted.
- A confidence level of 95% has been adopted for detailed investigation.

#### Step 7 Optimise Sample Design

 Sample design was based on the need for a reliable data for assessment of site contamination. The horizontal and vertical spacing of sampling was based on expected contamination potential. Sample locations were selected to assess targeted areas and site coverage.

#### 5.3 Sampling & Testing

Field investigations for limited Stage 2 and the geotechnical investigation was carried out on 19, 22 & 29 November 2013 by NG Engineering staff and comprised a walkover assessment as well. Drilling included twelve hand augur holes of 0.2m diameter for contamination testing to a termination depths ranging from 0.3m to 1.0m. Contamination samples were also collected during the geotechnical investigation. Geotechnical drilling was carried out by a truck mounted drilling rig attached to a 125mm auger with TC-bit attachment. Disturbed soil samples were collected in laboratory prepared glass jars and placed in an insulated box with ice and transferred to the laboratory.

A summary of sample composting and testing type is shown in the table below:

Sample Reference	Sample Description		Composite Sample Reference	Testing
BH1 (0.0-0.1m)	Fill: Silty CL	ΑY	Discrete	TPH/BTEX/PAH
BH1 (0.0-0.1m)	Fill: Silty CL	ΑY	C1	8 Metals/Asbestos
BH1 (0.5-0.7m)	Fill: Silty CL	ΑY	C1	8 Metals/Asbestos
BH2 (0.0-0.1m)	Topsoil: CLAY	Silty	C1	8 Metals/Asbestos
BH3 (0.0-0.1m)	Topsoil: CLAY	Silty	C2	8 Metals/OC/CP/PCB/Asbestos
BH4 (0.0-0.1m)	Topsoil: CLAY	Silty	C2	8 Metals/OC/CP/PCB/Asbestos
BH5 (0.0-0.1m)	Topsoil: CLAY	Silty	C3	8 Metals/OC/CP/PCB/Asbestos
BH6 (0.0-0.1m)	Topsoil: CLAY	Silty	C3	8 Metals/OC/CP/PCB/Asbestos
BH10 (0.8-1.0m)	Fill: Sandy C	CLAY	Discrete	8 Metals/TPH/BTX/PAH Asbestos
BH12 (0.3-0.5m)	Fill: Silty CL	ΑY	Discrete	8 Metals/TPH/BTX/PAH Asbestos
BH13 (0.4-0.5m)	Fill: Sandy C	CLAY	Discrete	8 Metals/TPH/BTX/PAH Asbestos
BH14 (0.1-0.2m)	Fill: Sandy C	CLAY	Discrete	8 Metals/TPH/BTX/PAH Asbestos
BH15 (0.1-0.3m)	Fill: Silty CL	ΑY	Discrete	8 Metals/TPH/BTX/PAH Asbestos

Borehole logs are included in Appendix A and approximate borehole locations are shown on Drawing No. G09/1100-2.

#### 6.0 QUALITY ASSURANCE & QUALITY CONTROL

#### 6.1 Field Quality Assurance & Quality Control

Field quality assurance objectives were designed based on Australian Standard AS4482 and comprised the following:

- Sample collection and dispatch to testing laboratory were carried out by experienced environmental/civil engineers appropriately trained for such tests.
- All sampling tools were decontaminated prior to use. Soil samples were collected from auger cuttings. The borehole was drilled with a clean auger

head to the target depth and the auger was retrieved, cleaned using a rag, washed with clean water, decontaminated with 1% DECON 90 solution and rinsed with distilled water. The auger was advanced by further 150mm and the sample was retrieved from auger using decontaminated hand tools. Water samples were collected from a new Teflon bailer for each monitoring well.

- Chain of custody forms were used in dispatching samples.
- Containers, sampling packaging and holding times were checked prior to dispatch of samples and checked after samples were received by the laboratories.

#### 6.2 Laboratory Quality Assurance & Quality Control

Only NATA accredited laboratories were used for testing. Certificates of analysis and quality control records were reviewed for each batch of test results.

Specific elements that have been checked and assessed include the following:

- Preservation and storage of samples upon collection and during transport to the laboratory;
- Sample holding times;
- Use of appropriate analytical and field sampling procedures;
- Required limits of reporting and;
- The occurrences of apparently unusual or anomalous results, eg laboratory results that appear to be inconsistent with field observations or measurements have been assessed.

On the basis of the analytical data validation procedures employed, the overall quality of the analytical data produced is considered to be of an acceptable standard for interpretive use.

#### 7.0 SITE ASSESSMENT CRITERIA

The assessment of potentially contaminated land involves the evaluation of potential human health hazards and environmental impacts. The receptors (or potential receptors) of concern may be within the site being assessed, or outside the site boundaries due to potential off-site migration of contaminants.

The following assessment criteria were used for assessment of the site soils:

 The Health-Based Investigation Levels (HBIL) summarised in the following Table 1a, which are Schedule B1 of the NEPM and Guidelines May 2013 are used for assessing the risk to human health

The above mentioned levels are presented on the following Tables 1A(1), 1A(2) and 1A(3) below:

Table 1A(1) Health Investigation Levels for soil contaminants (mg/kg)

	Health-based investigation levels (mg/kg)								
Chemical	Residential <sup>1</sup> A	Residential <sup>1</sup> B	Recreational <sup>1</sup> C	Commercial/ industrial <sup>1</sup> D					
	Metals a	nd Inorganics							
Arsenic <sup>2</sup>	100	500	300	3 000					
Beryllium	60	90	90	500					
Boron	4500	40 000	20 000	300 000					
Cadmium	20	150	90	900					
Chromium (VI)	100	500	300	3600					
Cobalt	100	600	300	4000					
Copper	6000	30 000	17 000	240 000					
Lead <sup>3</sup>	300	1200	600	1 500					
Manganese	3800	14 000	19 000	60 000					
Mercury (inorganic) <sup>5</sup>	40	120	80	730					
Methyl mercury <sup>4</sup>	10	30	13	180					
Nickel	400	1200	1200	6 000					
Selenium	200	1400	700	10 000					
Zinc	7400	60 000	30 000	400 000					
Cyanide (free)	250	300	240	1 500					
* ; ;	Polycyclic Aromat	ic Hydrocarbons (							
Carcinogenic	2 ory cyclic 121 oznik	L 11) al ocuitous (							
PAHs									
(as BaP TEQ) <sup>6</sup>	3	4	3	40					
Total PAHs <sup>7</sup>	300	400	300	4000					
	I	henols							
Phenol	3000	45 000	40 000	240 000					
Pentachlorophenol	100	130	120	660					
Cresols	400	4 700	4 000	25 000					
	Organoch	lorine Pesticides							
DDT+DDE+DDD	240	600	400	3600					
Aldrin and dieldrin	6	10	10	45					
Chlordane	50	90	70	530					
Endosulfan	270	400	340	2000					
Endrin	10	20	20	100					
Heptachlor	6	10	10	50					
HCB	10	15	10	80					
Methoxychlor	300	500	400	2500					
Mirex	10	20	20	100					
Toxaphene	20	30	30	160					
	H	erbicides							
2,4,5-T	600	900	800	5000					
2,4-D	900	1600	1300	9000					
MCPA	600	900	800	5000					

	Health-based investigation levels (mg/kg)								
Chemical	Residential A Residential B		Recreational <sup>1</sup> C	Commercial/ industrial <sup>1</sup> D					
MCPB	600	900	800	5000					
Mecoprop	600	900	800	5000					
Picloram	4500	6600	5700	35000					
	Othe	r Pesticides							
Atrazine	320	470	400	2500					
Chlorpyrifos	160	340	250	2000					
Bifenthrin	600	840	730	4500					
	Othe	r Organics							
PCBs <sup>8</sup>	1	1	1	7					
PBDE Flame Retardants (Br1-Br9)	,	2	2	10					

<u>Table 1A(2) Interim soil vapour health investigation levels for volatile organic chlorinated compounds</u>

		Interim soil vapour HIL (mg/m³)										
Chemical	Residential <sup>1</sup> A	Residential <sup>1</sup> B	Recreational <sup>1</sup> C	Commercial / Industrial <sup>1</sup> D								
TCE	0.02	0.02	0.4	0.08								
1,1,1-TCA	60	60	1200	230								
PCE	2	2	40	8								
cis-1,2- dichloroethene	0.08	0.08	2	0.3								
Vinyl chloride	0.03	0.03	0.5	0.1								

#### Notes:

- 1) NEPM Table 1A(2) was used for volatile chlorinated compound.
- 2) NEPM Table 1A(3) for clay soils were used for assessment of hydrocarbon compounds.

Table 1A(3) Soil HSL's for vapour intrusion (mg/kg)

	HSL A & HSL B Low - high density residential				HSL C recreational / open space			HSL D Commercial / Industrial					
Naphthalene	4	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	10
Benzene	0.6	0.7	1	2	NL	NL	NL	NL	4	4	6	10	440
F1(9)	40	65	100	190	NL	NL	NL	NL	250	360	590	NL	910
F2(10)	230	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	570
						CLA	Υ						
Toluene	480	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	630
Ethylbenzene	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	68
Xylenes	110	310	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	330
Naphthalene	5	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	10
Benzene	0.7	1	2	3	NL	NL	NL	NL	4	6	9	20	430
F1(9)	50	90	150	290	NL	NL	NL	NL	310	480	NL	NL	850
F2(10)	280	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	NL	560

#### Notes:

- 1) Land use settings are equivalent to those described in Table 1A (1) Footnote 1 and Schedule B7, though secondary school buildings should be assessed using residential 'A/B' for vapour intrusion purposes.
- 2) Interim HIL's for VOCCs are conservative soil vapour concentrations that can be adopted for the purpose of screening sites where further investigation is required on a site specific basis. They are based on the potential for vapour intrusion using an indoor air-to-soil vapour attenuation factor of 0.1 and an outdoor air-to-soil vapour attenuation factor of 0.05.
- 3) Application of the interim HIL's is based on a measurement of shallow (to 1m depth) soil vapour (or deeper where the values are to be applied to a future building with a basement) or sub slab soil vapour.

- 4) The applicability of the interim HIL's needs to be further considered when used for other building types such as homes with crawl space and no slab, which may require site specific assessment.
- 5) Use of the interim HIL's requires comparison with data that has been collected using appropriate methods and meets appropriate data quality requirements.
- 6) To obtain F1 subtract the sum of BTEX concentrations from the C6 to C10 fraction.
- 7) To obtain F2 subtract naphthalene from the >C10-C16 fraction.

The site is assessed under Commercial/Residential use. Consequently, the issues of concern for contamination within the site are considered to be the risk of harm to human health and environmental impacts.

The test results for soils will therefore be assessed against the available Health-Based Investigation Levels (HBIL) for Commercial/Residential 'A' & 'B'.

Based on NEPM and EPA guidelines, the following assessment criteria will be used for the assessment of site contamination and validation:

- The 95% Upper Confidence Level (UCL) of the mean of the data set must be less than the relevant threshold level; ie, it is acceptable to have individual exceedances of the guideline, but the 95% UCL of the mean of the data set of soil sample results should not exceed the threshold level.
- The standard deviation of the data set must be less than 50% of the relevant threshold level.
- No individual test result exceeds 250% of the relevant threshold level.

#### 8.0 RESULTS & DISCUSSION

#### 8.1 Boreholes & Visual Assessment

Samples recovered from boreholes (BH1 to BH22) were examined in the laboratory. There were no visible signs or odours to suspect soil contamination in BH1 to BH22. Fill samples were found to be typically dark brown or grey.

#### 9.0 DISCUSSION AND SITE CHARACTERISATION

#### 9.1 **Soils**

Test results recorded during the limited Stage 2 investigation are discussed below.

#### 9.1.1 Metals (soil)

Total of 3 composite and 5 discrete soil samples were tested. All samples tested recorded below the Health-Based Investigation Levels (HBIL), for residential sites with accessible gardens (NEHF-A), and the suggested Levels in the EPA service station guidelines.

#### 9.1.2 Total Petroleum Hydrocarbon/BTEX

Six discrete samples were tested for TPH/BTEX. All samples tested recorded TPH/BTEX levels below the laboratory detection level.

#### 9.1.3 Polynuclear Aromatic Hydrocarbon

Six discrete samples were tested for PAH. All samples tested recorded PAH below Laboratory detection level.

#### 9.1.4 Organochlorine and Organo phosphate Pesticides

Two composite samples were tested for OC/OP. All samples tested recorded OC/OP below Laboratory detection level.

#### 9.1.5 Asbestos

No asbestos was detected in any of the eight soils samples tested. It may be noted that all fill samples collected were tested for asbestos.

#### 9.2 Acid Sulphate Soil

#### 9.2.1 Indicators of AASS & PASS

Indicators of acid sulphate materials are as follows:

**Screening Tests:** Potential Acid Sulphate Soil (PASS) indicators include significant negative pH shifts during screening tests and pH following oxidation (pHFox) below pH 3. Samples with pHF <4.0 indicate that insitu conditions are already acidic. For pHF approximately equal to 7 the soil is considered neutral.

**Chromium Suite Tests:** Indicators of PASS materials include significant actual acidity (TAA greater than 18 Mole H+/t) and Chromium Reducible Sulphur percentages ScR greater than 0.03%. Samples with pHKCL < 6.5 indicate that insitu conditions are already somewhat acidic, but TAA greater than 18 mole H+/t is required for this to be significant (depending on scale of the job and nature of the soil).

#### 9.2.2 Assessment Criteria

The ASSMAC (1998) action criteria for treatment of ASS based on the percentage of oxidisable sulphur or equivalent Titratable Actual Acidity (TAA) or Titratable Peroxide Acidity (TPA) for broad soil texture categories are presented in Table 6.1. When analysis results exceed the action criteria, a treatment regime and management plan for the materials is triggered. For disturbances of less than 1000 tonnes, the action criteria vary according to the texture of the material, however if more than 1000 tonnes is to be disturbed, all action criteria are the same: S% 0.03% and Acid 18 mole H<sup>+</sup>/tonne. For the purposes of this assessment the criteria applicable for disturbing more than 1000 tonnes of soil disturbed has been adopted.

Table 9.1 Action Criteria for Treatment of AASS & PASS

			O tonnes urbed	>1000 tonr	nes disturbed
Texture Range	Clay Content	Sulfur Content %	Acid Trail mole H+/tonne	Sulfur Content %	Acid Trail mole H+/tonne
Coarse (sands-gravels)	<5	0.03	18	0.03	18
Medium (sandy loam-light clay)	5-40	0.06	36	0.03	18
Fine (medium to heavy clays, silty clays)	>40	0.1	62	0.03	18

Source: Ahern et al., 1998

Note: AASS – Actual Acid Sulfate Soils

PASS - Potential Acid Sulfate Soils

#### 9.2.3 Screening Tests

The first stage consisted of the initial qualitative screening of the disturbed samples collected over every 0.5 metres or change of formation. The test is used to determine existing and potential acidity and was conducted by NG using the field pH (pH $_{\rm F}$ ) and oxidised (pH $_{\rm FOX}$ ) test method, which is a quick, qualitative assessment of the potential acidity of the soil. Field screening tests were carried out in NG laboratory using the following procedures:

- A soil sample approximately about 5g was placed in a test tube and a soil water suspension was made with 25ml of water.
- A second 5g soil sample was combined with 25ml of hydrogen peroxide buffered to pH 4.5-5.5 range with sodium hydroxide.
- pH readings of both suspensions were taken at the start and about one hour later.

Results of  $pH_F/pH_{FOX}$  screening tests are presented in Table 6.2.

It may be noted that ASSMAC Guideline indicates that pHf >4 are unlikely to be actual acid sulphate soils. However, a change of test methods subsequent to 1998 Guidelines requires the actual acidity to be assessed by titrating to pH 6.5. Therefore, many soils previously assessed to be not acid sulphate soils have actual acidity more than the intervention levels.

#### 9.2.4 Results of Laboratory Testing

Results of the laboratory tests ( $pH_{KCL}$ ) on selected sample is summarised in Table 9.2.

Table 9.2 Results of EAL Testing

Sample site	Soil Text.	Sample Depth (m)	$pH_f$	$pH_{fox}$
BH2	Fine	1.5-1.7	5.4	5.1
BH3	Fine	0.4-0.5	6.1	4.5
BH5	Fine	0.0-0.1	7.2	4.7
BH5	Fine	0.5-0.95	6.5	5.9
BH6	Fine	0.4-0.5	8.2	6.3
BH8	Fine	0.5-0.8	7.9	4.6
BH8	Fine	1.0-1.2	8.0	5.4
BH9	Fine	0.5-0.95	6.9	6.1

Based on the above test results, it is noticed that pH tests in water recorded pH>4.7 and pH tests in Hydrogen Peroxide recorded pH>3.0. Therefore, it is assessed that site soils are neither Actual Acid Sulphate Soils (AASS) nor Potential Acid Sulphate Soil (PASS).

No sample was sent to the external laboratory for TAA and  $S_{Cr}$  testing. And no acid sulphate management would be required for the proposed project.

#### 10.0 SITE CHARACTERISATION

Based on the test results for samples tested, site observations, visual assessment of soils exposed in the boreholes and the site history contained in Clearsafe Phase 1 report we assess that the risk of site contamination to be low and the site is suitable for the proposed development.

Clearsafe Phase 1 contamination report identified possible pesticides from agriculture activities, heavy metal, hydrocarbon and asbestos contamination due the unknown source of the fill. The investigation targeted all these aspects and the results indicated contamination levels below the health based guidelines.

Fill was encountered in the site at a number of boreholes. Based on the investigations carried out by NG and others it is unlikely that large volume of fill to be found in the site. However the actual extent of fill present on site could only be assessed after stripping of vegetation and topsoil. It is possible that unexpected contamination hot spots, including asbestos, could be found during construction. Such contamination could be managed during construction. We recommend that an environmental/geotechnical engineer be engaged full time during initial earthworks to identify any contamination hot spots and provide advice on remediation.

#### 11.0 WASTE DISPOSAL

In general, we consider most soils excavated to be Virgin Excavated Natural Material (VENM). This classification applies to residual soils and rock.

Fill to be excavated may need to be classified based on Excavated Natural Materials (ENM) exemption October 2012. As the physical extent of fill is not mapped accurately all fill excavated should be stockpiled in smaller stockpiles each not more than 2000t and assessed based on chemical testing.

While the fill is unlikely to be contaminated with chemicals and asbestos, it may contained process materials (concrete, bricks, ceramics etc) and foreign materials (rubber, plastic, bitumen, paper cloth etc) which may make the fill to be not ENM.

Therefore fill containing such material should be stockpiled separately from cleaner fill based on visual assessment and on the advice from a supervising environmental/geotechnical engineer. Fill assessed to be suitable based on visual assessment may be incorporated on site earthworks.

It is anticipated that there will be excess material. Residual soils or rock encountered may be disposed offsite as Virgin Excavated Natural Material (VENM).

VENM may be disposed offsite for re-use in landfill for residential/commercial developments.

#### 12.0 CONCLUSION & RECOMMENDATIONS

Based on the investigations, it is assessed that site comprises fill to a depth of about 1.7m. The analytical test results did not record any contamination higher than the NEPM Health Based Investigation Levels (HIL) for residential use with garden/accessible soil (Column 1). Therefore the risk of contamination is assessed to be low.

The proposed development includes excavation of fill and residual soils to expose rock over most of the area proposed for development. The potential for encountering contaminated hot spots, including asbestos, is assessed to be low.

If any such contamination hot spot is found during construction, they should be managed appropriately.

Based on the investigation carried out we assess that no further stage 2 contamination assessment to be required.

For and on behalf of Network Geotechnics Ptv Ltd

Reviewed By

Raj Singh BEng Civil
Geotechnical Engineer

V W de Silva MEng, SMIE Aust, CPEng, NPER Principal Geotechnical Engineer





#### **GENERAL**

Geotechnical reports present the results of investigations carried out for a specific project and usually for a specific phase of the project (e.g. preliminary design). The report may not be relevant for other phases of the project (e.g. construction), or where project details change.

#### SOIL AND ROCK DESCRIPTIONS

Soil and rock descriptions are based on AS 1726 – 1993, using visual and tactile assessment except at discrete locations where field and / or laboratory tests have been carried out. Refer to the terms and symbols sheet for definitions.

#### **GROUNDWATER**

The water levels indicated on the logs are taken at the time of measurement and depending on material permeability may not reflect the actual groundwater level at those specific locations. Also, groundwater levels can vary with time due to seasonal or tidal fluctuations and construction activities.

#### INTERPRETATION OF RESULTS

The discussion and recommendations in the accompanying report are based on extrapolation / interpolation from data obtained at discrete locations. The actual interface between the materials may be far more gradual or abrupt than indicated. Also, actual conditions in areas not sampled may differ from those predicted.

#### **CHANGE IN CONDITIONS**

Subsurface conditions can change with time and can vary between test locations. Construction operations at or adjacent to the site and natural events such as floods, earthquakes or groundwater fluctuations can also affect subsurface conditions.

#### **REPRODUCTION OF REPORTS**

This report is the subject of copyright and shall not be reproduced either totally or in part without the express permission of this firm. Where information from the accompanying report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimise the likelihood of misinterpretation from logs.


#### **FURTHER ADVICE**

Network Geotechnics would be pleased to further discuss how any of the above issues could affect your specific project. We would also be pleased to provide further advice or assistance including:

- assessment of suitability of designs and construction techniques;
- contract documentation and specification;
- construction control testing (earthworks, pavement materials, concrete);
- construction advice (foundation assessments, excavation support).

### APPENDIX A

Borehole Logs (BH1 to BH22) Terms & Symbols



BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK GEOTECHNICS PTY LTD.GDT 3/1/14

## **BOREHOLE LOG**

Logged:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A

Hole No: **BH01**Sheet: PAGE 1 / 1

LT


Client: TCG PLANNING Started: 28/11/13

Project: LIFE CITY WOLLONONG Finished: 28/11/13

GPS 301549E 6183771N Checked: VDS

Equipment Type: MOBILE DRILL B80 RL Surface: 46.7

	reho	ole Dia	met	ter: 100	mm (I.I	D.)	Inclination: -90 deg Bearing:	Datum	:	A.H.D	
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture condition	Consistency/ relative density	comments  notes, structure, and additional observations	
	None encountered	D 2, 3, 4	_			CH	Silty CLAY: high plasticity, dark brown, with roots and trace of fine to medium grained ironstone and sandstone gravel	>PI	-	FILL, GRASS COVER	
		2, 3, 4 N=7 N 7,4/70mm,		1.0 1.0 		CH	Silty CLAY: high plasticity, dark brown, with root fibres	>PI	St	COLLUVIAL HP READING: 150, 170  "V" BIT REFUSED AT 1.8m DEPTH	_
ADT		,4//Umm,				-	SANDSTONE : fine to medium grained, orange brown, red brown and light grey, with occassional iron indurated band, extremely low strength	xw		VL TC BIT RESISTANCE  -	
		D		4.0 		-	As above, but low strength	DW	L	L 'TC' BIT RESISTANCE	_
				5.0			BH01 Terminated at 4.5 m			'TC' BIT REFUSAL	



## **BOREHOLE LOG**

Logged:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310


Job No: G09/1100 A BH02 Hole No: Sheet: PAGE 1 / 1

LT

Started: 28/11/13

LIFE CITY WOLLONONG 28/11/13 Finished:

	, aci	on:					ierkeley 183722N	Logge		LI
	.:	t T						Check		VDS
		ment T					ILE DRILL B80  Inclination: -90 deg Bearing:	RL Sui		45.4 A.H.D
501	еп	Die Dia	mei	.er. 100		D.)		Datum	· 	A.H.D
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture	Consistency/ relative density	notes, structure, and additional observations
	ered	D			7/1 1/N	СН	Silty CLAY : high plasticity, dark brown, with roots	>PI	-	TOPSOIL, GRASS COVER
	None encountered			_	7 71					
	None	1, 2, 4 N=6		1.0		СН	Silty CLAY: high plasticity, dark brown and orange brown	>PI	St/VSt	COLLUVIAL HP READING: 170, 220, 230
		5, 10, 10 N=20		_		CL	Sandy Silty CLAY: low to medium plasticity, fine grained, orange brown, red brown and dark brown	<pi< td=""><td>VSt</td><td>HP READING: 250, 300</td></pi<>	VSt	HP READING: 250, 300
ADI				2.0			SOWII			
,				_		-	SANDSTONE : fine to coarse grained, orange brown and red brown, extremely low strength	XW	-	'V' BIT REFUSAL  VERY LOW 'TC' BIT RESISTANCE
				3.0		-	As above, but with medium strength iron indurated band			VERY LOW 'TC' BIT RESISTANCE
		D		_						
				_						
		D		4.0 		-	As above, coarse grained			
			-	_			BH02 Terminated at 4.4 m			'TC' BIT REFUSAL
				5.0						
				_						
				_						
				6.0 						
				_						



BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK GEOTECHNICS PTY LTD.GDT 3/1/14

## **BOREHOLE LOG**

Logged:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A

Hole No: BH03

Sheet: PAGE 1 / 3

LT

Plient: TCG PLANNING Started: 21/11/13


Project: LIFE CITY WOLLONONG Finished: 21/11/13

GPS 301455E 6183661N Checked: VDS

Equipment Type: MOBILE DRILL B80 RL Surface: 41.6

Borehole Diameter: 100mm (I.D.) Inclination: -90 deg Bearing: Datum: A.H.D.

		S				_	Material Description		· 5:	comments
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol		Moisture	Consistency/ relative density	notes, structure,
_		es	u d			ň			C	and additional observations
	untered	D		_	\( \bar{7} \cdot	СН	Silty CLAY: high plasticity, dark brown, with roots	>PI	-	TOPSOIL, GRASS COVER
	None encountered	D		_		СН	Silty CLAY: high plasticity, grey and dark brown, with roots	>PI	F-St	COLLUVIAL HP READING: 90, 110
	ž	1, 2, 4 N=6		_						- THE READING. 30, 110
				1.0		СН	As above, but brown, with root fibres		St-VSt	
				_						
		2, 3, 5 N=8		_						HP READING: 190, 210,220
				2.0						_
ADT				_						_
				_						_
		N>23 15,		3.0	(/X//	-	Latite, coarse, light brown and orange brown, with medium to high strength red brown iron indurated band, extremely low strength	XW		VERY LOW 'V' BIT RESISTANCE
		8/50mm		_						'V' BIT REFUSAL VERY LOW 'TC' BIT
<u>†</u>				_						RESISTANCE
				4.0						A 50mm PVC INSTALLED TO THE BOTTOM, MACHINE SLOTTED BETWEEN 4.47m TO
										7.47m, 2mm FILTER —— SAND BACKFILLED TO 0.7m, BENTONITE — SEALED BETWEEN 0.2m
				_			BH03 continued from 4.49 m on sheet 2 / 3			TO 0.7m. MONUMENT CONCRETED AT SURFACE
S C C C C C C C C C C C C C C C C C C C				_						
A CONTRACTOR				5.0						



BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK GEOTECHNICS PTY LTD.GDT 3/1/14

## **BOREHOLE LOG**

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A

Hole No: BH04

Sheet: PAGE 1 / 3


Client: TCG PLANNING Started: 21/11/13

Project: LIFE CITY WOLLONONG Finished: 22/11/13

Location: Warwick Street, Berkeley Logged: LT

GPS 301395E 6183588N Checked: VDS

Ec	uipr	nent T	уре:		ı	МОВ	ILE DRILL B80	RL Sur	face:	47.4
Вс	reh	ole Dia	met	er: 100	mm (I.I	D.)	Inclination: -90 deg Bearing:	Datum:	:	A.H.D
		ş				-	Material Description		· t	comments
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol		Moisture condition	Consistency/ relative density	notes, structure, and additional observations
	ered	D			7/1/X	СН	Silty CLAY: high plasticity, dark brown, with fine to medium grained ironstone gravel and roots	>PI	-	TOPSOIL, GRASS COVER
	None encountered			_		CH	Silty CLAY: high plasticity, dark brown and orange brown, trace of roots and fine grained gravel	>PI	St	COLLUVIAL, HP READING: 150, 170, 180
	_	1, 2, 2 N=4	-	1.0						_
		D		_		CH	As above, but orange brown, without roots			_
	1	N=16 0,9,7/50m	m			SC	Sandy CLAY: medium plasticity, fine to medium grained, orange brown, red brown and dark brown	<pi< td=""><td></td><td>HP READING: 160, 170</td></pi<>		HP READING: 160, 170
ADT			-	_						_
			-	_						
				3.0		-	Latite, coarse grained, orange brown and red brown, with clay band, extremely low strength	XW		V' BIT REFUSAL VERY LOW 'TC' BIT RESISTANCE
† 5			-	_						_
			-	4.0 _				DW to XW	L-VL	VERY LOW TO LOW 'TC' BIT RESISTANCE
				_			BH04 continued from 4.7 m on sheet 2 / 3			_
				5.0 						
				_						_
				6.0						_
מאבו ומרך בס				_						_



# **BOREHOLE LOG**

Checked:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A

Hole No: BH05

Sheet: PAGE 1 / 3

VDS


Client: TCG PLANNING Started: 22/11/13

 Project:
 LIFE CITY WOLLONONG
 Finished:
 22/11/13

 Location:
 Warwick Street, Berkeley
 Logged:
 LT

Faurinment Type: MORII F DRII L R80 RI Surface: 51.0

Ξqι	uipn	nent T	ype	:		MOB	ILE DRILL B80	RL Sur	face:	51.0	
3or	ehc	ole Dia	me	ter: 100	mm (l.l	D.)	Inclination: -90 deg Bearing:	Datum	:	A.H.D	
metnod	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture	Consistency/ relative density	notes, structure, and additional observations	
	None encountered	D	-	_	71 1/2   7/1 1/2   7	СН	Silty CLAY : high plasticity, dark brown, with roots	>PI	-	TOPSOIL, GRASS COVER	
	None	2, 3, 4 N=7	-			CH	Silty CLAY: high plasticity, brown, trace of root fibres and fine grained ironstone gravel	>PI	VSt	COLLUVIAL HP READING: 250, 270, 290	
	_					СН	Silty CLAY: high plasticity, grey brown, trace of root fibres and fine grained ironstone gravel	<pi< td=""><td></td><td>HP READING: 300, 320,</td></pi<>		HP READING: 300, 320,	
ADI	-	3, 6, 9 N=15	-	2.0						370	
				_		СН	Silty CLAY: high plasticity, grey to dark brown, orange brown and red brown, fine to medium ironstone gravel				
	4,8	N>18 3,10/100m	nm	3.0		-	SANDSTONE : fine to medium grained, orange brown, extremely low strength	VIA		HP READING: 370, 380, 380	
				_				XW		RESISTANCE 'V' BIT REFUSAL	
				4.0		-	Latite: dark grey	SW	Н	MEDIUM 'TC' BIT RESISTANCE	
						-	Latite, coarse grained, orange brown with iron indurated band BH05 continued from 4.15 m on sheet 2 / 3	HW	L	LOW 'TC' BIT RESISTANCE	
				5.0							
				_							
				6.0							
				_							



BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK GEOTECHNICS PTY LTD.GDT 3/1/14

## **BOREHOLE LOG**

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A

Hole No: BH06

Sheet: PAGE 1 / 2


Client: TCG PLANNING Started: 21/11/13

Project: LIFE CITY WOLLONONG Finished: 21/11/13

Location: Warwick Street, Berkeley Logged: LT

GPS 301512E 6183598N Checked: VDS

E	uipr	nent T	уре:			МОВ	ILE DRILL B80	RL Sur	face:	51.5
В	reh	ole Dia	met	er: 100	).l) mm	D.)	Inclination: -90 deg Bearing:	Datum		A.H.D
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture condition	Consistency/ relative density	notes, structure, and additional observations
	ered	D			7/1 1/N	СН	Silty CLAY: high plasticity, dark brown, with roots and trace of fine to medium grained ironstone gravel	>PI	-	TOPSOIL, GRASS COVER
ADT	None encountered	1, 2, 3 N=5				CH	Silty CLAY: high plasticity, grey and dark brown, trace of fine to medium grained ironstone gravel	>PI	St	COLLUVIAL HP READING: 110, 120
			-	_		-	SANDSTONE : fine to medium grained, brown, extremely low strength	XW		VERY LOW 'V' BIT RESISTANCE
		D		_ _ _				DW	VL	'V' BIT REFUSAL  LOW 'TC' BIT  RESISTANCE, A 50mm PVC INSTALLED TO THE BOTTOM, MACHINE SLOTTED
ORETICE LOG GOS-1100 LOGGSGTS INELWORN GEOTECHNICS THE LIDGEL S/1714							BH06 continued from 1.95 m on sheet 2 / 2			BETWEEN 3m TO 4.74m, 2mm FILTER SAND BACKFILLED TO 0.7m, BENTONITE SEALED BETWEEN 0.2m TO 0.7m. MONUMENT CONCRETED AT SURFACE



## **BOREHOLE LOG**


ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A Hole No: BH07 Sheet: PAGE 1 / 1

Started: 21/11/13 Finished: 21/11/13

LT Logged:

				GPS 30	01609	E 61	183584N	Checke	ed:	VDS
Equ	uipr	nent T	уре:		ı	МОВ	ILE DRILL B80	RL Sur	face:	67.1
301	reho	ole Dia	met	er: 100	).l) mm	D.)	Inclination: -90 deg Bearing:	Datum	:	A.H.D
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture	Consistency/ relative density	comments  notes, structure, and additional observations
	None encountered						Silty CLAY : high plasticity, orange brown	>PI		RESIDUAL
	None 6	4, 3, 7 N=10	-			СН	As above, but with fine to medium grained very low strength sandstone grave	<pi< td=""><td>St</td><td></td></pi<>	St	
		3, 4, 7 N=11	-							
ADI			-	- - -						
		N=R 6 5,-	,	3.0		-	SANDSTONE : fine to medium grained, orange brown	DW	VL	'V' BIT REFUSAL  VERY LOW 'TC' BIT RESISTANCE
		D		4.0 			BH07 Terminated at 4.4 m			'TC' BIT REFUSAL
			-	5.0						
			-							
				_						



## **BOREHOLE LOG**

Logged:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A

Hole No: BH08

Sheet: PAGE 1 / 1

LT


TCG PLANNING Started: 28/11/13

Project: LIFE CITY WOLLONONG Finished: 28/11/13

GPS 301461E 6183614N Checked: VDS

Equipment Type: MOBILE DRILL B80 RL Surface: 43.3

Boı	reh	ole Dia	me	ter: 100	Omm (I.I	D.)	Inclination: -90 deg Bearing:	Datum:		A.H.D	
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture	Consistency/ relative density	comments  notes, structure, and additional observations	
	ntered	0		_	1 7 7 1 1 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1	СН	Silty CLAY high plasticity, dark grey and dark brown, with fine grained sand, fine grained ironstone gravel and roots	>PI	-	TOPSOIL, GRASS COVER	_
	None encountered	1, 4, 4 N=8		 1.0			Silty CLAY high plasticity, dark brown and dark grey, with root fibres	>PI	St	COLLUVIAL HP READING: 170, 180, 190	
	Nor	2, 4, 7 N=11		   2.0		CH	As above, but brown and grey, trace of fine grained ironstone gravel		VSt	HP READING: 270, 290, 300	
						-	Latite, coarse grained, orange brown and dark grey, with clay band, extremely low strength	xw		VERY LOW 'V' BIT RESISTANCE	_
ADT		N>18 6, 18,-		3.0   				XW/DW		'V' BIT REFUSAL VERY LOW 'TC' BIT RESISTANCE	_
				4.0  						RESISTANCE	
				5.0 5.0 							
				 6.0 							
				8.0			BH08 Terminated at 7 m			A 50mm PVC INSTALLED TO THE BOTTOM, MACHINE SLOTTED BETWEEN 4m TO 7m, 2mm FILTER SAND BACKFILLED TO 0.7m, BENTONITE SEALED BETWEEN 0.2m TO 0.7m. MONUMENT CONCRETED AT	
				9.0 						CONCRETED AT SURFACE	
				10.0 							
				11.0 10							
				  <u>1</u> 3.0							



As above, but orange brown

BH09 Terminated at 5.1 m

BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK GEOTECHNICS PTY LTD.GDT 3/1/14

D

5.0

6.0

### **BOREHOLE LOG** Job No: G09/1100 A BH09 Hole No: Sheet: PAGE 1 / 1 Started: 28/11/13 Finished: 28/11/13 LT Logged: VDS Checked: RL Surface: 46.4 Datum: A.H.D Bearing: comments Moisture condition notes, structure, and additional observations TOPSOIL, GRASS COVER COLLUVIAL >PI St 'V' BIT REFUSAL VERY LOW 'TC' BIT XW RESISTANCE

MEDIUM 'TC' BIT RESISTANCE


HIGH 'TC' BIT RESISTANCE

'TC' BIT REFUSAL

DW


SW

Н



BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK GEOTECHNICS PTY LTD.GDT 3/1/14

### **BOREHOLE LOG** ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310 Job No: G09/1100 A Hole No: BH10 PAGE 1 / 1 Sheet: Started: 28/11/13 Finished: 28/11/13 RS Logged: Checked: VDS RL Surface: 45.8 Datum: A.H.D Bearing: comments notes, structure, and additional observations FILL, GRASS COVER




						02 84380310		noie iv		<b>ВП</b> ТТ
								Sheet:		PAGE 1 / 1
lient:	<u>:                                    </u>		TCG PI	ANN	ING			Started	d:	28/11/13
rojec	ct:		LIFE C	ITY W	/OLL	ONONG		Finishe	ed:	28/11/13
ocati			Warwic	k Stre	eet, E	Berkeley		Logge	d:	RS
						183814N		Check	ed:	VDS
ימווח	ment T	Tyne			HANI	D AUGER		RL Su		46.9
	ole Dia					Inclination: -90 deg	Bearing:	Datum		A.H.D
OLELL		11110	.ei. 100	(i	J.,		Dearing.	Datam		A.H.D
water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description		Moisture	Consistency/ relative density	comments notes, structure,
	ιχ								_ O <u>e</u>	and additional observations
ing					ML	Sandy SILT low plasticity, fine grained, dark grey, with root fibres		w	_	TOPSOIL
augerin						SANDSTONE extremely weathered, brown			-	ROCK
ring a			_			BH11 Terminated at 0.2 m				
ed du			_							
unter										
enco			1.0							
None encountered during augering			1.0							
			_							
			_							
			_							
			_							
			2.0							
			_							
			_							
			_							
			3.0							
			_							
			_							
			_							
			_							
			4.0							
			·							
			_							
			_							
			_							
			5.0							
			_							
			_							
			- 6.0							
			6.0							
			_							
			_							


Job No:

Hole No:

G09/1100 A BH11




6.0



BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK GEOTECHNICS PTY LTD.GDT 3/1/14

5.0

# **BOREHOLE LOG** G09/1100 A Job No: Hole No: BH13 PAGE 1 / 1 Sheet: Started: 28/11/13 Finished: 28/11/13 RS Logged: Checked: VDS RL Surface: 42.2 Datum: A.H.D comments Consistency/ relative density notes, structure, and additional observations >Wp FILL





ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A BH14 Hole No: Sheet: PAGE 1 / 1

Started: 28/11/13 Finished: 28/11/13

Location: Warwick Street, Berkeley  GPS 301459E 6183731N  Logged: RS  Checked: V/DS										
<b>Г</b> а.	iinn	nont T					D AUGER	Check		VDS 38.9
		nent T		ter: <sup>100</sup>			Inclination: -90 deg Bearing:	Datum		A.H.D
method	water	samples, tests etc	DCP Blows per 150 mm		graphic log	USCS symbol	Material Description	Moisture condition	Consistency/ relative density	comments  notes, structure, and additional observations
¥	untered	D		_		CI/CH	Sandy CLAY medium to high plasticity, dark grey, sand fine to medium grained, some gravel	≥Wp	-	FILL
	None Encountered						BH14 Terminated at 0.3 m			
				2.0 						
				3.0						
				4.0						
				5.0						
				_						
				6.0 						





Logged:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310


Job No: G09/1100 A BH16 Hole No: Sheet: PAGE 1 / 1

RS

Started: 28/11/13 Finished:


28/11/13

	S 301420E 6			Logge		
		D AUGER		Check		VDS
Equipment Type:		RL Sur		37.7		
Borehole Diameter:	100mm (I.D.)	Inclination: -90 deg	Bearing:	Datum	:	A.H.D
water samples, tests etc DCP Blows per 150 mm	graphic log USCS symbol	Material Description		Moisture	Consistency/ relative density	notes, structure, and additional observations
None Encountered		Silty SAND fine to medium grained, brown, traces of grass rootlets Silty CLAY medium to high plasticity, grey		- M >Wp		TOPSOIL RESIDUAL
, noou	<u> </u>	BH16 Terminated at 0.3 m		1		
None E						
	.0					
2	.0					
	.0					
4	.0					
5.	.0					
6.	0.0					



# **BOREHOLE LOG** Job No: G09/1100 A Hole No: BH17 PAGE 1 / 1 Sheet: Started: 28/11/13 Finished: 28/11/13 RS Logged: Checked: VDS RL Surface: 42.3 Datum: A.H.D comments Consistency/ relative density notes, structure, and additional observations <Wp TOPSOIL RESIDUAL

5.0



Started:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A


Hole No: BH18

Sheet: PAGE 1 / 1

28/11/13

Client: TCG PLANNING

	4	: LIFE CITY WOLLONONG								Finished: 28/11/13			
⊃roj													
_006	atio	on:					Berkeley		Logged	d:	RS		
	GPS 301451E 6183679N								Checked: VDS				
qu	ipm	nent 7	Гуре	:		HAN	D AUGER		RL Sur	face:	41.3		
				ter: 100	Omm (I.	D.)	Inclination: -90 deg	Bearing:	Datum	:	A.H.D		
							Material Description						
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	macrial accomption		Moisture	Consistency/ relative density	notes, structure, and additional observations		
	g e				<u> </u>		Sandy SILT low plasticity, dark grey, some grass rootlets		<wp,< td=""><td></td><td>TOPSOIL</td></wp,<>		TOPSOIL		
₹ E	nute			_		СН	Silty CLAY high plasticity, dark grey		≥Wp	-	RESIDUAL		
	None Encountered						BH18 Terminated at 0.3 m						
				5.0									
				6.0									




ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A BH19 Hole No: Sheet: PAGE 1 / 1 Started: 28/11/13

Finished: 28/11/13

FIC	yec	ι.		LIFE	III V	VOLL	UNUNG	Finishe	au.	28/11/13
Loc	catio	on:					erkeley	Logge	d:	RS
	GPS 301553E 6183707N									VDS
Equipment Type: HAND AUGER									face:	52.4
				er: 100			Inclination: -90 deg Bearing:	Datum		A.H.D
БОІ	CII			.ei. 100	T	J.,		Datum		Allin
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture	Consistency/ relative density	notes, structure, and additional observations
∢	pere	D			7/1/8	CI	Sandy CLAY medium to high plasticity, grey, sand fine to medium grained	<wp< td=""><td>-</td><td>TOPSOIL</td></wp<>	-	TOPSOIL
H	onnte				1, ,1,		SANDSTONE extremely weathered, brown			ROCK
	None Encountered						BH19 Terminated at 0.3 m			
				5.0						
				6.0 						




ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A BH20 Hole No: Sheet: PAGE 1 / 1

Started: 28/11/13

Project: LIFE CITY WOLLONONG					VOLL	ONONG	Finishe	ed:	28/11/13		
Location: Warwick Street, Berkeley								Logge	d:	RS	
	GPS 301538E 6183661N								Checked: VDS		
Ξqι	uipr	nent T	уре	•		HAN	D AUGER	RL Sui	face:	52.5	
Зоі	reho	ole Dia	amet	er: 100	Omm (I.I	D.)	Inclination: -90 deg Bearing:	Datum	:	A.H.D	
method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol	Material Description	Moisture condition	Consistency/ relative density	notes, structure, and additional observations	
4	ered	D			<u>z<sub>1</sub> y</u> x	CI	Sandy CLAY medium to high plasticity, dark grey, sand fine to medium grained	<wp< td=""><td>-</td><td>TOPSOIL</td></wp<>	-	TOPSOIL	
¥	onnte				1, 11	_	SANDSTONE extremely weathered, brown	<del> </del>		ROCK	
	None Encountered						BH20 Terminated at 0.3 m			-	
				_							
				_							
				2.0						-	
				_							
				_							
				_							
				_							
				3.0						-	
				_							
				_							
				_							
				_							
				4.0							
				5.0							
				_							
				_							
				_							
				_							
				6.0							
				_							
				_							




ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A BH21 Hole No: Sheet: PAGE 1 / 1 Started: 28/11/13

LIFE CITY WOLLONONG 28/11/13

Project: LIFE CITY WOLLONONG	Finishe	ed:	28/11/13
Location: Warwick Street, Berkeley GPS 301538E 6183619N	Logged		RS
	Checke		VDS
Equipment Type: HAND AUGER	RL Sur		53.5
Borehole Diameter: 100mm (I.D.) Inclination: -90 deg Bearing:	Datum	:	A.H.D
method water samples, tests etc etc Etc BOCP Blows graphic log USCS symbol USCS symbol	Moisture	Consistency/ relative density	comments  notes, structure, and additional observations
ML Sandy SILT low plasticity, dark grey, sand fine to medium grained, some gravel/ironstone	<wp< td=""><td></td><td>TOPSOIL</td></wp<>		TOPSOIL
- SANDSTONE extremely weathered, brown			ROCK
No.   Sandy Sk.T low plaskity, dark grey, sand fine to medium grained, some grave/irronstone			



Datum:

ACN 069 211 561 Unit 12/9-15 Gundah Road Mt Kuring-Gai NSW 2080 02 84380300 02 84380310

Job No: G09/1100 A Hole No: BH22 Sheet: PAGE 1 / 1

A.H.D

Started: 28/11/13 Finished: 28/11/13

Logged: LT

> VDS Checked:

RL Surface: 65.3

Bearing: Material Description comments 

	method	water	samples, tests etc	DCP Blows per 150 mm	depth (m)	graphic log	USCS symbol		Moisture	Consistency/ relative density	notes, structure, and additional observations
	¥	None encountered	D			17 711 711×	CL	Silty CLAY : medium plasticity, dark brown, with roots	>PI	-	TOPSOIL, GRASS COVER
	_	noou					CH	Silty CLAY: high plasticity, orange brown, with fine to medium grained sandstone gravel	<pi< td=""><td>St</td><td>RESIDUAL</td></pi<>	St	RESIDUAL
		ne er						BH22 Terminated at 0.4 m			
		Š			_						HAND AUGER REDFUSAL —
					_						_
					1.0						
					_						
					_						_
					_						_
					2.0						
					_						
					_						
					_						_
					_						_
					3.0						
					_						
					_						
3/1/1					_						
TQ:					_						_
GEOTECHNICS PTY LTD.GDT 3/1/14					4.0						
ΣĮ					_						_
ICS F					_						
CF											
0.0					_						
					_						
WOR					5.0						
Ä					_						_
GPJ					_						
JGS.											
00 FC					_						
BOREHOLE LOG G09-1100 LOGS.GPJ NETWORK					_						
3 60					6.0						
ICO					_						_
H H H											_
ORE											
ω [				1		1					



# **TERMS AND SYMBOLS**

SOLL DE	SCRIPTIONS			FZ	Fractured z	one st	ŧ	Stepped
JOIL DE	SCRIP HONS			SZ	Shear zone			Irregular
Moisture	Condition			VN	Vein			Ü
	D	Dry			0 11	_		
	M W	Moist			or Coating		oughne	
	vv Wp	Wet Plastic Limit		Cn Cl	Clean Clay		ol Ik	Polished Slickensided
	WI	Liquid Limit		Ca	Calcite		mo	Smooth
	MC	Moisture Content		Fe	Iron oxide		ou	Rough
		moloculo comoni		Mi	Micaceous		ro	Very rough
Consiste	ncy		Qu (kPa)	Qz	Quartz			. ,
	VS	Very Soft	< 25					
	S	Soft	25 – 50	EXCA	VATION/DRIL	LING ME	THOD 8	& CASING
	F	Firm	50 – 100					
	St	Stiff	100 – 200		BH			tor bucket
	VSt H	Very Stiff Hard	200 – 400		NE HE	Natural e		
	н Fb	Friable	>400		AS	Hand exc Auger Scr		
	10	THADIC			AD	Auger Dri		
Density I	Index		I <sub>D</sub> (%)		R	Roller/Tri		
Density i	VL	Very Loose	< 15		W	Washbore		
	L	Loose	15 – 35		* de	notes bit	shown l	by suffix
	MD	Medium Dense	35 – 65		В	Blank Bit		,
	D	Dense	65 – 85		V	"V" Shape	ed Bit	
	VD	Very Dense	> 85		T	Tungsten	Carbid	e Bit
					LB			Tube Drilling
					MC			Tube Drilling
					DT	Dual Push	n Tube I	Drilling
ROCK D	ESCRIPTIONS	3		1	NMLC	NMLC Cor	e Drillin	ng
				N	Q/HQ	Wireline (	Core Dr	illing
Weather	3							
	Rs	Residual Soil			С	Casing		
	XW	Extremely Weath			М	Mud		
	HW	Highly Weathered		CANAD	L FC /TFCTC			
	MW DW	Moderately Weat Distinctly Weather		SAIVIP	LES/TESTS			
	SW	Slightly Weather			В	Bulk sam	nlo	
	FR	Fresh	<del>su</del>		D	Disturbed		۵
		ooth HW & MW)			U50	Thin-wall		
	(211 0010.02	,			000	(50mm d		
Strength			Is (50) MPa		PP			eter (kPa)
3	EL	Extremely Low	< 0.03		N*	SPT (blow		
	VL	Very Low	0.03 - 0.1			*denotes	sampl	e taken
	L	Low	0.1 - 0.3		Nc	SPT with		one
	M	Medium	0.3 – 1		R	SPT refus	al	
	H	High	1 – 3					
	VH EH	Very High	3 – 10	VANE	SHEAR TESTS	•		
	ЕП	Extremely High	> 10					
Structure	Э		Spacing		Su	Vane shea	ar strer	ngth
	Thinly Lamina	ated	< 6mm			Peak/resi	dual (kl	Pa) and
	Laminated		6 – 20mm			Vane size	(mm)	
	Very thinly be		20 – 60mm					
	Thinly bedded		60 – 200mm	WATE	R MEASUREM			
	Medium bedd	led	0.2 – 0.6m		lacktriangle	Water lev	el at th	e time of
	Thislaha badda	ad .	0.4 2.0m		_	drilling		
	Thickly bedde Very thickly be		0.6 – 2.0m > 2.0m		$\nabla$	Water lev	el afte	r drillina
					<del></del>			·
NOTE:		k descriptions are	based on AS 1726	4	<b>\</b> -	Water inf	low	
	- 1993			_		Water out	tflow	
					-	vater ou	LITOVV	
Natural F	ractures				TUBE DRILLI	NG		_
_		<u>.</u> .			e of Resistance			Factor
Type	1.1.1	Shape	Discour		rcussion			0
JT	Joint	pl	Planar		ush with percus			1
BP SM	Bedding plan		Curved		m push with pe			2
SM	Seam	un	Undulose		oush with percu slow – nearin			3 4
				refus		_		÷

# APPENDIX B

Laboratory Contamination Test Results

Network Geotechnics G09/1100-B



# **CERTIFICATE OF ANALYSIS**

Work Order : **ES1326530** Page : 1 of 7

Client : NETWORK GEOTECHNICS PTY LTD Laboratory : Environmental Division Sydney

Contact : LONG TSANG Contact : Client Services

Address : UNIT 1, 140 INDUSTRIAL ROAD Address : 277-289 Woodpark Road Smithfield NSW Australia 2164

OAK FLATS NSW, AUSTRALIA 2529

 E-mail
 : ltsang@netgeo.com.au
 E-mail
 : sydney@alsglobal.com

 Telephone
 : +61 02 4257 5548
 Telephone
 : +61-2-8784 8555

 Facsimile
 : +61 02 4257 4463
 Facsimile
 : +61-2-8784 8500

Project : LIFE OF CITY QC Level : NEPM 2013 Schedule B(3) and ALS QCS3 requirement

Order number : GO9/1100

 C-O-C number
 : -- Date Samples Received
 : 04-DEC-2013

 Sampler
 : LT
 Issue Date
 : 13-DEC-2013

Site : ----

Quote number SY/455/13 No. of samples received : 24

Quote number SY/455/13 No. of samples analysed 4

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. All pages of this report have been checked and approved for release.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results
- Surrogate Control Limits



NATA Accredited Laboratory 825

Accredited for compliance with ISO/IEC 17025.

Signatories

This document has been electronically signed by the authorized signatories indicated below. Electronic signing has been carried out in compliance with procedures specified in 21 CFR Part 11.

 Signatories
 Position
 Accreditation Category

 Celine Conceicao
 Senior Spectroscopist
 Sydney Inorganics

Pabi Subba Senior Organic Chemist Sydney Organics

Address 277-289 Woodpark Road Smithfield NSW Australia 2164 | PHONE +61-2-8784 8555 | Facsimile +61-2-8784 8500 |
Environmental Division Sydney ABN 84 009 936 029 Part of the ALS Group An ALS Limited Company



Page : 2 of 7 Work Order : ES1326530

Client : NETWORK GEOTECHNICS PTY LTD

Project : LIFE OF CITY



#### **General Comments**

The analytical procedures used by the Environmental Division have been developed from established internationally recognized procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are employed in the absence of documented standards or by client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Key: CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.

LOR = Limit of reporting

^ = This result is computed from individual analyte detections at or above the level of reporting

ALS is not NATA accredited for the analysis of Bifenthrin in soils when performed under ALS Method EP068D

Page : 3 of 7 Work Order : ES1326530

Client : NETWORK GEOTECHNICS PTY LTD

Project · LIFE OF CITY





Page : 4 of 7 ES1326530 Work Order

: NETWORK GEOTECHNICS PTY LTD Client

LIFE OF CITY Project




	CI	ient sampli	ng date / time	28-NOV-2013 15:00	22-NOV-2013 15:00	21-NOV-2013 15:00	 
Compound	CAS Number	LOR	Unit	ES1326530-021	ES1326530-022	ES1326530-023	 
EP068A: Organochlorine Pestic	ides (OC) - Continued						
Endosulfan sulfate	1031-07-8	0.05	mg/kg		<0.05	<0.05	 
4.4`-DDT	50-29-3	0.2	mg/kg		<0.2	<0.2	 
Endrin ketone	53494-70-5	0.05	mg/kg		<0.05	<0.05	 
Methoxychlor	72-43-5	0.2	mg/kg		<0.2	<0.2	 
Sum of Aldrin + Dieldrin	309-00-2/60-57-1	0.05	mg/kg		<0.05	<0.05	 
Sum of DDD + DDE + DDT		0.05	mg/kg		<0.05	<0.05	 
EP068B: Organophosphorus Pe	esticides (OP)						
Dichlorvos	62-73-7	0.05	mg/kg		<0.05	<0.05	 
Demeton-S-methyl	919-86-8	0.05	mg/kg		<0.05	<0.05	 
Monocrotophos	6923-22-4	0.2	mg/kg		<0.2	<0.2	 
Dimethoate	60-51-5	0.05	mg/kg		<0.05	<0.05	 
Diazinon	333-41-5	0.05	mg/kg		<0.05	<0.05	 
Chlorpyrifos-methyl	5598-13-0	0.05	mg/kg		<0.05	<0.05	 
Parathion-methyl	298-00-0	0.2	mg/kg		<0.2	<0.2	 
Malathion	121-75-5	0.05	mg/kg		<0.05	<0.05	 
Fenthion	55-38-9	0.05	mg/kg		<0.05	<0.05	 
Chlorpyrifos	2921-88-2	0.05	mg/kg		<0.05	<0.05	 
Parathion	56-38-2	0.2	mg/kg		<0.2	<0.2	 
Pirimphos-ethyl	23505-41-1	0.05	mg/kg		<0.05	<0.05	 
Chlorfenvinphos	470-90-6	0.05	mg/kg		<0.05	<0.05	 
Bromophos-ethyl	4824-78-6	0.05	mg/kg		<0.05	<0.05	 
Fenamiphos	22224-92-6	0.05	mg/kg		<0.05	<0.05	 
Prothiofos	34643-46-4	0.05	mg/kg		<0.05	<0.05	 
Ethion	563-12-2	0.05	mg/kg		<0.05	<0.05	 
Carbophenothion	786-19-6	0.05	mg/kg		<0.05	<0.05	 
Azinphos Methyl	86-50-0	0.05	mg/kg		<0.05	<0.05	 
EP066S: PCB Surrogate							
Decachlorobiphenyl	2051-24-3	0.1	%		60.7	60.9	 
EP068S: Organochlorine Pestici	ide Surrogate						
Dibromo-DDE	21655-73-2	0.1	%		83.0	85.6	 
EP068T: Organophosphorus Pe	sticide Surrogate						
DEF	78-48-8	0.1	%		96.1	79.8	 
					1	1	

Page : 5 of 7
Work Order : ES1326530

Client : NETWORK GEOTECHNICS PTY LTD

Project : LIFE OF CITY






Page : 6 of 7 Work Order : ES1326530

Client : NETWORK GEOTECHNICS PTY LTD

Project : LIFE OF CITY





Page : 7 of 7 Work Order : ES1326530

Client : NETWORK GEOTECHNICS PTY LTD

Project : LIFE OF CITY

# **Surrogate Control Limits**

Sub-Matrix: COMPOSITE	Recovery Limits (%)			
Compound	CAS Number	Low	High	
EP066S: PCB Surrogate				
Decachlorobiphenyl	2051-24-3	39	149	
EP068S: Organochlorine Pesticide Surrogate				
Dibromo-DDE	21655-73-2	49	147	
EP068T: Organophosphorus Pesticide Surrogat	е			
DEF	78-48-8	35	143	

Sub-Matrix: <b>SOIL</b>		Recovery	Limits (%)
Compound	CAS Number	Low	High
EP075(SIM)S: Phenolic Compound	Surrogates		
Phenol-d6	13127-88-3	63	123
2-Chlorophenol-D4	93951-73-6	66	122
2.4.6-Tribromophenol	118-79-6	40	138
EP075(SIM)T: PAH Surrogates			
2-Fluorobiphenyl	321-60-8	70	122
Anthracene-d10	1719-06-8	66	128
4-Terphenyl-d14	1718-51-0	65	129
EP080S: TPH(V)/BTEX Surrogates			
1.2-Dichloroethane-D4	17060-07-0	72.8	133.2
Toluene-D8	2037-26-5	73.9	132.1
4-Bromofluorobenzene	460-00-4	71.6	130.0





# **CERTIFICATE OF ANALYSIS**

Work Order : ES1326278 Page : 1 of 6

Client : NETWORK GEOTECHNICS PTY LTD Laboratory : Environmental Division Sydney

Contact : MR RAJ SINGH Contact : Client Services

Address : 12 / 9-15 Gundah Rd Address : 277-289 Woodpark Road Smithfield NSW Australia 2164

MT KU-RING-GAI NSW. AUSTRALIA 2080

 E-mail
 : rsingh@netgeo.com.au
 E-mail
 : sydney@alsglobal.com

 Telephone
 : +61 02 8438 0300
 Telephone
 : +61-2-8784 8555

 Facsimile
 : +61 02 8438 0310
 Facsimile
 : +61-2-8784 8500

Project : G09 1100 QC Level : NEPM 2013 Schedule B(3) and ALS QCS3 requirement

Order number : ----

C-O-C number : ---- Date Samples Received : 03-DEC-2013

Sampler : RAJ SINGH Issue Date : 11-DEC-2013

Site : BERKELEY

No. of samples received : 14

Quote number : SY/455/13 No. of samples analysed : 5

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. All pages of this report have been checked and approved for release.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results
- Surrogate Control Limits



NATA Accredited Laboratory 825

Accredited for compliance with ISO/IEC 17025.

#### Signatories

This document has been electronically signed by the authorized signatories indicated below. Electronic signing has been carried out in compliance with procedures specified in 21 CFR Part 11.

Signatories	Position	Accreditation Category
Celine Conceicao	Senior Spectroscopist	Sydney Inorganics
Pabi Subba	Senior Organic Chemist	Sydney Organics
Phalak Inthaksone	Laboratory Manager - Organics	Sydney Organics

Address 277-289 Woodpark Road Smithfield NSW Australia 2164 PHONE +61-2-8784 8555 | Facsimile +61-2-8784 8500 Environmental Division Sydney ABN 84 009 936 029 Part of the ALS Group An ALS Limited Company



Page : 2 of 6 Work Order : ES1326278

Client : NETWORK GEOTECHNICS PTY LTD

Project : G09 1100



#### **General Comments**

The analytical procedures used by the Environmental Division have been developed from established internationally recognized procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are employed in the absence of documented standards or by client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Key: CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.

LOR = Limit of reporting

^ = This result is computed from individual analyte detections at or above the level of reporting

Page : 3 of 6 Work Order : ES1326278

Client : NETWORK GEOTECHNICS PTY LTD

Project : G09 1100



Page : 4 of 6 Work Order : ES1326278

Client : NETWORK GEOTECHNICS PTY LTD

Project : G09 1100




Sub-Matrix: SOIL (Matrix: SOIL)		Cli	ent sample ID	BH10 0.8-1.0M	BH12 0.3-0.5M	BH13 0.4-0.5M	BH14 0.1-0.2M	BH15 0.1-0.3M
	CI	ient sampli	ng date / time	19-NOV-2013 15:00				
Compound	CAS Number	LOR	Unit	ES1326278-002	ES1326278-004	ES1326278-005	ES1326278-007	ES1326278-008
EP080/071: Total Petroleum Hydrocar	bons - Continued							
C6 - C9 Fraction		10	mg/kg	<10	<10	<10	<10	<10
C10 - C14 Fraction		50	mg/kg	<50	<50	<50	<50	<50
C15 - C28 Fraction		100	mg/kg	<100	<100	<100	<100	<100
C29 - C36 Fraction		100	mg/kg	<100	<100	<100	<100	<100
C10 - C36 Fraction (sum)		50	mg/kg	<50	<50	<50	<50	<50
EP080/071: Total Recoverable Hydroc	arbons - NEPM 201	3						
C6 - C10 Fraction	C6_C10	10	mg/kg	<10	<10	<10	<10	<10
C6 - C10 Fraction minus BTEX	C6_C10-BTEX	10	mg/kg	<10	<10	<10	<10	<10
>C10 - C16 Fraction	>C10_C16	50	mg/kg	<50	<50	<50	<50	<50
>C16 - C34 Fraction		100	mg/kg	<100	<100	<100	<100	<100
>C34 - C40 Fraction		100	mg/kg	<100	<100	<100	<100	<100
>C10 - C40 Fraction (sum)		50	mg/kg	<50	<50	<50	<50	<50
>C10 - C16 Fraction minus Naphthalene (F2)		50	mg/kg	<50	<50	<50	<50	<50
EP080: BTEXN								
Benzene	71-43-2	0.2	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Toluene	108-88-3	0.5	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Ethylbenzene	100-41-4	0.5	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
meta- & para-Xylene	108-38-3 106-42-3	0.5	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
ortho-Xylene	95-47-6	0.5	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Sum of BTEX		0.2	mg/kg	<0.2	<0.2	<0.2	<0.2	<0.2
Total Xylenes	1330-20-7	0.5	mg/kg	<0.5	<0.5	<0.5	<0.5	<0.5
Naphthalene	91-20-3	1	mg/kg	<1	<1	<1	<1	<1
EP075(SIM)S: Phenolic Compound Su	ırrogates							
Phenol-d6	13127-88-3	0.1	%	99.1	99.5	98.2	96.2	94.0
2-Chlorophenol-D4	93951-73-6	0.1	%	106	106	103	100	98.6
2.4.6-Tribromophenol	118-79-6	0.1	%	87.1	82.4	81.6	79.5	73.7
EP075(SIM)T: PAH Surrogates								
2-Fluorobiphenyl	321-60-8	0.1	%	114	111	106	105	102
Anthracene-d10	1719-06-8	0.1	%	94.0	89.8	90.6	88.1	84.7
4-Terphenyl-d14	1718-51-0	0.1	%	94.6	83.8	86.4	83.3	80.4
EP080S: TPH(V)/BTEX Surrogates								
1.2-Dichloroethane-D4	17060-07-0	0.1	%	99.4	109	108	107	92.7

Page : 5 of 6 Work Order : ES1326278

Client : NETWORK GEOTECHNICS PTY LTD

Project : G09 1100





Page : 6 of 6 Work Order : ES1326278

Client : NETWORK GEOTECHNICS PTY LTD

Project : G09 1100

# **Surrogate Control Limits**

Sub-Matrix: SOIL		Recovery	Limits (%)
Compound	CAS Number	Low	High
EP075(SIM)S: Phenolic Compound Surrogates			
Phenol-d6	13127-88-3	63	123
2-Chlorophenol-D4	93951-73-6	66	122
2.4.6-Tribromophenol	118-79-6	40	138
EP075(SIM)T: PAH Surrogates			
2-Fluorobiphenyl	321-60-8	70	122
Anthracene-d10	1719-06-8	66	128
4-Terphenyl-d14	1718-51-0	65	129
EP080S: TPH(V)/BTEX Surrogates			
1.2-Dichloroethane-D4	17060-07-0	72.8	133.2
Toluene-D8	2037-26-5	73.9	132.1
4-Bromofluorobenzene	460-00-4	71.6	130.0



## AUSTRALIAN SAFER ENVIRONMENT & TECHNOLOGY PTY LTD

ABN 36 088 095 112

Our ref: ASET36491/39671/1-3

Your ref: ES1326530

NATA Accreditation No: 14484

12 December 2013

Australian Laboratory Services Pty Ltd 277 - 284 Woodpark Road Smithfield NSW 2164

Attn: Ms Nanthini Coilparampil

Dear Nanthini

#### **Asbestos Identification**

This report presents the results of three samples, forwarded by Australian Laboratory Services Pty Ltd on 10 December 2013, for analysis for asbestos.

1.Introduction: Three samples forwarded were examined and analysed for the presence of asbestos.

2. Methods: The samples were examined under a Stereo Microscope and selected fibres were

analysed by Polarized Light Microscopy in conjunction with Dispersion Staining method.

(Safer Environment Method 1.)

3. Results: Sample No. 1. ASET36491 / 39671 / 1. ES1326530 - 21 - C1.

Approx dimensions 4.8 cm x 4.5 cm x 4.3 cm

The sample consisted of a mixture of clayish soil, stones and plant matter.

No asbestos detected.

Sample No. 2. ASET36491 / 39671 / 2. ES1326530 - 22 - C2.

Approx dimensions 4.8 cm x 4.6 cm x 4.5 cm

The sample consisted of a mixture of clayish soil, stones and plant matter.

No asbestos detected.

Sample No. 3. ASET36491 / 39671 / 3. ES1326530 - 23 - C3.

Approx dimensions 4.8 cm x 4.6 cm x 3.9 cm

The sample consisted of a mixture of clayish soil, stones and plant matter.

No asbestos detected.

Analysed and reported by,

Laxman Dias. BSc Analyst / Approved Identifier Approved Signatory WORLD RECOGNISED ACCREDITATION

This document is issued in accordance with NATA's Accreditation requirements. Accredited for compliance with ISO/IEC 17025.

## AUSTRALIAN SAFER ENVIRONMENT & TECHNOLOGY PTY LTD

ABN 36 088 095 112

Our ref: ASET36492/39672 / 1 - 5

Your ref: ES1326278

NATA Accreditation No: 14484

11 December 2013

Australian Laboratory Services Pty Ltd 277 – 284 Woodpark Road Smithfield NSW 2164

**Attn: Ms Nanthini Coilparampil** 

Dear Nanthini,

#### **Asbestos Identification**

This report presents the results of five samples, forwarded by Australian Laboratory Services Pty Ltd on 10 December 2013, for analysis for asbestos.

1.Introduction: Five samples forwarded were examined and analysed for the presence of asbestos.

2. Methods: The samples were examined under a Stereo Microscope and selected fibres were analysed

by Polarized Light Microscopy in conjunction with Dispersion Staining method (Safer

**Environment Method 1.)** 

3. Results: Sample No. 1. ASET36492 / 39672 / 1. ES1326278 - 002 - BH10 - 0.8-1.0.

Approx dimensions 4.2 cm x 4.1 cm x 2.2 cm

The sample consisted of a mixture of soil, stones, plant matter, fragments of plaster and

corroded metal.

No asbestos detected.

Sample No. 2. ASET36492 / 39672 / 2. ES1326278 - 004 - BH12 - 0.3-0.5.

Approx dimensions 4.0 cm x 4.0 cm x 2.4 cm

The sample consisted of a mixture of clayish soil, stones, plant matter and fragments of plaster.

No asbestos detected.

Sample No. 3. ASET36492 / 39672 / 3. ES1326278 - 005 - BH13 - 0.4-0.5.

Approx dimensions 4.3 cm x 4.0 cm x 2.3 cm

The sample consisted of a mixture of clayish soil, stones and plant matter.

No asbestos detected.

Sample No. 4. ASET36492 / 39672 / 4. ES1326278 - 007 - BH14 - 0.1-0.2.

Approx dimensions 4.5 cm x 4.0 cm x 2.2 cm

The sample consisted of a mixture of clayish soil, stones, plant matter and pieces of corroded metal.

No asbestos detected.

SUITE 710 / 90 GEORGE STREET, HORNSBY NSW 2077 – P.O. BOX 1644 HORNSBY WESTFIELD NSW 1635 PHONE: (02) 99872183 FAX: (02)99872151 EMAIL: aset@bigpond.net.au WEBSITE: www.Ausset.com.au



## Sample No. 5. ASET36492 / 39672 / 5. ES1326278 - 008 - BH15 - 0.1-0.3.

Approx dimensions 4.1 cm x 4.1 cm x 2.1 cm

The sample consisted of a mixture of clayish soil, stones and plant matter.

No asbestos detected.

Analysed and reported by,

Nisansala Maddage. BSc(Hons)

 ${\bf Environmental\ Scientist/Approved\ Identifier}$ 

**Approved Signatory** 



This document is issued in accordance with NATA's Accreditation requirements. Accredited for compliance with ISO/IEC 17025.




## **LEGEND**

- O NETWORK GEOTECHNICS BOREHOLE 2013
- Δ COFFEY GEOTECHNICS TEST PIT 2012
- ☐ CLEARSAFE CONTAMINATION SPOT 2012



ACN 069 211 561 Unit 1/140 Industrial Road Oak Flats NSW 2529 AUSTRALIA Telephone 61 2 4257 4458 Facsimile 61 2 4257 4463 Email southcoast@netgeo.com.au



NOT IN SCALE DRAWING NO: G09/1100-A CLIENT: TCG PLANNING

PROJECT: PROPOSED LIFE CITY PROJECT

LOCATION: WARWICK STREET, BERKELEY, NSW

APPROXIMATE TEST LOCATION PLAN