

Project No: MAR/MET/12 Report No: MAR/MET75W/AIA/A

ARBORICULTURAL IMPACT ASSESSMENT TREE PROTECTION SPECIFICATION

Marrickville Metro Section 75W

Prepared for: AMP CAPITAL

11th October 2017 Revision A

Authors:

Anna Hopwood

Grad. Cert (Arboriculture), Dip. Horticulture (Arboriculture) Dip. Horticulture (Landscape Design)

Martin Peacock

BSc (Hons.) Arboriculture, Dip. Horticulture (Landscape Design)
HN Dip. Arboriculture. N Dip. Horticulture

Nicole O'Connell

Grad. Cert (Heritage Conservation), Dip. Hort (Landscape Design)

Matthew Laurence

BSc. (Hons) Biology, PhD Plant Pathology Grad. Cert (Arboriculture) p. 0404 424 264 f. 02 9012 0924 po box 146 summer hill 2130 info@treeiQ.com.au

treeiQ.com.au





Contents

1.0	INTRODUCTION	3
1.1	Background	3
1.2	The Proposal	3
	The Froposal	3
2.0	RESULTS	4
2.1	The Site	4
2.1	The Trees	4
2.2	The frees	·
3.0	ARBORICULTURAL IMPACT ASSESSMENT	4
3.1	Trees 62-64	4
3.2	Trees 65-67	5
3.3	Tree 68	5
3.4	Trees 69-74	5
3.5	Trees 75-78	6
3.6	Trees 79 & 83	7
3.7	Trees 80, 81 and 84	7
3.8	Tree 82	8
3.9	Tree 88	8
3.10	Trees 89, 90, 92, 94, 95, 98 & 100-104	8
3.11	93 & 97	8
3.12	2 105-108	9
3.13	B Pruning Specification	9
3.14	Replacement Planting	11
4.0	CONCLUSION	11
5.0	LIMITATIONS & DISCLAIMER	12
	DIDLIGORADIN O DEFENDAÇÃO	40
6.0	BIBLIOGRAPHY & REFERENCES	13
7.0	APPENDICES	14
	endix 1: Methodology	15
	endix 2: Plans	17
	endix 3: Tree Assessment Schedule	18
App	endix 4: Plates	23
	endix 5: Tree Protection Specification	27
App	endix 6: Typical Tree Protection Details	30

p. 0404 424 264 f. 02 9012 0924 po box 146 summer hill 2130 info@treeiQ.com.au abn 62 139 088 832

INTRODUCTION

1.1 **Background**

- 1.1.1 This Arboricultural Impact Assessment Report and Tree Protection Specification was prepared for AMP Capital in relation to the Section 75W Application for the Marrickville Metro Shopping Centre Redevelopment. The purpose of this Report is to undertake a Visual Tree Assessment (VTA), determine the impact of the proposed works on the trees, and where appropriate, recommend the use of sensitive construction methods to minimise adverse impacts.
- Previous Arboricultural Reports (Rev A dated 19th February 2010, Rev B dated 17th May 2010, Rev C dated 23rd May 1.1.2 2010, Rev B – dated 17th December 2012) for the Marrickville Metro project have been prepared by treeiQ. Tree numbering from the previous reports has been used for consistency. All of the trees addressed within this Report have been reassessed.
- 1.1.3 In preparing this Report, the author is aware of and has taken into account the objectives of the Marrickville DCP (2.20 Generic Provisions - Tree Management), Marrickville Street Tree Masterplan (2014), Australian Standard 4970 Protection of Trees on Development Sites (2009), Australian Standard 4373 Pruning of Amenity Trees (2007) and Australian Standard 2303 Tree Stock for Landscape Use (2015).

Refer to Methodology (Appendix 1)

- 1.1.4 This impact assessment is based on an assessment of the following supplied documentation/plans only:
 - Landscape Cover Sheet (Dwg No. 000/B) prepared by Site Image, dated 27.09.17
 - Landscape Character Plan (Dwg No. 002/B) prepared by Site Image, dated 27.09.17
 - Landscape Existing Tree Plan (Dwg No. 010/B) prepared by Site Image, dated 27.09.17
 - Landscape Masterplan (Dwg No. 100/B) prepared by Site Image, dated 27.09.17
 - Landscape Plan (Dwg No. 101/B) prepared by Site Image, dated 27.09.17
 - Landscape Plan (Dwg No. 102/B) prepared by Site Image, dated 27.09.17
 - Ground Floor Plan (EA106 Rev A) prepared by Hames Sharley, dated 25/09/17
 - Level 1 Floor Plan (EA107 Rev A) prepared by Hames Sharley, dated 25/09/17
 - Level 2 Floor Plan (EA108 Rev A) prepared by Hames Sharley, dated 25/09/17
 - Level 2A Floor Plan (EA109 Rev A) prepared by Hames Sharley, dated 25/09/17
 - Roof Plan (EA110 Rev A) prepared by Hames Sharley, dated 25/09/17
 - South & North Elevations (EA111 Rev A) prepared by Hames Sharley, dated 25/09/17
 - West & East Elevations (EA112 Rev A) prepared by Hames Sharley, dated 25/09/17

Refer to Plans (Appendix 2)

1.2 The Proposal

- 1.2.1 The proposal is for a Section 75W Application for the Marrickville Metro Shopping Centre Redevelopment. The supplied plans show the proposed works in the vicinity of the existing trees include the:
 - Demolition of existing structures and pavements
 - Construction of a new retail building
 - Installation of landscape treatments along the Smidmore Street, Edinburgh Road and Murray Street road reserve areas

Refer to Plans (Appendix 2)

¹ Mattheck & Breloer (2003)

3 | Page

RESULTS

2.1 The Site

- The site is a commercial allotment located to the south of the existing Marrickville Metro Shopping Centre, and is 2.1.1 bound by Smidmore Street to the north, Murray Street to the east, and Edinburgh Road to the south and west.
- An existing warehouse building occupies the eastern area of the site and a smaller single commercial building is 2.1.2 positioned in the centre-west.
- 2.1.3 The site is irregular in shape and is generally level.

2.2 The Trees

- Forty one (41) trees (and groups of trees) were assessed using the Visual Tree Assessment² (VTA) criteria and notes, and 2.2.1 consist of a mix of locally indigenous, Australian native and exotic species. With the exception of Trees 65-74 and 88, all of the trees are located within the road reserve areas and are managed by Inner West Council.
- 2.2.2 As required by Clause 2.3.2 of Australian Standard 4970 (2009) Protection of Trees on Development Sites (AS-4970), each tree assessed has been allocated a Retention Value. The Retention Value is based on the tree's Useful Life Expectancy and Landscape Significance with consideration to its health, structural condition and site suitability. The Retention Values do not take into account any proposed development works and are not a schedule for tree retention or removal. The trees have been allocated one of the following Retention Values:
 - **Priority for Retention**
 - Consider for Retention
 - Consider for Removal
 - Priority for Removal

Refer to Tree Assessment Schedule (Appendix 3)

2.2.3 A search of the BioNet Atlas of NSW Wildlife Database was undertaken in September 2017. Trees 79 and 83 Eucalyptus nicholii (Narrow Leaf Peppermint) were identified at the site and are listed as a Vulnerable Species under the NSW Biodiversity Conservation Act (2016) and the Commonwealth Environment Protection and Biodiversity Conservation Act (1999).3 Tree 92 Syzygium paniculatum (Lillypilly) was identified at the site and is listed as an Endangered Species under the NSW Biodiversity Conservation Act (2016). Based on their location within the road reserve, these trees are planted specimens and not a component of a locally indigenous vegetation community.

3.1 Trees 62-64

Trees 62-64 have been identified as Ficus microcarpa var. 'Hillii' (Hills Weeping Fig) and are located within the Western 3.1.1 road reserve of Murray Street, near the junction of Smidmore Street. The trees have been allocated a moderate to high Landscape Significance and a Retention Value of Consider for Retention.

4 | Page

3.1.2 The supplied plans show no works are proposed within the Tree Protection Zone (TPZ) areas of Trees 62-64.

p. 0404 424 264

f. 02 9012 0924

abn 62 139 088 832

po box 146 summer hill 2130 info@treeiQ.com.au

² Mattheck & Breloer (2003)

³ NSW Office of Environment and Heritage (2011)

⁴ NSW Environment & Heritage (2013)

3.2 Trees 65-67

- 3.2.1 Trees 65-67 have been identified as *Ficus microcarpa* var. *'Hillii'* (Hills Weeping Fig) and are located on the northern side of Smidmore Street, adjacent to the existing shopping centre building. The trees have been allocated a high Landscape Significance and a Retention Value of *Consider for Retention*.
- 3.2.2 The supplied plans show that landscape works including the installation of new pavement surfaces and timber decking are proposed within the TPZ areas of Trees 65-67. The extent of works represents *Major Encroachments* as defined by AS-4970. Clause 3.3.4 of AS-4970 notes that design factors and tree sensitive methods can be used to minimise the impact of the encroachment.

3.2.3 Recommendations

The following methods are recommended within the TPZ areas of Trees 65-67 to minimise adverse impacts:

- Demolition of existing structures and pavements should be undertaken using tree sensitive methods. Where possible, existing underground structures should be left in-situ.
- Decking, walls and seating (and other structures as required) should be supported on isolated piered footings (with all other parts of the structures positioned above existing ground levels to minimise excavation and root loss). Excavation for the pier holes should be undertaken using tree sensitive methods (hand/hydrovac/airspade etc). Pier hole locations should be flexible to enable the retention of roots (>25mmø, or as deemed necessary by the Project Arborist).
- Pavements (including sub-base materials) should be installed above or at existing grade and utilize existing sub-base layers where possible. Surfaces and sub-base materials should be thinned as required above roots (with appropriate root protection installed). The design and levels of pavements/kerbs should be modified to enable the retention of roots (>25mmø, or as deemed necessary by the Project Arborist).
- Plant installation should be undertaken using hand tools and roots (>25mmø) should be retained and protected.
 No mechanical cultivation/ripping of soils should be undertaken.

3.3 Tree 68

- 3.3.1 Tree 68 is a group of two (2) trees identified as *Acacia floribunda* (Sally Wattle) and are located on the northern side of Smidmore Street, adjacent to the existing vehicular entrance ramp. The trees have been allocated a low Landscape Significance and a Retention Value of *Priority for Removal*.
- 3.3.2 The supplied plans show no works are proposed within TPZ of Tree 68. However, given its Retention Value of *Priority for Removal*, consideration should be given to its removal and replacement as part of the proposed works.

3.4 Trees 69-74

- 3.4.1 Trees 69-74 have been identified as *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig) and are located on the northern side of Smidmore Street, near the junction of Edinburgh Road. The trees have been allocated a high Landscape Significance and a Retention Value of *Consider for Retention*.
- 3.4.2 The supplied plans show no works are proposed within the TPZ areas of Trees 69-74.

5 | Page

treeiQ.com.au

3.5 Trees 75-78

- 3.5.1 Trees 75-78 have been identified as *Corymbia citriodora* (Lemon Scented Gum) and are located within the southern road reserve of Smidmore Street, near the junction of Edinburgh Road. Trees 75 and 77 have been allocated a high Landscape Significance and a Retention Value of *Priority for Retention*. Trees 76 and 78 have been allocated a high Landscape Significance and a Retention Value of *Consider for Retention*.
- 3.5.2 The supplied plans show that demolition works, construction of a new retail building and footpath renewal works are proposed within the TPZ areas of Trees 75-78. The new building footprint falls outside of the trees' Structural Root Zone (SRZ) areas. The extent of works represents *Major Encroachments* as defined by AS-4970. Clause 3.3.4 of the AS-4970 outlines that the presence of existing or past structures or obstacles affecting root growth should be considered when determining the potential impact of the encroachment. A 300mm (approx.) high retaining wall is located along the north-western site boundary and adjacent to Trees 75-78. Within the site, the area to the rear of the retaining wall comprises of hard-stand. It is assumed the hardstand is supported on a 300mm deep (approx.) layer of compacted fill. It is likely that the spread of roots would have been partially restricted by the footing of the retaining wall and the suboptimal growing conditions beneath the hardstand area.
- 3.5.3 Pruning of Trees 75-78 will be required to accommodate the new building. Due to the trees' crown form with limited lateral branching, the removal of a number of large diameter first and second order branches will be required. Trees 76-78 have a reduced crown densities indicating they may be subject to a degree of physiological stress. Particularly for these trees, the extent of pruning works proposed may impact tree vigour and reduce their Useful Life Expectancies. The pruning will also impact the trees' crown form and symmetry although this will be less evident when the trees are viewed from within the street. Refer to Pruning Specification (Section 3.13).

3.5.4 Recommendations

The following methods are recommended within the TPZ areas of Trees 75-78 to minimise adverse impacts to the trees:

- Demolition of existing structures and pavements should be undertaken using tree sensitive methods. Where possible, existing underground structures should be left in-situ. Where tree roots are in contact with, or have grown under existing structures or footings within SRZ areas, the structure/footing should remain in situ and be assessed by the Project Arborist to determine if they are potentially providing support to the trees' root systems.
- The new building should be supported on isolated piered footings (with all other parts of the structures positioned above existing ground levels) unless root investigations show no roots are present within the building footprint. Excavation for the pier holes should be undertaken using tree sensitive methods (hand/hydrovac/airspade etc). No excavation for footings should extend into the trees' SRZ areas.
- Pavements (including sub-base materials) should be installed above or at existing grade and utilize existing sub-base layers where possible. Surfaces and sub-base materials should be thinned as required above roots (with appropriate root protection installed). The design and levels of pavements/kerbs should be modified to enable the retention of roots (>25mmø, or as deemed necessary by the Project Arborist).
- Plant installation should be undertaken using hand tools and roots (>25mmø) should be retained and protected. No mechanical cultivation/ripping of soils should be undertaken within the TPZ.

3.6 Trees 79 & 83

- 3.6.1 Trees 79 and 83 have been identified as *Eucalyptus nicholii* (Narrow Leaf Peppermint) and are located within the southern road reserve of Smidmore Street. The trees have been allocated a moderate Landscape Significance and a Retention Value of *Consider for Retention*.
- 3.6.2 The supplied plans show Trees 79 and 83 are proposed for removal as part of the landscape treatment. Anecdotally, *Eucalyptus nicholii* are considered to be a relatively short lived species in the Sydney area. The assessment of Trees 79 and 83 has determined the trees' health to be fair based on the volume of epicormic growth and deadwood within their crowns, and reduced crown densities. Replacement planting using healthy, advanced-size specimens could replace the loss of amenity from tree removal within a medium timeframe.

3.7 Trees 80, 81 and 84

- 3.7.1 Trees 80, 81 and 84 have been identified as *Corymbia citriodora* (Lemon Scented Gum) and are located within the southern road reserve of Smidmore Street. Tree 80 has been allocated a high Landscape Significance and a Retention Value of *Consider for Retention*. Trees 81 and 84 have been allocated a high Landscape Significance and a Retention Value of *Priority for Retention*.
- 3.7.2 The supplied plans show that demolition works, construction of a new retail building and footpath renewal works are proposed within the TPZ areas of Trees 80, 81 and 84. The extent of works represents *Major Encroachments* as defined by AS-4970. Clause 3.3.4 of AS-4970 notes that design factors and tree sensitive methods can be used to minimise the impact of the encroachment.
- 3.7.3 Pruning of Trees 80, 81 and 84 will be required to accommodate the new building. Due to the trees' crown form with limited lateral branching, the removal of a number of large diameter first and second order branches will be required. Tree 80 has a reduced crown density indicating the tree may be subject to a degree of physiological stress. Particularly for this tree, the extent of pruning works proposed may impact tree vigour and potentially reduce its Useful Life Expectancy. The pruning will also impact the trees' crown form and symmetry although this will be less evident when the trees are viewed from within the street. Refer to Pruning Specification (Section 3.13).

3.7.4 Recommendations

The following methods are recommended within the TPZ areas of Trees 80, 81 and 84 to minimise adverse impacts:

- Demolition of existing structures and pavements should be undertaken using tree sensitive methods. Where possible, existing underground structures should be left in-situ. Where tree roots are in contact with, or have grown under existing kerb sections or footings within SRZ areas, the kerb/footing should remain in situ and be assessed by the Project Arborist to determine if they are potentially providing support to the trees' root systems.
- The colonnade area and pathway adjacent to Trees 80 and 81 should be an elevated structure supported on isolated piered footings (with all other parts of the structure positioned above existing ground levels). Pier hole locations should be flexible to enable the retention of roots (>25mmø, or as deemed necessary by the Project Arborist). The pier diameters should be kept as small as possible to enable positioning between tree roots with minimal root pruning. No fill should be installed beneath the elevated structure to maintain adequate gaseous exchange through profile. Excavation for the pier holes should be undertaken using tree sensitive methods (hand/hydrovac/airspade etc.

An irrigation system with soil moisture monitors should be installed in the void beneath the elevated pathway to ensure ongoing and adequate water supply to the trees.

- New pavements (including sub-base materials) should be installed above or at existing grade and utilize existing sub-base layers where possible. Surfaces and sub-base materials should be thinned as required above roots (with appropriate root protection installed). The design and levels of pavements/kerbs should be modified to enable the retention of roots (>25mmø, or as deemed necessary by the Project Arborist).
- Plant installation should be undertaken using hand tools and roots (>25mmø) should be retained and protected. No mechanical cultivation/ripping of soils should be undertaken.

3.8 Tree 82

- 3.8.1 Tree 82 has been identified as *Corymbia citriodora* (Lemon Scented Gum) and is located within the southern road reserve of Smidmore Street. Tree 82 has been allocated a high Landscape Significance and a Retention Value of *Priority for Retention*.
- 3.8.2 The supplied plans show Tree 82 is proposed for removal to accommodate the elevated pedestrian connection. The pedestrian connection runs through eastern side of the tree's crown and the extent of pruning required to accommodate the structure would require the removal of more than 50% of its total crown volume.

3.9 Tree 88

- 3.9.1 Tree 88 has been identified as *Corymbia citriodora* (Lemon Scented Gum) and is located at the western end of the site, near the junction of Smidmore Street and Edinburgh Road. Tree 88 has been allocated a moderate Landscape Significance and a Retention Value of *Consider for Retention*.
- 3.9.2 The supplied plans show Tree 88 is proposed for removal to accommodate the new building footprint. Tree 88 is an early-mature specimen growing at the junction of two existing masonry walls. The tree is partially suppressed by the larger adjacent trees. Replacement planting using healthy, advanced-size specimens could replace the loss of amenity within a short to medium timeframe.

3.10 Trees 89, 90, 92, 94, 95, 98 & 100-104

- 3.10.1 Trees 89, 90, 92, 95, 98 and 100-104 are a mixed species planting including *Acmena smithii* 'Minor' (Lillypilly), *Syzygium paniculatum* (Lillypilly), *Leptospermum petersonii* (Lemon Scented Teatree), *Pistacia chinensis* (Chinese Pistachio) and *Callistemon viminalis* (Weeping Bottlebrush), and are located within the Edinburgh Road road reserve. Tree 94 *Elaeocarpus reticulatus* (Blueberry Ash) has recently died (as indicated by the dead foliage currently present within its crown). These trees have been allocated a low Landscape Significance and a Retention Value of *Consider for Removal*.
- 3.10.2 The supplied plans show Trees 89, 90, 92, 94, 95, 98 and 100-104 are proposed for removal as part of the landscape treatment. Their removal should have a low visual impact due to their relatively small size and location. Replacement planting using healthy, advanced-size specimens could replace the loss of amenity within a short timeframe.

3.11 Trees 93 & 97

3.11.1 Trees 93 and 97 have been identified as *Melaleuca quinquenervia* (Broad-leafed Paperbark) and are located within the Edinburgh Road road reserve. The trees have been allocated a moderate Landscape Significance and a Retention Value of *Consider for Retention*.

p. 0404 424 264 f. 02 9012 0924 po box 146 summer hill 2130 info@treeiQ.com.au abn 62 139 088 832 3.11.2 The supplied plans show Trees 93 and 97 are proposed for removal as part of the landscape treatment. The trees have developed a poor and asymmetrical crown form as a result of repeat line clearance works. A high volume of epicormic growth is also present at the lopping points. Epicormic growth can have an increased failure potential, particularly in storms and strong winds.

3.12 105-108

- 3.12.1 Trees 105-108 have been identified as *Livistona australis* (Cabbage Tree Palm) and are located within the Edinburgh Road road reserve. The trees have been allocated a moderate Landscape Significance and a Retention Value of *Consider for Retention*.
- 3.12.2 The supplied plans show Trees 105-108 are proposed for transplanting to an unspecified location. *Livistona australis* (Cabbage Tree Palm) are arborescent monocots and are generally tolerant of transplanting, even when of a large mature size. A tree transplanting contractor should be engaged to advise on the rootball preparation, transplanting and aftercare methods required to ensure successful relocation of these trees.

3.13 Pruning Specification

3.13.1 The supplied plans show that Trees 75-78, 80, 81 and 84 will need to be pruned to provide clearance to the new building as outlined within Tabled 1-7 below.

3.13.2 Table 1: Tree 75

Branch Orientation	Order of Branch	Branch Diameter	Height Above Grade	Comments	Plate No.
SE	1 st	300mm	6.5m	2 x branches	7
	Higher order	<50mm		Selectively reduce to suitable small diameter lateral branches	

3.13.3 Table 2: Tree 76

Branch Orientation	Order of Branch	Branch Diameter	Height Above Grade	Comments	Plate No.
SE	1 st	275mm	6m		8
SE	1 st	250mm	10m		8
	Higher order	<50mm		Selectively reduce to suitable small diameter lateral branches	

3.13.4 Table 3: Tree 77

Branch	Order of Branch	Branch Diameter	Height Above	Comments	Plate
Orientation	Order of Branch	Diancii Dianietei	Grade	Comments	No.
S	2 nd	200mm	6m	2 x branches	9
SE	3 rd	100mm	7m		9
	Higher order	<50mm		Selectively reduce to suitable	
	nigher order	Sollilli		small diameter lateral branches	

3.13.5 Table 4: Tree 78

Branch Orientation	Order of Branch	Branch Diameter	Height Above Grade	Comments	Plate No.
	1 st	250mm	6m		10
	1 st	125mm	8m		10
	1 st	125mm	10m		10
	Higher order	<50mm		Selectively reduce to suitable small diameter lateral branches	

3.13.6 Table 5: Tree 80

Branch Orientation	Order of Branch	Branch Diameter	Height Above Grade	Comments	Plate No.
S	1 st	200mm	6.5m		11
SW	3 rd	100mm	6.5		11
S	1 st	125mm	7m		11
SE	1 st	100mm	8.5m		11
S	1 st	125mm	9m		11
	Higher order	<50mm		Selectively reduce to suitable small diameter lateral branches	

3.13.7 Table 6: Tree 81

	_				
Branch Orientation	Order of Branch	Branch Diameter	Height Above Grade	Comments	Plate No.
SW	2 nd	200mm	8m	Selectively reduce to 2 nd order lateral branches	13
SE	3 rd	75mm	8.5m		12
S	2 nd	75mm	10m		12
SW	1 st	125mm	12m		12
S	1 st	150mm	12m		12
	Higher order	<50mm		Selectively reduce to suitable small diameter lateral branches	

3.13.8 Table 7: Tree 84

able 7. Hee o-	*				
Branch Orientation	Order of Branch	Branch Diameter	Height Above Grade	Comments	Plate No.
S	2 nd	200mm	9m	Selectively reduce to 2 nd order lateral branch	14
S	1 st	250mm	10m		14
	Higher order	>75mm		Selectively reduce to suitable small diameter lateral branches	

3.13.9 The assessment of the pruning requirements detailed in this Report was estimated from ground level only. Provision should be made within the design so that additional pruning for construction access and scaffolding/hoarding is not required. Where additional clearance is required, branches may be temporarily pushed or tied. Where branches cannot be pushed or tied back without damage, scaffolding/hoarding should be modified and constructed around branches (with appropriate branch protection installed as required).

3.13.10 Pruning works should be carried out by a Practising Arborist. The Practising Arborist should hold a minimum qualification equivalent (using the Australian Qualifications Framework) of Level 3 or above, in Arboriculture or its recognised equivalent. The Practising Arborist should have a minimum of 3 years' experience in practical Arboriculture. Pruning work should be undertaken in accordance with Australian Standard 4373: Pruning of Amenity Trees (2007), Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work (2016) and other applicable legislation and codes.

3.14 Replacement Planting

- 3.14.1 The supplied plans show replacement street trees are proposed along Edinburgh Road and Murray Street. The trees should be supplied as advanced-size stock to help offset the loss of amenity resultant from the tree removals.
- 3.14.2 Replacement planting should be supplied/installed in accordance with the *Marrickville Street Tree Masterplan (2014)* and *Australian Standard 2303 (2015) Tree Stock for Landscape Use.*

4.0 CONCLUSION

- 4.1 Forty one (41) trees were assessed in preparation of this Report, and consist of a mix of locally indigenous, Australian native and exotic species. With the exception of Trees 65-74 and 88, all of the trees are located within the road reserve areas and are managed by Inner West Council.
- 4.2 The proposal is for a Section 75W Application for the Marrickville Metro Shopping Centre Redevelopment. The supplied plans show the proposed works in the vicinity of the existing trees include the demolition of existing structures and pavements, construction of a new retail building and installation of landscape treatments along the road reserve areas.
- 4.3 The supplied plans show that sixteen (16) trees (Trees 79, 82, 83, 88-90, 92-95, 97, 98 & 100-104) are to be removed to accommodate the proposed development. Of these, one (1) tree has been allocated a Retention Value of *Priority for Retention*, five (5) trees have been allocated a Retention Value of *Consider for Retention*, and ten (10) trees have been allocated a Retention Value of *Consider for Removal*. Tree 94 is dead.
- 4.4 The supplied plans show twenty (20) trees (Trees 62-78, 80, 81 & 84) are to be retained as part of the proposed development. Of these, works are proposed within the TPZ areas of Trees 65, 66, 67, 69, 75, 76, 77, 78, 80, 81 and 84. Tree sensitive design, demolition and construction methods should be used to minimise adverse impacts (refer to Section 3.0). The trees should be protected in accordance with the Tree Protection Specification (Appendix 5).
- 4.5 The supplied plans show that Trees 75-78, 80, 81 and 84 will need to be pruned to provide clearance to the new building. Trees 76-78 and 80 have a reduced crown densities indicating the trees may be subject to a degree of physiological stress. Particularly for these trees, the extent of pruning works proposed may impact tree vigour and potentially reduce their Useful Life Expectancies. The pruning will also impact the trees' crown form and symmetry although this will be less evident when the trees are viewed from within the street. Pruning work should be undertaken in accordance with Australian Standard 4373: Pruning of Amenity Trees (2007), Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work (2016) and other applicable legislation and codes.

11 | Page

- 4.6 The supplied plans show that four (4) trees (Trees 105-108) are proposed for transplanting to an unspecified location. Livistona australis (Cabbage Tree Palm) are arborescent monocots and are generally tolerant of transplanting, even when of a large mature size. A tree transplanting contractor should be engaged to advise on the rootball preparation, transplanting and aftercare methods required to ensure successful relocation of these trees.
- 4.7 The supplied plans show replacement street trees are to be installed along Edinburgh Road and Murray Street. The trees should be supplied as advanced-size stock to help offset the loss of amenity resultant from the tree removals. Replacement planting should be supplied/installed in accordance with the Marrickville Street Tree Masterplan (2014) and Australian Standard 2303 (2015) Tree Stock for Landscape Use.

5.0 LIMITATIONS & DISCLAIMER

TreeiQ takes care to obtain information from reliable sources. However, TreeiQ can neither guarantee nor be responsible for the accuracy of information provided by others. Plans, diagrams, graphs and photographs in this Arboricultural Report are visual aids only and are not necessarily to scale. This Report provides recommendations relating to tree management only. Advice should be sought from appropriately qualified consultants regarding design/construction/ecological/heritage etc issues.

This Report has been prepared for exclusive use by the client. This Report shall not be used by others or for any other reason outside its intended target or without the prior written consent of TreeiQ. Unauthorised alteration or separate use of any section of the Report invalidates the Report.

Many factors may contribute to tree failure and cannot always be predicted. TreeiQ takes care to accurately assess tree health and structural condition. However, a tree's internal structural condition may not always correlate to visible external indicators. There is no warranty or guarantee, expressed or implied that problems or deficiencies regarding the trees or site may not arise in the future. Information contained in this report covers only the trees assessed and reflects the condition of the trees at the time of inspection. Additional information regarding the methodology used in the preparation of this Report is attached as Appendix 1. A comprehensive tree risk assessment and management plan for the trees is beyond the scope of this Report.

Reference should be made to any relevant legislation including Tree Management Controls. All recommendations contained within this Report are subject to approval from the relevant Consent Authority.

This Report is based on Standards Australia Ltd copyrighted material that is distributed by SAI Global Ltd on Standards Australia Ltd's behalf. It may be reproduced and modified in accordance with the terms of SAI Global Ltd's Licence 1110-c049 to TreeiQ ('the Licensee'). All amended, marked-up and licensed copies of this document must be obtained from the Licensee. Standards Australia Ltd's copyright material is not for resale, reproduction or distribution in whole or in part without written permission from SAI Global Ltd: tel +61 2 8206 6355 or copyright@saiglobal.com

6.0 BIBLIOGRAPHY & REFERENCES

Barrell (1995), 'Pre-development Tree Assessments', in *Trees & Building Sites, Proceedings of an International Conference Held in the Interest of Developing a Scientific Basis for Managing Trees in Proximity to Buildings,* International Society of Arboriculture, Illinois, USA, pp. 132-142

Harris, Clark & Matheny (1999), Arboriculture: Integrated Management of Landscape Trees, Shrubs And Vines, Prentice Hall, New Jersey

Inner West Council (2011), Marrickville DCP (2.20 Generic Provisions - Tree Management)

Inner West Council (2014), Marrickville Street Tree Masterplan

Matheny & Clark (1994), A Photographic Guide to the Evaluation of Hazard Trees in Urban Areas, International Society of Arboriculture, USA

Mattheck & Breloer (1994), The Body Language of Trees: A Handbook for Failure Analysis, The Stationary Office, London

Simon, Dormer & Hartshorne (1973), Lowson's Botany, Bell & Hyman, London

Office of Environment and Heritage (2011), BioNet Atlas of NSW Wildlife

Standards Australia (2009), Protection of Trees on Development Sites AS-4970

Standards Australia (2007), Pruning of Amenity Trees AS-4373

Standards Australia (2015), Tree Stock for Landscape Use AS-2303

Appendix 1: Methodology

- 1.1 Site Inspection: This report was determined as a result of a comprehensive site during September 2017. The comments and recommendations in this report are based on findings from this site inspection.
- 1.2 Visual Tree Assessment (VTA): The subject tree(s) was assessed using the Visual Tree Assessment criteria and notes as described in The Body Language of Trees – A Handbook for Failure Analysis.⁵ The inspection was limited to a visual examination of the subject tree(s) from ground level only. No internal diagnostic testing was undertaken as part of this assessment. Trees outside the subject site were assessed from the property boundaries only.
- 1.3 **Tree Dimensions**: The dimensions of the subject tree(s) are approximate only.
- **Tree Locations:** The location of the subject tree(s) was determined from the supplied plans. 1.4
- 1.5 Trees & Development: Tree Protection Zones, Tree Protection Measures and Sensitive Construction Methods for the subject tree were based on methods outlined in Australian Standard 4970-2009 Protection of Trees on Development Sites.

The Tree Protection Zone (TPZ) is described in AS-4970 as a combination of the root area and crown area requiring protection. It is an area isolated from construction disturbance, so that the tree remains viable.

The Structural Root Zone (SRZ) is described in AS-4970 as the area around the base of a tree required for the tree's stability in the ground. Severance of structural roots within the SRZ is not recommended as it may lead to the destabilisation and/or demise of the tree.

In some cases it may be possible to encroach into or make variations to the theoretical TPZ. A Minor Encroachment is less than 10% of the area of the TPZ and is outside the SRZ. The area lost to this encroachment should be compensated for elsewhere and contiguous with the TPZ. A Major Encroachment is greater than 10% of the TPZ or inside the SRZ. In this situation the Project Arborist must demonstrate that the tree would remain viable. This may require root investigation by non-destructive methods or the use of sensitive construction methods.

- 1.6 **Tree Health**: The health of the subject tree(s) was determined by assessing:
 - I. Foliage size and colour
 - II. Pest and disease infestation
 - III. Extension growth
 - IV. Crown density
 - V. Deadwood size and volume
 - VI. Presence of epicormic growth
- 1.7 Tree Structural Condition: The structural condition of the subject tree(s) was assessed by:
 - I. Assessment of branching structure
 - (i.e co-dominant/bark inclusions, crossing branches, branch taper, terminal loading, previous branch failures)
 - Visible evidence of structural defects or instability
 - (i.e root plate movement, wounds, decay, cavities, fungal brackets, adaptive growth)
 - III. Evidence of previous pruning or physical damage
 - (root severance/damage, lopping, flush-cutting, lions tailing, mechanical damage)
- 1.8 Useful Life Expectancy (ULE): The ULE is an estimate of the longevity of the subject tree(s) in its growing environment. The ULE is modified where necessary to take in consideration tree(s) health, structural condition and site suitability. The tree(s) has been allocated one of the following ULE categories (Modified from Barrell, 2001):
 - I. 40 years +
 - II. 15-40 years
 - III. 5-15 years
 - Less than 5 years IV.

p. 0404 424 264 f. 02 9012 0924 po box 146 summer hill 2130 info@treeiQ.com.au

abn 62 139 088 832

⁵ Mattheck & Breloer (2003)

1.9 Landscape Significance: Landscape Significance was determined by assessing the combination of the cultural, environmental and aesthetic values of the subject tree(s). Whilst these values are subjective, a rating of high, moderate, low or insignificant has been allocated to the tree(s). This provides a relative value of the tree's Landscape Significance which may aid in determining its Retention Value. If the tree(s) can be categorized into more than one value, the higher value has been allocated.

Landscape	Description
Significance	Description
	The subject tree is listed as a Heritage Item under the <i>Local Environmental Plan</i> with a local or state level of significance.
Very High	The subject tree is listed on Council's Significant Tree Register or is considered to meet the criteria for significance assessment of trees and/or landscapes by a suitably qualified professional. The criteria are based on general principles outlines in the Burra Charter and on criteria from the Register of the National Estate.
	The subject tree is a remnant tree.
	The subject tree creates a 'sense of place' or is considered 'landmark' tree.
	The subject tree is of local, cultural or historical importance or is widely known.
High	The subject tree has been identified by a suitably qualified professional as a species scheduled as a Threatened or Vulnerable Species or forms part of an Endangered Ecological Community associated with the subject site, as defined under the provisions of the <i>Threatened Species Conservation Act</i> 1995 (NSW) or the <i>Environmental Protection and Biodiversity Conservation Act</i> 1999.
півіі	The subject tree is known to provide habitat to a threatened species.
	The subject tree is an excellent representative of the species in terms of aesthetic value.
	The subject tree is of significant size, scale or makes a significant contribution to the canopy cover of the locality.
	The subject tree forms part of the curtilage of a heritage item with a known or documented association with that item.
	The subject tree makes a positive contribution to the visual character or amenity of the area.
Moderate	The subject tree provides a specific function such as screening or minimising the scale of a building.
Wioderate	The subject tree has a known habitat value.
	The subject tree is a good representative of the species in terms of aesthetic value.
	The subject tree is an environmental pest species or is exempt under the provisions of the local Council's
Low	Tree Management Controls
LOW	The subject tree makes little or no contribution to the amenity of the locality.
	The subject tree is a poor representative of the species in terms of aesthetic value.
Insignificant	The subject tree is declared a Noxious Weed under the Noxious Weeds Act

- **1.10 Retention Value**: Retention Value was based on the subject tree's Useful Life Expectancy and Landscape Significance. The Retention Value was modified where necessary to take in consideration the subject tree's health, structural condition and site suitability. The subject tree(s) has been allocated one of the following Retention Values:
 - I. Priority for Retention
 - II. Consider for Retention
 - III. Consider for Removal
 - IV. Priority for Removal


ULE			Landscape Signi	ificance	
	Very High	High	Moderate	Low	Insignificant
40 years +		Priorit	ty for Retention		
15-40 years	Priority for Retention	Priority for Retention	Consider for Retention	Consider for Removal	Priority for Removal
5-15 years		Consid	er for Retention		
Less than 5 years	Consider for Removal		Priority for Re	moval	

The above table has been modified from the Footprint Green Tree Significance and Retention Value Matrix.

p. 0404 424 264 f. 02 9012 0924 po box 146 summer hill 2130 info@treeiQ.com.au abn 62 139 088 832

Marrickville Metro Expansion 34 Victoria Road, Marrickville, NSW 2204

Coversneet	Landscape Character Plan	Tree Removal Plan	Landscape Masterplan	Landscape Plan
9	000	010	100	101



Indicative Plant Schedule

Botanical Name	Common Name	Mature Height (m.)	Mature Spread (m.)	Plant Origin	Water
rees					
Elaeocarpus eumundii	Eumundi Quandong	15	10	Non Indigenous	Medium
agerstroemia indica	Crepe Myrtle	9	e	Non Indigenous	Low
Hedge					
Acmena smithii var.minor	Dwarf Lillypilly	8	2	Indigenous	Medium
Acmena smithii var. minor 'Allyn Magic'	Allyn Magic Lilly Pilly	8:0	9.0	Indigenous	Medium
Wurraya paniculata	Orange Jasmine	e	2	Non Indigenous	Medium
Westringia Wymyabbie Gem'	Wynyabbie Rosemary	1.5	1.5	Indigenous	Low
Accents					
Cycas revoluta	Cycad	ю	2	Non Indigenous	Medium
Doryanthes excelsa	Gymea Lily	2	2	Indigenous	Low
Sroundcovers & Grasses					
Jinope muscari Evergreen Giant'	Giant Liriope	9:0	9.0	Non Indigenous	Medium
comandra fongifolia Tanika'	Tanika Mat Rush	0.7	9:0	Indigenous	Low
Frachelospemum jasminoides	Star Jasmine	0.3	-	Indigenous	Low
Themeda australis	Kangaroo Grass	8:0	0.3	Indigenous	Low
Philodendron Xanadu'	Xanadu	9:0	8:0	Non Indigenous	High
Carex appressa	Grass Flag	8.0	9.0	Indigenous	Medium
Juncus usitatus	Juncus	8.0	0.3	Indigenous	Medium
solepsis nodosa	Knobby Club Grass	-	0.7	Indigenous	Low
And the state of t	Transfer Adams Donner	1			

NOT FOR CONSTRUCTION

LEGEND

AMPCAPITAL *** Marrickville Metro Shopping Centre Redevelopment 34 Victoria Rd, Marrickville NSW


SECTION 75W Scale: Job Number: SS16-3593

lesue: 000 B









































LEGEND



Marrickville Metro Shopping Centre Redevelopment 34 Victoria Rd, Marrickville NSW

NOT FOR CONSTRUCTION


Detail Plan 1 - Smidmore Street

SECTION 75W


Drawing Name: Landscape Character Plan


AMPCAPITAL **

SITE IMAGE









Appendix 3: Tree Assessment Schedule

Implication	Retain. No works within TPZ.	Retain. No works within TPZ.	Retain. No works within TPZ.	Retain. Major encroachment, landscape works.	Retain. Major encroachment, landscape works.	Retain. Major encroachment, landscape works.	Retain. No works within TPZ.	Retain. No works within TPZ.
Radial SRZ (m)	2.6	3.1	3.3	ю	2.9	ю	2	3.4
Radial TPZ (m)	9.9	10.2	11.4	9.1	8.2	9.1	3.6	12
Retention Value	Consider for Retention	Consider for Retention	Consider for Retention	Consider for Retention	Consider for Retention	Consider for Retention	Priority for Removal	Consider for Retention
L/Significance	Moderate	High	High	High	High	High	Low	High
ULE (years)	5-15	5-15	5-15	5-15	5-15	5-15	\$	5-15
Comments	Wound/s with advanced stages of decay. Branch inclusions. Trunk cavity, minor.	Wound/s with early stages of decay. Branch inclusions.	Wound/s with early stages of decay. Branch inclusions. Failed lower branch, presumed resulting from high sided vehicle impact.	Structures with SRZ. Branch inclusion/s. Wound/s with advanced stages of decay. Branch contact with steel cage.	Co-dominant inclusion. Wound, advanced stages of decay.	Branch inclusion/s. Wound/s with early stages of decay. Exposed surface roots.	Group of 2. Crown density 50-75%. Wound/s with early stages of decay.	Wound/s with early stages of decay. Low volumes of small diameter (<25mm) epicormic growth.
Structural Condition Rating	Poor	Fair	Fair	Fair	Fair	Fair	Fair	Good
Health Rating	Good	Good	Good	Good	Good	Good	Fair	poog
Radial Crown Spread (m)	ιΩ	10	б	6	12	6	5 max	O
Height (m)	13	17	17	18	18	16	7 max	18
DBH (mm)	550	850	950	350 300 600	400 450 300	400 400 400 300	200 200 + 200	1000
Species	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	<i>Acacia</i> floribunda (White Sally Wattle)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)
Tree No.	62	63	64	99	99	29	89	69

	_			_	_	t,	r,	t,	ر ب ۲
Implication	Retain. No works within TPZ.	Retain. No works within TPZ.	Retain. No works within TPZ.	Retain. No works within TPZ.	Retain. No works within TPZ.	Retain. Major encroachment, building & landscape works.	Retain. Major encroachment, building & landscape works.	Retain. Major encroachment, building & landscape works.	Retain. Major encroachment, building & landscape
Radial SRZ (m)	3.4	ю	2.9	3.1	4.3	2.8	2.8	2.6	2.8
Radial TPZ (m)	12	6	8.4	9.6	15	7.8	7.8	9.9	7.8
Retention Value	Consider for Retention	Consider for Retention	Consider for Retention	Consider for Retention	Consider for Retention	Priority for Retention	Consider for Retention	Priority for Retention	Consider for Retention
L/Significance	High	High	High	High	High	High	High	High	High
ULE (years)	5-15	5-15	5-15	5-15	5-15	15-40	5-15	15-40	5-15
Comments	Codominant inclusion. Wound/s with early stages of decay. Low volumes of small diameter (<25mm) epicormic growth. Mechanical damage to exposed surface roots.	Codominant inclusion. Wound/s with early stages of decay. Low volumes of small diameter (<25mm) epicormic growth.	Wound/s with early stages of decay. Low volumes of small diameter (<25mm) epicormic growth.	Codominant inclusion. Wound/s with early stages of decay. Low volumes of small diameter (<25mm) epicormic growth.	Codominant inclusion. Wound/s with early stages of decay. Low volumes of small diameter (<25mm) epicormic growth.	Low volumes of medium (25-75mm) diameter deadwood. Girdled roots. Existing structures within SRZ.	Crown density 50-75%. Existing structures within SRZ.	Crown density 50-75%. Low volumes of large (75mm+) diameter deadwood. Existing structures within SRZ.	Hanger. Crown density 50-75%. Existing structures within SRZ.
Structural Condition Rating	Fair	Fair	Good	Fair	Fair	Good	Good	Good	P009
Health Rating	Good	Good	Good	Good	Good	Good	Fair	Fair	Fair
Radial Crown Spread (m)	œ	10	∞	9	11	Ō	Ø	7	œ
Height (m)	19	19	18	18	18	16	16	15	17
DBH (mm)	009	600	400 300x2 250x2 150	600 450 400 200	1000 900x2 750	650	029	550	650
Species	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Ficus microcarpa var. 'Hillii' (Hills Weeping Fig)	Corymbia citriodora (Lemon Scented Gum)	Corymbia citriodora (Lemon Scented Gum)	Corymbia citriodora (Lemon Scented Gum)	Corymbia citriodora (Lemon Scented Gum)
Tree No.	70	71	72	73	74	75	92	77	78

Implication	works.	Remove. Landscape treatment.	Retain. Major encroachment, building & landscape works.	Retain. Major encroachment, building & landscape works.	Remove. Landscape treatment.	Remove. Landscape treatment.	Retain. Major encroachment, building & landscape works.	Remove. Building footprint.
Radial SRZ (m)		2.7	2.6	2.8	3.5	2.6	3.1	2
Radial TPZ (m)		8.8	9.9	7.8	13.2	9.9	10.2	3.6
Retention Value		Consider for Retention	Consider for Retention	Priority for Retention	Priority for Retention	Consider for Retention	Priority for Retention	Consider for Retention
L/Significance		Moderate	High	High	High	Moderate	High	Moderate
ULE (years)		5-15	5-15	15-40	15-40	5-15	15-40	5-15
Comments		Crown density 75-95%. Low volumes of medium diameter (25-75mm) deadwood. Low volumes of small diameter (<25mm) epicormic growth. Wound/s, various stages of decay. Existing structures within SRZ. Impact damage to branches.	Low volumes of medium (25-75mm) diameter deadwood. Crown density 50-75%. Girdled roots. Existing structures within SRZ. Mechanical damage to exposed surface roots.	Crown density 75-95%. Low volumes of medium (25-75mm) diameter deadwood. Existing structures within SRZ.	Crown density 75-95%. Low volumes of medium (25-75mm) diameter deadwood. Structures within SRZ.	Crown density 25-50%. Moderate volumes of small diameter (<25mm) deadwood. Moderate volumes of small diameter (<25mm) epicormic growth. Partially suppressed. Existing structures within SRZ.	Low volumes of medium diameter (25-50mm) deadwood. Crown density 75-95%. Structures within SRZ.	Retaining wall within SRZ. Partially suppressed. Asymmetrical crown form.
Structural Condition Rating		Fair	Good	Good	9009	Poog	Good	Good
Health Rating		Fair	Fair	Fair	Fair	Fair	Good	Good
Radial Crown Spread (m)		7	7	12	∞	œ	12	7
Height (m)		თ	15	20	20	თ	20	∞
(mm)		400	550	650	1100	300	850	300
Species		Eucalyptus nicholii (Narrow Leaf Peppermint)	Corymbia citriodora (Lemon Scented Gum)	Corymbia citriodora (Lemon Scented Gum)	Corymbia citriodora (Lemon Scented Gum)	Eucalyptus nicholii (Narrow Leaf Peppermint)	Corymbia citriodora (Lemon Scented Gum)	Corymbia citriodora (Lemon Scented Gum)
Tree No.		79	80	81	82	83	84	88

Implication	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.
Radial SRZ (m)	1.5	1.5	1.5	æ		1.7	3.5	2	1.5
Radial TPZ (m)	2	2	2	O		2.4	13.2	3.5	2
Retention Value	Consider for Removal	Consider for Removal	Consider for Removal	Consider for Retention		Consider for Removal	Consider for Retention	Consider for Removal	Consider for Removal
L/Significance	Low	Low	Low	Moderate		Low	Moderate	Low	Low
ULE (years)	5-15	5-15	5-15	5-15		5-15	5-15	5-15	15-40
Comments	Under powerlines. Whipper snipper damage. Scale and sooty mould.	Under powerlines. Crown density 50-75%.	Pruned for powerline clearance.	Pruned for powerline clearance. High volumes of small diameter (<25mm) epicormic growth. Wound/s, no visible signs of decay. Poor form.	Dead	Co-dominant stem removed.	Pruned for powerline clearance. High volumes of small diameter (<25mm) epicormic growth. Wound/s, no visible signs of decay. Poor form. Path/kerb displacement.	Wound/s with early stages of decay. Co-dominant inclusion. Recently crown lifted.	Not in full leaf at time of assessment. Low volumes of small diameter (<25mm) deadwood. Recently crown lifted.
Structural Condition Rating	Fair	Good	Fair	Poor		Fair	Poor	Poor	Good
Health Rating	Poog	Fair	900g	Poog		900g	p0009	Poog	9009
Radial Crown Spread (m)	2	2	m	7		2	7	m	7
Height (m)	м	ю	m	∞		т	14	5	4
(mm)	75	75	100	750		200	1100	200	100
Species	Acmena smithii 'Minor' (Lillypilly)	Acmena smithii 'Minor' (Lillypilly)	Syzygium paniculatum (Lillypilly)	Melaleuca quinquenervia (Broad-leafed Paperbark)	Elaeocarpus reticulatus (Blueberry Ash)	Leptospermum petersonii (Lemon Scented Teatree)	Melaleuca quinquenervia (Broad-leafed Paperbark)	Acmena smithii 'Minor' (Lillypilly)	<i>Pistacia chinensis</i> (Chinese Pistachio)
Tree No.	68	06	92	93	94	95	26	86	100

Implication	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Remove. Landscape treatment.	Transplant.	Transplant.	Transplant.	Transplant.
Radial SRZ (m)	1.5	1.7	1.5	1.5	n/a	n/a	n/a	n/a
Radial TPZ (m)	2	2.4	2	2	4	4	4	4
Retention Value	Consider for Removal	Consider for Removal	Consider for Removal	Consider for Removal	Consider for Retention	Consider for Retention	Consider for Retention	Consider for Retention
L/Significance	Low	Low	Low	Low	Moderate	Moderate	Moderate	Moderate
ULE (years)	5-15	15-40	15-40	15-40	15-40	15-40	15-40	15-40
Comments	Previous branch failure. Mechanical damage to roots. Moderate volumes of small diameter (<25mm) deadwood. Recently crown lifted.	Girdling roots. Recently crown lifted.	Moderate volumes of small diameter (<25mm) deadwood. Mechanical damage to base.	Recently crown lifted.				
Structural Condition Rating	Poog	900g	Fair	900g	poo9	9009	900g	Poog
Health Rating	Poog	poog	Poog	Poo 9	Good	Poo 9	Poog	Bood
Radial Crown Spread (m)	2	2	2	2	т	m	т	м
Height (m)	4	4	4	4	7	7	7	œ
DBH (mm)	150	200	100	150	400	400	400	400
Species	Callistemon viminalis (Weeping Bottlebrush)	Acmena smithii 'Minor' (Lillypilly)	Callistemon viminalis (Weeping Bottlebrush)	Acmena smithii 'Minor' (Lillypilly)	<i>Livistona australis</i> (Cabbage Tree Palm)	<i>Livistona australis</i> (Cabbage Tree Palm)	<i>Livistona australis</i> (Cabbage Tree Palm)	Livistona australis (Cabbage Tree Palm)
Tree No.	101	102	103	104	105	106	107	108

Plate 6: Showing Trees 100-108


































Appendix 5: Tree Protection Specification

1.0 Appointment of Project Arborist

A Project Arborist shall be engaged prior the commencement of work on-site and monitor compliance with the protection measures. The Project Arborist shall inspect the tree protection measures and Compliance Certification shall be prepared by the Project Arborist for review by the Principal Certifying Authority prior to the release of the Compliance Certificate.

The Project Arborist shall have a minimum qualification equivalent (using the Australian Qualifications Framework) of NSW TAFE Certificate Level 5 or above in Arboriculture.

1.1 Compliance

Contractors and site workers shall receive a copy of these specifications a minimum of 3 working days prior to commencing work on-site. Contractors and site workers undertaking works within the Tree Protection Zone shall sign the site log confirming they have read and understand these specifications, prior to undertaking works on-site.

The Project Arborist shall undertake regular site inspections and certify that the works are being undertaken in accordance with this specification.

Compliance Documentation shall be prepared by the Project Arborist following each site inspection. The Compliance Documentation shall include documentary evidence of compliance with the tree protection measures and methods as outlined within this Specification. Upon the completion of the works, a final assessment of the trees shall be undertaken by the Project Arborist and future recommended management strategies implemented as required.

1.2 Tree Protection Zone

The trees to be retained shall be protected prior and during construction from activities that may result in an adverse effect on their health or structural condition. The area within the Tree Protection Zone (TPZ) shall exclude the following activities, unless otherwise stated:-

- Modification of existing soil levels, excavations and trenching
- Mechanical removal of vegetation
- Movement of natural rock
- Storage of materials, plant or equipment or erection of site sheds
- Affixing of signage or hoarding to the trees
- Preparation of building materials, refueling or disposal of waste materials and chemicals
- Lighting fires
- Movement of pedestrian or vehicular traffic
- Temporary or permanent location of services, or the works required for their installation
- Any other activities that may cause damage to the tree

NOTE: If access, encroachment or incursion into the TPZ is deemed essential, prior authorisation is required by the Site Arborist.

1.3 Site Management

Materials, waste storage, and temporary services shall not be located within the TPZ.

1.4 Scaffolding

Where possible, scaffolding shall not be located within the TPZ. Scaffolding shall not be in contact with the tree. As necessary, this shall be achieved by erecting scaffolding around branches. Branches shall be tied back and protected as deemed necessary by the Project Arborist. Refer to Typical Tree Protection Details (5) (Appendix 6).

1.5 Works within the Tree Protection Zones

In some cases works within the TPZ may be authorized by the determining authority. **These works shall be supervised by the Project Arborist**. When undertaking works within the TPZ, care should be taken to avoid damage to the tree's root system, trunks and lower branches.

p. 0404 424 264 f. 02 9012 0924 po box 146 summer hill 2130 info@treeiQ.com.au abn 62 139 088 832 If roots (>25mmø) are encountered during the demolition, excavation and construction works, these roots must be retained in an undamaged condition and advice sought from the Project Arborist. Adjustment of final levels and design shall remain flexible to enable the retention of roots (>25mmø) where deemed necessary by the Project Arborist.

1.6 Ground Protection

Where deemed necessary by the Project Arborist, machinery movements shall be restricted to areas of existing pavement or from areas of temporary ground protection such as ground mats or steel road plates. Refer to Typical Tree Protection Details (3) (Appendix 6).

1.7 Trunk Protection

Trunk protection shall be installed onto Trees 65-67, 75-78, 80, 81 and 84. Trunk protection shall be installed by wrapping padding (either carpet underlay or 10mm thick jute geotextile mat) around the trunk and first order branches to a minimum height of 2m. Timber battens (90 x 45mm) spaced at 150mm centres shall be strapped together and placed over the padding. Timber battens must not be fixed to the trees. Refer to Typical Tree Protection Details (3) (Appendix 6).

Branch protection shall be installed as deemed necessary by the Project Arborist.

1.8 Structure & Pavement Demolition

Demolition of existing structures/pavement within the TPZ shall be supervised by the Project Arborist. Machinery is to be excluded from the TPZ unless operating from the existing slabs, pavements or areas of ground protection (refer to Section 1.6). Machinery should not contact the tree's roots, trunk, branches and crown.

The existing pavement shall be carefully lifted by hand to minimise damage to the existing sub-base and to prevent damage to tree roots. Wherever possible, the existing sub-base material shall remain in-situ.

When removing slab sections within TPZ, machinery shall work backwards out of the TPZ to ensure machinery remains on undemolished sections of slab at all times. Wherever possible, footings or elements below grade shall be retained to minimise disturbance to the tree's roots.

Where deemed necessary by the Project Arborist, the structures shall be shattered prior to removal with a hand-operated pneumatic/electric breaker.

If roots (>25mmø) are encountered during the demolition works, these roots must be retained in an undamaged condition and advice sought from the Project Arborist. Exposed roots shall be protected from direct sunlight, drying out and extremes of temperature by covering with a 10mm thick jute geotextile fabric. The geotextile fabric shall be kept in a damp condition at all times. Where the Project Arborist determines that the tree is using underground elements (i.e footings, pipes, rocks etc.) for support, these elements shall be left in-situ.

1.9 Pavement/Kerb Installation

Installation of the pavements and sub-base within the TPZ shall be supervised by the Project Arborist. The new surfaces and sub-base materials shall be placed at or above grade to minimise excavations and retain roots (unless prior root mapping results show above sensitive construction to be unnecessary).

If roots (>25mmø) are encountered during the installation of the new sub-base and surfaces, these roots must be retained in an undamaged condition and advice sought from the Project Arborist. Adjustment of final levels and design shall remain flexible to enable the retention of structural roots (>25mmø) where deemed necessary by the Project Arborist.

New sub-base material shall be a 20mm no-fines road base (Benedict Sand & Gravel - Product Code 20NF/RB or similar approved material). Recycled concrete aggregates shall not be used to avoid raising soil pH levels.

If required, bedding sand shall be a washed river sand (recycled crushed paving blends shall not be used). The bedding sand shall be consolidated with a pedestrian-operated plate compactor only. If possible, the pavement material shall be permeable.

Where required, new kerbs within the TPZ should be modified to bridge tree roots (>25mmø) unless root pruning is approved and undertaken by the Project Arborist.

28 | Page

1.10 Underground Services

Underground service installation within the TPZ shall be supervised by the Project Arborist.

The installation of underground services shall be located outside of the TPZ. Where this is not possible, they shall be installed using either hydrovac or hand excavation methods with the services installed around/below roots (>25mmø, or as determined by the Project Arborist).

Alternatively, boring methods may be used for underground service installation where the installation depth is greater than 800mm below existing grade. Excavations for starting and receiving pits for boring equipment shall be located outside of the TPZ or located to avoid roots (>25mmø, or as determined by the Project Arborist).

1.11 Excavations, Root Protection & Root Pruning

Excavations and root pruning within the TPZ shall be supervised by the Project Arborist. Excavations within the TPZ shall be avoided wherever possible.

Excavations within the TPZ shall be undertaken by hand or using hydro vacuum excavation methods (or similar approved device) to protect tree roots. If there is any delay between excavation works and backfilling, exposed roots shall be protected from direct sunlight, drying out and extremes of temperature by covering with a 10mm thick jute mat. The mat shall be kept in a damp condition at all times.

No over-excavation, battering or benching shall be undertaken beyond the footprint of any structure unless approved by the Project Arborist. Hand excavation and root pruning shall be undertaken along the excavation line prior to the commencement of mechanical excavation to prevent tearing and shattering damage to the roots from excavation equipment.

Roots (>25mmø) shall be pruned by the Project Arborist only. Roots (<25mmø) may be pruned by the Principal Contractor. Root pruning shall be undertaken with clean, sharp secateurs or a pruning saw to ensure a smooth wound face, free from tears.

Damaged roots shall be pruned behind the damaged tissues with the final cut made to an undamaged part of the root.


1.12 Footings within the TPZ

Footing installation within TPZ areas shall be supervised by the Project Arborist. Other than for the isolated piers, all other parts of the structure shall be installed above grade.

Drilling/piling machinery shall be excluded from the TPZ unless operating from an area where ground protection has been installed (refer to Section 1.6) or from the existing slabs or pavements. Drilling/piling machinery shall be of a suitable size to not damage the trees' roots, trunk, branches and crown. No clearance pruning is permitted to allow for machinery access. Machinery shall work in conjunction with an observer to ensure that adequate clearance from trees is maintained at all times.

1.13 Plant Installation

Plant installation within the TPZ shall be undertaken using hand tools and roots (>25mmø) shall be protected. No mechanical cultivation/ripping of soils shall be undertaken within the TPZ.



Tree Protection Fencing

