### ONSITE STORMWATER DETENTION DESIGN

### Project: KAREENA PRIVATE HOSPITAL EXTENSION

### OSD No: 1 Description: Under ground tank, detention volume = 32.5 cum., orifice dia.=202mm

### Stage - Storage relationship:

Catchment Areas:

H (RL)	Vol. (m3)				
34.2	0				
34.4	14.45				
34.6	28.88				
34.65	32.5				
34.7	32.6				
35.1	32.9				
Tank plan area (m2) = 72.2					

	Predev	reloped	Direct	runoff	Proposed with OSD		
Area (ha)	0.19	0.19253		0	0.19253		
	Paved	Grassed	Paved	Grassed	Paved	Grassed	
% of Area	37	63	0	0	84.5	15.5	
Constant Time (mins)	2	2	0	0	6	2	
Flow Path length (m)	50	60	8	0	75	10	
Flow path Slope (%)	2	2	1	0	1	2	
Flow path roughness	0.013	0.3	0	0	0.013	0.3	
Lag (mins)		0		0	0	0	

### Results:

		EXISTING	POST DEVEL.	PERMISSIBLE	POST DEVEL.	PEAK	POST DEVEL.	PEAK VOL.	Comments
		PREDEV.	DIRECT	SITE	OSD PEAK	OVERFLOW	PEAK TOTAL	OSD	
ARI	STORM	FLOWS	FLOWS	DISCHARGE	FLOW	FROM OSD	<b>FLOWS FROM</b>		
							OSD		
		cum/s	cum/s	cum/s	cum/s	cum/s	cum/s	m3	
5	25	0.045	0.000	0.045	0.044	0.000	0.044	10.19	34.54 - PSD adopted
5	30	0.041	0.000	0.041	0.045	0.000	0.045	8.79	34.54
5	90	0.042	0.000	0.042	0.045	0.000	0.045	5.04	34.53
10	25	0.053	0.000	0.053	0.045	0.000	0.045	15.86	34.55 - PSD adopted
10	30	0.049	0.000	0.049	0.045	0.000	0.045	14.32	34.55
10	90	0.051	0.000	0.051	0.045	0.000	0.045	11.55	34.54
20	25	0.064	0.000	0.064	0.045	0.001	0.046	23.78	34.56 - PSD adopted
20	90	0.062	0.000	0.062	0.045	0.000	0.045	22.99	34.55
50	25	0.073	0.000	0.073	0.046	0.015	0.061	28.59	34.6
50	90	0.075	0.000	0.075	0.047	0.019	0.066	29.59	34.61 - PSD adopted
100	25	0.084	0.000	0.084	0.049	0.028	0.077	31.54	34.58
100	30	0.079	0.000	0.079	0.048	0.025	0.073	30.97	34.63
100	60	0.082	0.000	0.082	0.050	0.033	0.083	32.52	34.65
100	90	0.087	0.000	0.087	0.050	0.031	0.081	32.18	34.64 - PSD Adopted

### Comments:

Head over outlet=0.45 mMax PSD =0.045 cum/sSuggested Orifice size0.202 m

061777 DRAINS SUMMARY.xls

### **ONSITE STORMWATER DETENTION DESIGN**

### Project: KAREENA PRIVATE HOSPITAL EXTENSION

### OSD No: 2 Description: Under ground tank, detention volume = 3 cum., orifice dia.=120mm

### Stage - Storage relationship:

### Catchment Areas:

H (RL)	Vol. (m3)				
33.2	0				
33.4	0.75				
33.6	1.50				
33.8	2.3				
34	3				
34.15	3.1				
Tank plan area $(m2) = 3.75$					

	Predev	veloped	Direc	t runoff	Proposed with OSD		
Area (ha)	0.0	0.0435		0	0.0435		
	Paved	Grassed	Paved	Grassed	Paved	Grassed	
% of Area	62	38	0	0	79.3	20.7	
Constant Time (mins)	3	3	0	0	1	1	
Flow Path length (m)	12	5	0	0	12	5	
Flow path Slope (%)	1	1	0	0	1	1	
Flow path roughness	0.013	0.3	0	0	0.013	0.3	
Lag (mins)		0		0	0	0	

### Results:

	OTODM	EXISTING PREDEV.	POST DEVEL. DIRECT	SITE	OSD PEAK	PEAK OVERFLOW	POST DEVEL. PEAK TOTAL	PEAK VOL. OSD	Comments
ARI	STORM	FLOWS	FLOWS	DISCHARGE	FLOW	FROM OSD	FLOWS FROM OSD		
		cum/s	cum/s	cum/s	cum/s	cum/s	cum/s	m3	
5	25	0.017	0.000	0.017	0.017	0.000	0.017	1.41	33.58 - PSD adopted
10	25	0.020	0.000	0.020	0.019	0.000	0.019	1.76	33.67 - PSD adopted
20	25	0.023	0.000	0.023	0.022	0.000	0.022	2.24	33.8 - PSD adopted
50	90	0.024	0.000	0.024	0.023	0.000	0.023	2.55	33.88 - PSD adopted
100	90	0.027	0.000	0.027	0.027	0.000	0.027	3.04	34.05 - PSD Adopted

### Comments:

Head over outlet=	
Max PSD =	
Suggested Orifice size	

0.85 m 0.017 cum/s 0.120 m



# PRELIMINARY



FOR NOTES AND LEGENDS

REFER TO DRAWING No C01.

KAREENA PRIVATE HOSPITAL

EROSION AND SEDIMENT CONTROL PLAN

P1 FOR COUNCIL DA

Rev Description

Sheet Subject

Architect



AL DH 16-03-07





8 2 8









8 2 8









Architect HASSE ARCHITE	LL CTS ADDRESS	
	<b>TaylorThon</b> Consulting Engineers 48 Chandos Street St.Le T: +61 2 9439 7288 F: +6	onards NSW 20
	Taylor Thomson Whitting (NSW) Pt	y Ltd A.C.N. 113 578
Scale : B1	Drawn	Author
1:200	DH	
Job No	Dra	awing No
0617	77 C	;02
Plot File Crea	ated: Mar 16, 2007 - 5:26pm	



# AL DH 16-03-07 Eng Draft Date





### GENERAL NOTES

- 1. Contractor must verify all dimensions and existing levels on site prior SURVEY to commencement of works. Any discrepancies to be reported to the Origin of levels Engineer
- 2. Strip all topsoil from the construction area. All stripped topsoil shall be disposed of off-site unless directed otherwise.
- 3. Make smooth connection with all existing works. 4. Compact subgrade under buildings and pavements to minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1.
- Compaction under buildings to extend 2m minimum beyond building footprint. 5. All work on public property, property which is to become public property, or any work which is to come under the control of the
- Statutory Authority is to be carried out in accordance with the requirements of the relevant Authority. The Contractor shall obtain these requirements from the Authority. Where the requirements of the Authority are different to the drawings and specifications, the requirements of the Authority shall be applicable. 6. For all temporary batters refer to geotechnical recommendations.

### REFERENCE DRAWINGS

1. These drawings have been based from, and to be read in conjunction with the following Consultants drawings. Any conflict to the drawings

must	be notified	immediately	10	uie	Ligineer.		
<u>Consultant</u>	<u>Dwg</u>	<u>Title</u>			<u>Dwg No</u>	<u>Rev</u>	<u>Date</u>

## <u>PIT SCHEDULE</u>

Note: Grate size does not necessarily reflect pit size, refer pit type details, shown on detail sheets - C???

Туре	Description	Cover (Clear Opening)	Number
A	Kerb inlet pit 900 lintel	450 x 900 Class D galvanised mild steel grate hinged to frame	????????
В	Surface inlet pit	600 x 900 Class D galvanised mild steel grate hinged to frame	????????
С	Junction pit	600 x 900 Class D cast iron cover with concrete infill	????????
D		Existing pit to be demolished and removed	????????
E		Existing pit to remain	?????????

### STORMWATER DRAINAGE NOTES

- 1 Stormwater Design Criteria :
- (A) Average recurrence interval 1:100 years for roof drainage to first external pit
- 1:20 years for paved and landscaped areas (B) Rainfall intensities —
- Time of concentration: 5 minutes
- 1:100 years = 261 mm/hr
- 1:20 years = 202 mm/hr (C) Runoff coefficients -
- Roof areas: C100 = 1.08
- Roads and paved areas:  $C_{20} = 0.91$ Landscaped areas: C20 = 0.58
- 2. Pipes 300 dia and larger to be reinforced concrete Class "2" approved spigot and socket with rubber ring joints U.N.O.
- 3. Pipes up to 300 dia shall be sewer grade uPVC with solvent welded joints.
- 4. Equivalent strength VCP or FCP pipes may be used subject to approval.
- 5. Precast pits may be used external to the building subject
- to approval by X 6. Enlargers, connections and junctions to be manufactured
- fittings where pipes are less than 300 dia.
- 7. Where subsoil drains pass under floor slabs and vehicular
- pavements, unslotted uPVC sewer grade pipe is to be used. 8. Grates and covers shall conform with AS 3996-2006, and
- AS 1428.1 for access requirements.
- 9. Pipes are to be installed in accordance with AS 3725. All bedding to be type H2 U.N.O.
- 10. Care is to be taken with levels of stormwater lines. Grades
- shown are not to be reduced without approval. 11. All stormwater pipes to be 150 dia at 1.0% min fall U.N.O.
- 12. Subsoil drains to be slotted flexible uPVC U.N.O. 13. Adopt invert levels for pipe installation (grades shown are

# only nominal).

- <u>SITEWORKS NOTES</u>
- 1. All basecourse material to comply with RTA specification No 3051 and compacted to minimum 98% modified standard dry density in
- accordance with AS 1289 5.2.1.
- 2. All trench backfill material shall be compacted to the same density as the adjacent material.
- 3. All service trenches under vehicular pavements shall be backfilled with an approved select material and compacted to a minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1

## SURVEY AND SERVICES INFORMATION

- Datum of levels : A.H.D. AUSTRALIAN HEIGHT DATUM Coordinate system : <u>ISG OR MGA OR LOCAL</u> Survey prepared by
- CONTACT THE SURVEYOR Setout Points CONTACT THE SURVEYOR

Taylor Thomson Whitting does not guarantee that the survey information shown on these drawings is accurate and will accept no liability for any inaccuracies in the survey information provided to us from any cause

### <u>UNDERGROUND SERVICES - WARNING</u>

whatsoever.

The locations of underground services shown on Taylor Thomson Whittings drawings have been plotted from diagrams provided by service authorities. This information has been prepared solely for the authorities own use and may not necessarily be updated or accurate. The position of services as recorded by the authority at the time of installation may not reflect changes in the physical environment subsequent to installation.

Taylor Thomson Whitting does not guarantee that the services information shown on these drawings shows more than the presence or absence of services, and will accept no liability for inaccuracies in the services information shown from any cause whatsoever. The Contractor must confirm the exact location and extent of services prior to construction and notify any conflict with the drawings immediately to the Engineer/Superintendent.

The contractor is to get approval from relevant the state survey department, to remove any survey mark. This includes but is not limited to; State Survey Marks (SSM), Permanent Marks (PM), cadastral reference marks or any other survey mark which is to be removed or adjusted in any way. Taylor Thomson Whitting plans do not indicate the presence of any

survey mark. The contractor is to undertake their own search.

### EROSION AND SEDIMENT CONTROL NOTES

I. All work shall be generally carried out in accordance with (A) Local authority requirements, (B) EPA — Pollution control manual for urban stormwater,

- (C) Department of conservation and land management manual-"Urban Erosion & Sediment Control".
- . Erosion and sediment control <u>drawings and notes</u> are provided for the whole of the works. Should the Contractor stage these works then the design may require to be modified. Variation to these details may require to be approved by the relevant authorities. The erosion and sediment control **plan** shall be implemented and adopted to meet the varying situations as work on site progresses.
- Maintain all erosion and sediment control devices to the satisfaction of the superintendent and the local authority. 4. When stormwater pits are constructed prevent site runoff entering
- the pits unless silt fences are erected around pits. Minimise the area of site being disturbed at any one time. 6. Protect all stockpiles of materials from scour and erosion. Do not
- stockpile loose material in roadways, near drainage pits or in watercourses.
- All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site conditions.
- 8. Control water from upstream of the site such that it does not enter the disturbed site. 9. All construction vehicles shall enter and exit the site via the
- temporary construction entry/exit. 10. All vehicles leaving the site shall be cleaned and inspected before
- leavina. 1. Maintain all stormwater pipes and pits clear of debris and
- sediment. Inspect stormwater system and clean out after each storm event. 2. Clean out all erosion and sediment control devices after each storm event.

## <u>Sequence Of Works</u>

- . Prior to commencement of excavation the following soil
- management devices must be installed. 1. Construct silt fences below the site and across all potential runoff sites.
- .2. Construct temporary construction entry/exit and divert runoff to suitable control systems.
- .3. Construct measures to divert upstream flows into existing
- stormwater system. .4. Construct sedimentation traps/basin including outlet control and overflow.
- .5. Construct turf lined swales. 1.6. Provide sandbag sediment traps upstream of existing pits. Construct geotextile filter pit surround around all proposed pits
- as they are constructed. On completion of pavement provide sand bag kerb inlet sediment
- traps around pits. Provide and maintain a strip of turf on both sides of all roads after the construction of kerbs.





DD — Dish drain →・→ I→ Stormwater pit, flow direction and line with



GD Grated drain Subsoil drainage line (100 dia)

Flushing point



WPJ

Wheelstop Blockwork retaining wall Brickwork retaining wall Dowelled expansion joint Weakened plane joint — Expansion joint \_\_\_\_\_TKJ\_\_\_\_\_ Tied keyed joint < - <--- <--- Overland flow path

Invert level upstream

Pipe size and class

Flow (Litres per second)

Invert level downstream

Pipe grade

## EROSION AND SEDIMENT CONTROL LEGEND

Batter — x — x — Siltation fence Stormwater pit with Geotextile filter surround Hay bale barriers  $\mathcal{A}$ Sandbag sediment trap ---- --- Catch drain --- <--- Overland flow path

### KERBING NOTES

are shown.

- Includes all kerbs, gutters, dish drains, crossings and edges.
- 1. All kerbs, autters, dish drains and crossings to be constructed on minimum 75mm granular basecourse compacted to minimum 98% modified maximum dry density in accordance with AS 1289 5.2.1. 2. Expansion joints (EJ) to be formed from 10mm compressible cork
- filler board for the full depth of the section and cut to profile. Expansion joints to be located at drainage pits, on tangent points of curves and elsewhere at 12m centres except for integral kerbs where the expansion joints are to match the joint locations in slabs. . Weakened plane joints to be min 3mm wide and located at 3m centres except for integral kerbs where weakened plane joints are to
- match the joint locations in slabs. 4. Broomed finished to all ramped and vehicular crossings, all other kerbing or dish drains to be steel float finished.
- 5. In the replacement of kerbs Existing road pavement is to be sawcut 900mm from lip of gutter. Upon completion of new kerbs, new basecourse and surface is to be laid 900mm wide to match existing materials and thicknesses. Existing allotment drainage pipes are to be built into the new kerb with a 100mm dia hole. Existing kerbs are to be completely removed where new kerbs

SURVEY LEGEND	
+18.48	Surface level
19	Contour
	Kerb line
	Batter
[]	Retaining wall
SW	Stormwater drainage line
⊤	Telecommunications line
G	Gas line
W	Water main
S	Sewer line
EASEMENT FOR(m WIDE)	Easement
/	Fence
X	Tree to be removed/be retained
⊂ SGN	Boundary Sign
E H	Hydrant
MH	Manhole
G	Gas
SV	Stop Valve
W	Water
TEL	Telstra
TRAP	Trap
	Gully
	Grate
S E	Sewer Manhole Energy Australia (Electricity)
o elp	Electric Light Pole
O L	Traffic Light
II TLL	Traffic Light Lid
TLB	Traffic Light Box
ТВ	Telephone Box
o PKM	Parking Meter
□PM 1234	Permanent Mark
<b>BM</b> 51.10	Bench Mark
- 🕀 ВН О	Borehole
-TP No	Test Pit
o FC	Fuel Cock
O FL	Flood Light
	Lamp Hole
O BUB	Bubbler Letter Box
LB FP	Flag Pole
FP BOX	Flag Pole Box
O BOL	Bollard
SEAT	Seat
BIN	Bin

Kerb Outlet

Monorail Pylon

0 K0

# PRELIMINARY

Job No 061777 Plot File Created: Mar 16, 2007 - 5:26pm

Taylor Thomson Whitting (NSW) Pty Ltd A.C.N. 113 578 377 Drawn Drawing No C00

Architect HASSELL

ARCHITECTS ADDRESS

N

Scale : B1

NOTES & LEGENDS

Consulting Engineers

Sheet Subject

**KAREENA PRIVATE HOSPITAL** 

P2 FOR COUNCIL DA AL DH 16-03-07 AL DG 14-02-07 PRELIMINARY Eng Draft Date Rev Description Project

FOR NOTES AND LEGENDS REFER TO DRAWING No C01.

# TaylorThomsonWhitting

48 Chandos Street St.Leonards NSW 2065 T: +61 2 9439 7288 F: +61 2 9439 3146 ttwsyd@ttw.com.au

Authorised

