

Civil



TaylorThomsonWhitting

---

# 128 Herring Road Residential Precinct Development - Road Works and Stormwater.

---

for Lipman Properties Pty Ltd

15<sup>th</sup> September 2010

TTW Job No: 091679

**Taylor Thomson Whitting (NSW) Pty Ltd Consulting Engineers** ACN 113 578 377  
48 Chandos Street St Leonards NSW 2065 PO Box 738 Crows Nest 1585  
T 61 2 9439 7288 F 61 2 9439 3146 ttwsyd@ttw.com.au [www.ttw.com.au](http://www.ttw.com.au)

This document is copyright and is the property of Taylor Thomson  
Whitting (NSW) Pty Ltd and must not be used without authorisation



Quality  
Endorsed  
Company  
ISO 9001  
QEC 6625/01

SYDNEY

CANBERRA

MELBOURNE

QEC 22375

## Table of Contents

	Page
1. INTRODUCTION.....	2
2. PROPOSED DEVELOPMENT.....	4
3. ROADWORKS.....	5
4. STORMWATER.....	5
APPENDIX A ROAD & STORMWATER CIVIL PLANS.....	7

## 1. INTRODUCTION

This report is submitted by Engineering Consultancy firm Taylor Thomson Whitting (TTW) who have been engaged by Lipman Properties Pty Ltd.

The objective of this report is to provide a stormwater and road infrastructure plan which defines the civil engineering requirements of the proposed development site with respect to road access, stormwater drainage, detention and stormwater reuse provision, water quality treatment measures and erosion and sediment control requirements.




### Existing Site

This report is intended to identify civil engineering issues for the 17,173 square metre development site.

The staged subdivision and staged development construction proposed will require detailed approval for each stage to ensure the development is compliant with the development consent requirements.


Each development stage will be designed to comply with the development consent requirements.



#### Local Environment Plan for the local area


The site is currently zoned B4 mixed use based on the Ryde Council LEP 2008. The site is currently part of the Morling College campus. The Morling College site will be subdivided to accommodate the proposed development in three stages to form 7 Lots. The site is next to Macquarie University.

## 2. PROPOSED DEVELOPMENT



The proposed development consists of five residential buildings with road access from Herring Road.

The proposed road is approximately 160m long. The proposed road is generally in accordance with Ryde Council's DCP 2006 Macquarie Park Corridor Plan, type 3 road from chapter 5.0 of the Public Domain requirement.



130m of the road and four of the residential building development sites (Buildings B, C, D and E) drain to University Creek.

One of the five residential building sites (Building A – Lot 10) and 30m of the road will drain east toward Herring Road and connect into the Herring Road street drainage as per the fall of the proposed road connection.

## **2. ROADWORKS**

The road works will be required to ensure adequate allowance is made for the residential traffic, garbage trucks and general traffic in accordance with AS2890.

Road levels are intended to match the existing road and ground levels to minimise the extent of retaining works and filling required.

Stormwater drainage for both construction stages of the roadworks of the development will be provided.

## **3. STORMWATER WORKS**

The majority of the 128 Herring Road development falls to the west toward University Creek which is within the site boundary. The first stage development building (Building A) is intended to drain to Herring Road through a detention and retention system.

The flood impact of the University Creek watercourse requires that development is to be above the 100 year flood zone with suitable freeboard, and outside the riparian zone.

TTW recommend stormwater detention and reuse storage be provided for the development to ensure there is no increase of stormwater peak flow downstream due to the proposed development.

Roof water for each development stage is drained to a reuse tank to store rainwater for irrigation to landscape areas.

The overflow from the reuse tank, surface runoff for the podium of each stage and air conditioner condensate drains to a stormwater detention tank for each stage sized in accordance with Council's Stormwater Management Development Control Plan.

An oil and silt arrestor and gross pollutant trap has been provided for each development stage prior to discharge to the street drainage system.

A first flush bio-swale treatment has been proposed prior to the discharge to University Creek on the western side of the site.

Water quality modelling has been undertaken using Music to confirm the pollution reduction rates achieved by the development to limit the impact of the proposed development on downstream water quality.

TTW recommend the core riparian zone setback (CRZ) requirements be 10m from the top of bank as per the requirement for a first order water course with intermittent flow characteristics. The vegetation buffer has been nominated as 20m from the top of bank for both the east and west sides of the creek (including the CRZ).

By:

**TAYLOR THOMSON WHITTING (NSW) PTY LTD**



**STEPHEN BRAIN**  
**Technical Director - Civil**

*P:\2009\0916\091679\Reports\TTW\100916 Civil Works Report.docx*

# **APPENDIX A**

## **ROAD & STORMWATER CIVIL PLANS**

B1 0 1 2 3 4 5 6 7 8 9 10


Plot File Created: Sep 29, 2010 - 12:53pm



CONTRACTOR IS TO LOCATE  
ALL EXISTING SERVICES PRIOR  
TO THE COMMENCEMENT OF  
WORK

FOR NOTES AND LEGENDS  
REFER TO DRAWING No C101

LEVELS SHOWN THUS - F10.00\* -  
ARE TO BE CONFIRMED PRIOR TO THE  
COMMENCEMENT OF WORKS



P8	ISSUE FOR EA SUBMISSION	SB	DH	29.09.10
P7	ISSUE FOR EA SUBMISSION	SB	DH	15.09.10
P6	ISSUE FOR COORDINATION	SB	DH	13.09.10
P5	ISSUE FOR EA SUBMISSION	SB	DH	06.05.10
P4	ISSUE FOR COMMENTS	SB	DH	05.03.10
P3	ISSUE FOR COMMENTS	SB	DH	26.02.10
P2	ISSUE FOR COMMENTS	SB	DH	23.02.10
P1	PRELIMINARY	SB	OR	10.02.10

Project  
**RESIDENTIAL DEVELOPMENT  
128 HERRING ROAD,  
MACQUARIE PARK**

Sheet Subject  
**BUILDING A CONSTRUCTION  
- STORMWATER CONCEPT  
PLAN**

Architect  
**TURNER + ASSOCIATES**  
Level 1, 410 Crown Street,  
Surry Hills NSW 2010



Client  
**TaylorThomsonWhitting**  
Consulting Engineers  
44 Chancery Street, St Leonards NSW 2055  
T: +61 2 9439 7288 F: +61 2 9439 3145 ttwytd@ttw.com.au  
TaylorThomsonWhitting Pty Ltd, ACN 411133177

Scale: B1 Drawn Authorised  
1:300 DH

Job No Drawing No Revision  
**091679 C102 P8**


Plot File Created: Sep 29, 2010 - 12:53pm



CONTRACTOR IS TO LOCATE  
ALL EXISTING SERVICES PRIOR  
TO THE COMMENCEMENT OF  
WORK

FOR NOTES AND LEGENDS  
REFER TO DRAWING No C101

LEVELS SHOWN THUS - F10.00" -  
ARE TO BE CONFIRMED PRIOR TO THE  
COMMENCEMENT OF WORKS



NOTE: FINAL LAYOUT OF  
RE-USE TANK TO BE CONFIRMED  
RE-USE VOLUME = 230m<sup>3</sup>  
12.8m DEEP x 4m (W) x 4.5m (L)  
DETENTION VOLUME = 58m<sup>3</sup>  
1.2m DEEP x 4m (W) x 12.1m (L)

PLAN  
SCALE 1: 200

SCALE 1:200 0 2 4 6 8 10  
AT ORIGINAL SIZE

P7	ISSUE FOR EA SUBMISSION	SB	DH	29.08.10
P6	ISSUE FOR EA SUBMISSION	SB	DH	15.08.10
P5	ISSUE FOR COORDINATION	SB	DH	13.08.10
P4	ISSUE FOR EA SUBMISSION	SB	DH	06.05.10
P3	ISSUE FOR COMMENTS	SB	DH	05.03.10
P2	ISSUE FOR COMMENTS	SB	DH	26.02.10
P1	ISSUE FOR COMMENTS	SB	DH	23.02.10

Rev Description Eng Draft Date

Project

**RESIDENTIAL DEVELOPMENT  
128 HERRING ROAD,  
MACQUARIE PARK**

Sheet Subject  
**BUILDING A CONSTRUCTION  
- SITEWORKS PLAN SHEET 1**


Architect  
**TURNER + ASSOCIATES**  
Level 1, 410 Crown Street,  
Surry Hills NSW 2010



TaylorThomsonWhitting  
Consulting Engineers  
44 Charles Street, St Leonards NSW 2065  
T: +61 2 9439 7288 F: +61 2 9439 3145 twhyt@ttw.com.au  
TaylorThomsonWhitting Pty Ltd, ACN 110 330 977

Scale: B1 Drawn Authorised  
1:200 DH

Job No Drawing No Revision  
**091679 C103 P7**



PLAN  
SCALE 1: 200

SCALE 1:200 0 2 4 6 8 10  
AT ORIGINAL SIZE



CONTRACTOR IS TO LOCATE  
ALL EXISTING SERVICES PRIOR  
TO THE COMMENCEMENT OF  
WORK

FOR NOTES AND LEGENDS  
REFER TO DRAWING No C101

LEVELS SHOWN THUS - F10.00" -  
ARE TO BE CONFIRMED PRIOR TO THE  
COMMENCEMENT OF WORKS

FOR CONTINUATION REFER TO DRAWING No C103

P7	ISSUE FOR EA SUBMISSION	SB	DH	29.09.10
P6	ISSUE FOR EA SUBMISSION	SB	DH	15.09.10
P5	ISSUE FOR COORDINATION	SB	DH	13.09.10
P4	ISSUE FOR EA SUBMISSION	SB	DH	06.05.10
P3	ISSUE FOR COMMENTS	SB	DH	05.03.10
P2	ISSUE FOR COMMENTS	SB	DH	26.02.10
P1	ISSUE FOR COMMENTS	SB	DH	23.02.10

Rev	Description	Eng	Draft	Date
-----	-------------	-----	-------	------

Project

**RESIDENTIAL DEVELOPMENT  
128 HERRING ROAD,  
MACQUARIE PARK**

Sheet Subject

**BUILDING A CONSTRUCTION  
- SITEWORKS PLAN SHEET 2**

Architect  
**TURNER + ASSOCIATES**  
Level 1, 410 Crown Street,  
Surry Hills NSW 2010



TaylorThomsonWhitting  
Consulting Engineers  
44 Charles Street, St Leonards NSW 2065  
T: +61 2 9439 7288 F: +61 2 9439 3145 ttwytd@ttw.com.au  
TaylorThomsonWhitting is a member of the ACCA 110129127

Scale: B1 Drawn Authorised  
1:200 DH

Job No Drawing No Revision  
**091679 C104 P7**

Plot File Created: Sep 29, 2010 - 12:53pm



CONTRACTOR IS TO LOCATE ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF WORK



#### EROSION AND SEDIMENT CONTROL NOTES

- All work shall be generally carried out in accordance with:  
(A) Local authority requirements,  
(B) EPA - Pollution control manual for urban stormwater,  
(C) Department of conservation and land management manual - "Urban Erosion & Sediment Control".
- Erosion and sediment control **drawings and notes** are provided for the whole of the works. Should the Contractor stage these works then the design may require to be modified. Variation to these details may require to be approved by the relevant authorities. The erosion and sediment control plan shall be implemented and adopted to meet the varying situations as work on site progresses.
- Maintain all erosion and sediment control devices to the satisfaction of the superintendent and the local authority.
- When stormwater pits are constructed prevent site runoff entering the pits unless silt fences are erected around pits.
- Minimise the area of site being disturbed at any one time.
- Protect all stockpiles of materials from scour and erosion. Do not stockpile loose material in roadways, near drainage pits or in watercourses.
- All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site conditions.
- Control water from upstream of the site such that it does not enter the disturbed site.
- All construction vehicles shall enter and exit the site via the temporary construction entry/exit.
- All vehicles leaving the site shall be cleaned and inspected before leaving.
- Maintain all stormwater pipes and pits clear of debris and sediment. Inspect stormwater system and clean out after each storm event.
- Clean out all erosion and sediment control devices after each storm event.


#### Sequence Of Works

- Prior to commencement of excavation the following soil management devices must be installed.
  - Construct silt fences below the site and across all potential runoff sites.
  - Construct temporary construction entry/exit and divert runoff to suitable control systems.
  - Construct measures to divert upstream flows into existing stormwater system.
  - Construct sedimentation traps/basin including outlet control and overflow.
  - Construct turf lined swales.
  - Provide sandbag sediment traps upstream of existing pits.
  - Construct geotextile filter pit surround around all proposed pits as they are constructed.
- On completion of pavement provide sand bag kerb inlet sediment traps around pits.
- Provide and maintain a strip of turf on both sides of all roads after the construction of kerbs.


#### EROSION AND SEDIMENT CONTROL LEGEND




PLAN  
SCALE 1: 300




SILTATION FENCE DETAIL  
SCALE 1: 20




TYPICAL SECTION THROUGH CATCH DRAIN  
SCALE 1: 20




GEOTEXTILE FILTER PIT SURROUND  
NTS




GEOTEXTILE PIT FILTER  
NTS




SEDIMENTATION TRAP  
NTS




SANDBAG KERB INLET SEDIMENT TRAP - TYPE B  
NTS



SECTION 20  
SCALE 1: 20



TEMPORARY CONSTRUCTION VEHICLE EXIT  
NTS



KERB INLET SEDIMENT TRAP  
SCALE 1: 20

P6	ISSUE FOR EA SUBMISSION	SB	DH	28.08.10
P5	ISSUE FOR EA SUBMISSION	SB	DH	15.09.10
P4	ISSUE FOR COORDINATION	SB	DH	13.09.10
P3	ISSUE FOR EA SUBMISSION	SB	DH	06.05.10
P2	ISSUE FOR COMMENTS	SB	DH	05.03.10
P1	ISSUE FOR COMMENTS	SB	DH	04.03.10
Rev	Description	Eng	Draft	Date

Project  
**RESIDENTIAL DEVELOPMENT  
128 HERRING ROAD,  
MACQUARIE PARK**

Sheet Subject  
**BUILDING A CONSTRUCTION  
- EROSION AND SEDIMENT  
CONTROL PLAN**

Architect  
**TURNER + ASSOCIATES**  
Level 1, 410 Crown Street,  
Surry Hills NSW 2010


Client  
**LIPMAN**  
the obvious choice  
in property

TaylorThomsonWhitting  
Consulting Engineers  
44 Charles Street, St Leonards NSW 2055  
T: +61 2 9439 7288 F: +61 2 9439 3145 twhyt@ttw.com.au  
TaylorThomsonWhitting Pty Ltd, ACN 110 330 077

Scale: B1  
1:300  
DH  
Authorised

Job No  
**091679**  
Drawing No  
**C105**  
Revision  
**P6**

Plot File Created: Sep 29, 2010 - 12:54pm



PLAN  
SCALE 1: 400



CONTRACTOR IS TO LOCATE  
ALL EXISTING SERVICES PRIOR  
TO THE COMMENCEMENT OF  
WORK

FOR NOTES AND LEGENDS  
REFER TO DRAWING No C101

P8	ISSUE FOR EA SUBMISSION	SB	DH	29.09.10
P7	ISSUE FOR EA SUBMISSION	SB	DH	15.09.10
P6	ISSUE FOR COORDINATION	SB	DH	13.09.10
P5	ISSUE FOR EA SUBMISSION	SB	DH	06.05.10
P4	ISSUE FOR COMMENTS	SB	DH	05.03.10
P3	ISSUE FOR COMMENTS	SB	DH	26.02.10
P2	ISSUE FOR COMMENTS	SB	DH	23.02.10
P1	PRELIMINARY	SB	OR	08.02.10

Rev Description Eng Draft Date

Project

**RESIDENTIAL DEVELOPMENT  
128 HERRING ROAD,  
MACQUARIE PARK**

Sheet Subject

**BUILDING B CONSTRUCTION  
- OVERALL PLAN**

Architect  
**TURNER + ASSOCIATES**  
Level 1, 410 Crown Street,  
Surry Hills NSW 2010



**TaylorThomsonWhitting**  
Consulting Engineers  
44 Chancery Street, St Leonards NSW 2055  
T: +61 2 9439 7288 F: +61 2 9439 3145 ttwytd@ttw.com.au  
TaylorThomsonWhitting is a subsidiary of TCTA 110129127

Scale: B1 Drawn Authorised  
1:400 DH

Job No Drawing No Revision  
**091679 C202 P8**