



p: +61 404 424 264

f: +61 2 9012 0924

ivm@ivm.net.au www.ivm.net.au

1/9 venus st gladesville 2111 NSW

integrated vegetation management

abn: 62 139 088 832

Project No: MA/ME/10

Report No: MA/ME/AIARTPS/E

ARBORICULTURAL IMPACT ASSESSMENT REPORT & TREE PROTECTION SPECIFICATION

Marrickville Metro

Prepared for:

Site Image Landscape Architects

2nd November 2010

Authors: Anna Hopwood
Dip. Hort (Arboriculture) Dip. Hort (Landscape Design)

Andrew Simpson
B. App Sci (Forestry), Dip. Hort (Arboriculture)
Cert 111 Horticulture (Tree Surgery)

This document contains Standards Australia Ltd copyrighted material that is distributed by SAI Global on Standards Australia Ltd's behalf. It may be reproduced in accordance with the terms of SAI Global Ltd's Licence 1009-c029 to Integrated Vegetation Management Pty Ltd. All licensed copies of this document must be obtained from the Licensee. Standards Australia Ltd's material is not for resale, reproduction or distribution in whole or in part without written permission from SAI Global Ltd: tel +61 2 8206 6355 or copyright@saiglobal.com.



CONTENTS

1.0	INTRODUCTION	3
1.1	Background	3
1.2	Aims	3
2.0	RESULTS	3
2.1	Site Description	3
2.2	Existing Vegetation	4
2.3	Tree Assessment	4
3.0	DISCUSSION	4
3.1	Trees Proposed for Removal	4
3.2	Trees Proposed for Retention	5
4.0	CONCLUSIONS	12
5.0	BIBLIOGRAPHY	14
6.0	APPENDICES	15
	Appendix 1: Methodology	16
	Appendix 2: Tree Assessment Schedule	18
	Appendix 3: Site Survey	30
	Appendix 4: Landscape Plan	31
	Appendix 5: Notes on AS: 4970 (2009)	32
	Appendix 6: General Tree Protection Specification	33
	Appendix 7: Typical Tree Protection Fencing Detail	37

1.0 INTRODUCTION

1.1 Background

This report forms part of a Preferred Project Report (PPR) prepared on behalf of AMP Capital Investors (AMPCI) in respect to the Concept Plan Application under Part 3A of the NSW Environmental Planning and Assessment Act 1979 for the proposed redevelopment of the Marrickville Metro Shopping Centre.

In preparing this report the author is aware of and has taken into account the objectives of the Marrickville Council's *Tree Preservation Order 2007*.

Refer to **Appendix 1: Methodology**.

1.2 Aims

The aims of this report are to:

- Review Council's Policies for applicable conditions regarding the preparation of Arboricultural Reports;
- Conduct a visual assessment of the subject trees and their growing environment;
- Review the supplied plans to determine the impact on the subject trees;
- Where appropriate, recommend the use of sensitive construction methods to minimise the adverse impacts on the subject trees;
- Prepare site specific tree protection measures for the subject trees to be retained.

There is no warranty or guarantee, expressed or implied that the problems or deficiencies regarding the subject trees or the subject site may not arise in the future. Information contained in this report covers only the subject tree that was assessed and reflects the condition of the subject tree at the time of inspection.

2.0 RESULTS

2.1 Site Description

Marrickville Metro Shopping Centre is located at 34 Victoria Road, Marrickville. The existing shopping centre fronts Victoria Road to the north, Murray Street to the east and Smidmore Street to the south, and is adjoined by single storey residential dwellings to the west. The shopping centre is predominantly a single level retail building with car parking located at rooftop level with existing vehicle ramp access via Smidmore Street and Murray Street.



Figure 1: Showing site Location Plan

The land at 13-55 Edinburgh Road is located to the south of Smidmore Street and is bounded by Edinburgh Road and Murray Street. This site is currently used as a warehouse with associated ground level car parking.

The shopping centre is located within an established residential and industrial precinct surrounded by small lot residential housing to the north and west, and predominantly industrial land comprising larger allotments and larger building scales to the south and east.

2.2 Existing Vegetation

Site vegetation consists predominantly of large canopy trees species such as *Lophostemon confertus* (Brush Box), *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig), *Cinnamomum camphora* (Camphor Laurel) and *Celtis* spp. (Celtis).

Figure 2: Showing site vegetation



2.3 Tree Assessment

Eighty-seven (87) trees have been surveyed as part of this assessment. The surveyed trees were assessed as generally being in fair health and structure. Full results of the tree assessment are shown in **Appendix 2: Tree Assessment Schedule**. Tree numbers correlate with the Site Survey attached as **Appendix 3**.

3.0 DISCUSSION

3.1 Trees Proposed for Removal

The supplied plans indicate that seven (7) trees are outlined for removal to accommodate proposed building or vehicular entry footprint.

Of the seven (7) trees outlined above;

- Trees 56, 58-60 and 67 have been allocated a Retention Value of *Consider for Retention*
- Trees 37 and 57 have been allocated a Retention Value of *Priority for Removal*

These trees are discussed in more detail below:

Trees 37 *Celtis sinensis* (Nettle Tree)

Tree 37 has been identified as *Celtis sinensis* (Nettle Tree). This tree has been assessed as being in good health and poor structure due to the presence of a co-dominant inclusion and multiple branch attachments. Tree 37 has moderate Landscape Significance, a Remaining Life Expectancy Range of less than 5 years and has been allocated a Retention Value of *Priority for Removal*.

The supplied plans indicate this tree will need to be removed to accommodate the proposed building footprint extension.


Trees 56-60 *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig)

Trees 56-60 have been identified as *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig) and are located on the outside of the Metro building on the Murray Street frontage.

These trees have generally been assessed as being in fair health due to the presence of small diameter deadwood throughout the canopies and a reduced canopy cover of approximately 60-70% (comparative to the same species growing in ideal site and environmental conditions).

Figure 3: Showing wound with possible decay on Tree 57

The structure of these trees has been assessed being fair to poor due to the presence of mature epicormic growth resultant from lopping. Wounds with possible decay were also noted on several of these trees.



The supplied plans indicate these trees will need to be removed to accommodate the proposed vehicular entry footprint.

Trees 67 *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig)

Tree 67 is positioned on the northern side of Smidmore Road. This tree has been assessed as being in fair health due to the presence of small diameter deadwood throughout its canopy. The structure of this tree has been assessed as being fair due to the presence of co-dominant inclusions. Tree 67 has high Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and has been allocated a Retention Value of *Consider for Retention*.

The supplied plans indicate this tree will need to be removed to accommodate the proposed building footprint extension.

3.2 Trees Proposed for Retention


The supplied plans indicate that eighty (80) trees are proposed for retention. Of these:

- Trees 28, 30, 33-35, 38, 40, 41, 75-77, 81, 82 and 84 have been allocated a Retention Value of *Priority for Retention*.
- Trees 1-20, 25, 27, 32, 36, 43-47, 49-55, 61-66, 69, 72, 78-80, 83, 85, 86 and 87 have been allocated a Retention Value of *Consider for Retention*.
- Trees 21-24 and 26 have been allocated a Retention Value of *Consider for Removal*.
- Trees 29, 31, 39, 42, 48, 68, 70, 71, 73 and 74 have been allocated a Retention Value of *Priority for Removal*.

3.2.1 Major Encroachment - Building Footprint

The supplied plans indicate that works are proposed within the TPZ of ten (10) trees. The extent of these works is considered a *Major Encroachment* as defined by the Australian Standard. The Australian Standard provides for undertaking works within the TPZ when more detailed root investigations have been undertaken or tree sensitive construction methods are to be utilised.

Therefore, further investigation in the form of exploratory root trenching should be undertaken to determine the presence and extent of root spread, and the impact of the proposed development on these trees.



Alternatively, tree sensitive construction techniques and materials such as isolated pier and beam footings or cantilevered slabs should be used within the trees' TPZ. No works should be undertaken with the trees' Structural Root Zone (SRZ).

These trees are discussed in more detail below:

Trees 75, 76, 77, 78, 79, 80 & 81

Trees 75, 76, 77, 78, 79, 80 and 81 have been identified as *Corymbia citriodora* (Lemon-scented Gum) and *Eucalyptus* sp. (Gum Tree) which are Council-managed

trees positioned on the road reserve on the southern side of Smidmore Street. These trees have been assessed as being in good to fair health and good structure.

Figure 4: Looking west showing Trees 75-77

Works within the trees' TPZ include the construction of the retail building, a vehicular entry ramp and paving.

Trees 82, 83 & 84

Trees 82, 83 and 84 have been identified as *Corymbia citriodora* (Lemon-scented Gum) and *Eucalyptus* spp. (Gum Tree) which are Council-managed trees positioned on the road reserve on the southern side of Smidmore Street. These trees have been assessed as being in good health and structure. An existing building is positioned approximately 3m south of these trees and is likely to have impeded the spread of roots to the south.

Works within the trees' TPZ include construction of the retail building and paving.



Figure 5: Showing Tree 84

Canopy pruning may also be required for Trees 75-84 to provide building clearance and for access during construction. All pruning work should be undertaken in accordance with AS4373: *Pruning of Amenity Trees* (2007) and the *Workcover Code of Practice for the Amenity Tree Industry* (1998).

AS4970-Integrated Vegetation Management Pty Ltd- reproduced under copyright Licence number 1009-c029
AS4373-Integrated Vegetation Management Pty Ltd- reproduced under copyright Licence number 1009-c029

All pruning should be carried out by an experienced and qualified Arborist. The Arborist shall hold a minimum qualification equivalent (using the Australian Qualifications Framework) of NSW TAFE Certificate Level 3 or above, in Arboriculture and a NSW TAFE Tree Surgery Certificate or its recognised equivalent. The Arborist shall have a minimum of 3 years experience in practical Arboriculture including demonstrated experience in tree surgery.

3.2.2 Landscape Treatment

The supplied plans indicate that landscape works are proposed within the TPZ of forty-eight (48) trees. The Australian Standard provides for undertaking works within the TPZ when more detailed root investigations have been undertaken or tree sensitive construction methods are to be utilised.

Therefore, further investigation in the form of exploratory root trenching should be undertaken to determine the presence and extent of root spread, and the impact of the proposed development on these trees.

Alternatively, tree sensitive construction techniques and materials such as no-dig designs, permeable pavements and timber decks should be used within the trees' TPZ. No works should be undertaken with the trees' Structural Root Zone (SRZ).

These trees are discussed in more detail below:

Tree 20 *Ficus macrophylla* (Moreton Bay Fig)

Tree 20 has been identified as *Ficus macrophylla* (Moreton Bay Fig). This tree has been assessed as being in fair health due to the canopy being comprised predominately of epicormic growth and the presence of small and large diameter deadwood throughout its canopy. It has been assessed as being in poor structure due to the presence of wounds with possible decay on the main stem and first order branches. Mechanical damage likely the result of lawn mower equipment was also noted on several surface roots.

Figure 6: Showing damage to exposed roots of Tree 20

This tree has a high Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and has been allocated a Retention Value of *Consider for Retention*. It is noted that this is a heritage-listed tree.



Further investigation in the form of an internal diagnostic test should be undertaken if this tree is to be retained. There are a number of instruments used to assess wood defects in trees. All methods should be approached with caution and testing should only be carried out when necessary to establish the 'physical' size/ width of remaining supportive tissue to allow a calculable risk analysis of the tree's stability to be made. Both the testing and the interpretation of the resultant data should always be undertaken by an appropriately qualified consultant.

AS4970-Integrated Vegetation Management Pty Ltd- reproduced under copyright Licence number 1009-c029

Trees 21-27 (Mixed Species)

This group of trees consists of a mixed species planting which is positioned in the northern area of the site, adjacent to the Victoria Road frontage.

Trees 21, 23, 24, 26 and 27 - these trees have been identified as *Celtis sinensis* (Nettle Tree). These trees have low Landscape Significance and have been allocated a Retention Value of *Consider for Removal*.



Tree 22 - this tree has been identified as *Agonis flexuosa* (Willow Myrtle). This tree has been assessed as being poor structure due to the presence of a wound with possible decay and major branch inclusions. This tree has low Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and has been allocated a Retention Value of *Consider for Removal*.

Tree 25 - this tree has been identified as *Cinnamomum camphora* (Camphor Laurel). This tree has been assessed as being in fair health due to the presence of small and large diameter deadwood throughout its canopy and a reduced canopy cover of approximately 70% (comparative to the same species growing in ideal site and environmental conditions). The structure of this tree has been assessed as poor due to the presence of wounds with decay at the base of the stem and throughout the tree.

Figure 7: Showing Tree 25

This tree has high Landscape Significance, a Remaining Life Expectancy Range of less than 5 years and has been allocated a Retention Value of *Consider for Removal*. If this tree is to be retained, internal diagnostic testing should be undertaken to determine the presence and extent of decay.

Tree 28 *Lophostemon confertus* (Brush Box)

Tree 28 has been identified as *Lophostemon confertus* (Brush Box) which is located on the road reserve of Victoria Road and is a Council managed tree. Tree 28 has been assessed as being in fair structure due to the presence of mature epicormic growth resultant from lopping. This tree has high Landscape Significance, a Remaining Life Expectancy range of 15-40 years and has been allocated a Retention Value of *Priority for Retention*.

Figure 8: Showing stem of Tree 28





Tree 29 *Lophostemon confertus* (Brush Box)

Tree 29 has been identified as *Lophostemon confertus* (Brush Box). This tree has been assessed as being in poor structure due to the presence mature epicormic growth and wounds with possible decay on first order branches.

This tree has high Landscape Significance, a Remaining Life Expectancy Range of less than 5 years and has been allocated a Retention Value of *Priority for Removal*. If this tree is to be retained, internal diagnostic testing should be undertaken to determine the presence and extent of decay.

Figure 9: Showing wound with possible decay of Tree 29

Trees 30 *Washingtonia* sp. (Fan Palm)

Tree 30 has been identified as *Washingtonia* sp. (Fan Palm) and has been assessed as being in good health and structure. This tree has high Landscape Significance, a

Remaining Life Expectancy Range of 15-40 years and has been allocated a Retention Value of *Priority for Retention*.

Tree 31 *Celtis sinensis* (Nettle Tree)

Tree 31 has been identified as *Celtis sinensis* (Nettle Tree). This tree has been assessed as being in fair structure due to restricted root volume and girdled roots. Tree 31 has low Landscape Significance, a Remaining Life Expectancy Range of less than 5 years and has been allocated a Retention Value of *Priority for Removal*.

Tree 32 *Schinus molle* var. *areira* (Peppercorn Tree)

Tree 32 has been identified as *Schinus molle* var. *areira* (Peppercorn Tree). This tree has been assessed as being in fair structure due to the presence of basal decay and mature epicormic growth. This tree has high Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and has been allocated a Retention Value of *Consider for Retention*.

Trees 33, 34, 38, 39, 40, 41 & 42 *Lophostemon confertus* (Brush Box)

Trees 33, 34, 35, 38, 39, 40 and 41 have been identified as *Lophostemon confertus* (Brush Box) which are positioned on the road reserve of Victoria Road. These are Council-managed trees which have been assessed as being in good health and fair structure due to the presence of mature epicormic growth resultant from lopping.

Figure 10: Showing lopped points of Brush Box

These trees have high Landscape Significance and a Remaining Life Expectance Range of 15-40 years.



Tree 35 *Lophostemon confertus* (Brush Box)

Tree 35 has been identified as *Lophostemon confertus* (Brush Box) and has been assessed as being in good health and structure. Tree 35 has high Landscape Significance, a Remaining Life Expectancy Range of 15-40 years and has been allocated a Retention Value of *Priority for Retention*.

Tree 36 *Cinnamomum camphora* (Camphor Laurel)

Tree 36 has been identified as *Cinnamomum camphora* (Camphor Laurel). This tree has been assessed as being in good health and fair structure due to the presence of multiple branch attachments and mature epicormic growth. Tree 36 has high Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and has been allocated a Retention Value of *Consider for Retention*.

Trees 43-55 and 61-64 *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig)

Trees 43-55 and 61-64 have been identified as *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig) which are located on the outside of the Metro building on the Murray Street frontage. These trees have been assessed as being in fair health due to the presence of small diameter deadwood throughout the canopies and a reduced canopy cover of approximately 60-70% (comparative to the same species growing in ideal site and environmental conditions).



The structure of these trees has been assessed as fair to poor due to the presence of mature epicormic growth resultant from lopping. Wounds with possible decay were also noted at branch attachments on the main stem of several of these trees.

Figure 11: Showing mature epicormic growth, a split branch and wounds with decay on Tree 48

Trees 65 & 66 *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig)

Trees 65 and 66 are positioned on the northern side of Smidmore Road. These trees have been assessed as being in fair health due to the presence of small diameter deadwood throughout their canopies. The structure of these trees has been assessed as fair due to the presence of co-dominant inclusions.

These trees have high Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and have been allocated a Retention Value of *Consider for Retention*.

Tree 68 (Group of 7) *Acacia* spp. (Wattle)

Tree 68 is a group of seven (7) trees located on the northern side of Smidmore Street. They have been identified as *Acacia* spp. (Wattle). These trees have been assessed as being in fair health and structure.

Figure 12: Showing Trees 68

These trees have low Landscape Significance, a Remaining Life Expectance Range of less than 5 years and have been allocated a Retention Value of *Priority for Removal*.



Trees 69-74 *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig)

Trees 69-74 are positioned on the northern side of Smidmore Road. These trees have high Landscape Significance.

Trees 69 and 72 have a Remaining Life Expectancy Range of 5-15 years and have been allocated a Retention Value of *Consider for Retention*.

Trees 70, 71, 73 and 74 have a Remaining Life Expectancy Range of less than 5 years and have been allocated a Retention Value of *Priority for Removal*.

3.2.3 No Works within TPZ

The supplied plans indicate that no works are proposed within the Tree Protection Zone (TPZ) of twenty-two (22) trees. These trees should not be impacted by the proposed works.

These trees are discussed in more detail below:

Tree 1 *Lophostemon confertus* (Brush Box)

Tree 1 has been identified as *Lophostemon confertus* (Brush Box) which is located on the road reserve of Victoria Road and is a Council-managed tree. Tree 1 has moderate Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and has been allocated a Retention Value of *Consider for Retention*.



Trees 2-8 and 10-19 *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig)

Trees 2-8 and 10-18 have been identified as *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig) which are located on the outside of the Metro building on the Victoria Road frontage.

Figure 13: Showing Hills Weeping Figs along Victoria Road

These trees have been assessed as being in fair health due to the presence of small diameter deadwood throughout the canopies and a reduced canopy cover of approximately 60-70% (comparative to the same species growing

in ideal site and environmental conditions).

The structure of these trees has been assessed as fair due to the presence of mature epicormic growth resultant from lopping. Wounds with possible decay were also noted at branch attachments to the main stem of several of these trees.

These trees have high Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and have been allocated a Retention Value of *Consider for Retention*.

Some branches from these trees are in contact with or are in close proximity to the adjacent wall and roof. These branches should be removed by Selective Pruning. Canopy pruning may also be required to provide building clearance and for access during construction. All pruning work should be undertaken in accordance with AS4373: *Pruning of Amenity Trees* (2007) and the *Workcover Code of Practice for the Amenity Tree Industry* (1998).



Figure 14: Showing contact of branch with wall

All pruning should be carried out by an experienced and qualified Arborist. The Arborist shall hold a minimum qualification equivalent (using the Australian Qualifications Framework) of NSW TAFE Certificate Level 3 or above, in Arboriculture and a NSW TAFE Tree Surgery Certificate or its recognised equivalent. The Arborist shall have a minimum of 3 years experience in practical Arboriculture including demonstrated experience in tree surgery.

Tree 9 *Schinus molle* var. *areira* (Peppercorn Tree)

Tree 9 has been identified as *Schinus molle* var. *areira* (Peppercorn Tree) which is a Council-managed tree located on the road reserve of Victoria Road. This tree has been assessed as being good health and structure with normal deadwood throughout the canopy. This tree has high Landscape Significance, a Remaining Life Expectancy Range of 5-15 years and has been allocated a Retention Value of *Consider for Retention*.

Trees 85-87 *Callistemon viminalis* (Weeping Bottle Brush)

Trees 85-87 have been identified as *Callistemon viminalis* (Weeping Bottle Brush) located on the eastern side of Murray St. These trees have moderate Landscape Significance, a Remaining Life Expectance Range of 5-15 years and have been allocated a Retention Value of *Consider for Retention*.

4.0 CONCLUSIONS

4.1 Eighty-seven (87) trees have been surveyed as part of this assessment. The surveyed trees were assessed as generally being in fair health and structure.

4.2 The supplied plans indicate that seven (7) trees are outlined for removal to accommodate proposed building or vehicular entry footprint.

4.3 The supplied plans indicate that works are proposed within the TPZ of ten (10) trees. The extent of these works is considered a *Major Encroachment* as defined by the Australian Standard. Further investigation in the form of exploratory root trenching should be undertaken to determine the presence and extent of root spread or tree sensitive construction techniques and materials such should be used within the trees' TPZ.

AS4970-Integrated Vegetation Management Pty Ltd- reproduced under copyright Licence number 1009-c029
AS4373-Integrated Vegetation Management Pty Ltd- reproduced under copyright Licence number 1009-c029

4.4 The supplied plans indicate that landscape works are proposed within the TPZ of forty-eight (48) trees. Further investigation in the form of exploratory root trenching should be undertaken to determine the presence and extent of root spread or tree sensitive construction techniques and materials such should be used within the trees' TPZ.

4.5 The supplied plans indicate that no works are proposed within the Tree Protection Zone (TPZ) of twenty-two (22) trees. These trees should not be impacted by the proposed works.

4.6 Some branches of Trees 2-8 and 10-18 are in contact with, or are in close proximity to the adjacent existing wall and roof. These branches should be removed by Selective Pruning. Canopy pruning may also be required to provide building clearance and for access during construction for Trees 75-84. All pruning work should be undertaken in accordance with AS4373: *Pruning of Amenity Trees* (2007), the *Workcover Code of Practice for the Amenity Tree Industry* (1998) and as outlined with Section 3.2.1 and 3.2.3.

4.7 Wounds with possible decay were noted on Trees 20, 25, 29. If these trees are to be retained, internal diagnostic testing should be undertaken to determine the presence and extent of decay.

4.8 Trees 48 and 57 have structural defects which require their immediate removal.

4.9 The trees to be retained should be protected in accordance with the Tree Protection Specifications outlined in **Appendix 6**.

NOTE: Reference should be made to any relevant legislation including Tree Preservation Orders i.e. permission to undertake tree pruning/removal should be sought from Council.

AS4373-Integrated Vegetation Management Pty Ltd- reproduced under copyright Licence number 1009-c029

5.0 BIBLIOGRAPHY

- American Society of Consulting Arborists (1995), *A Guide to Report Writing for Consulting Arborists*, International Society of Arboriculture, USA.
- Barrell (1993), 'Preplanning Tree Surveys: Safe Useful Life Expectancy (SULE) is the Natural Progression', *Arboricultural Journal* 17:1, February 1993, pp. 33-46.
- Barrell (1995), 'Pre-development Tree Assessments', in *Trees & Building Sites, Proceedings of an International Conference Held in the Interest of Developing a Scientific Basis for Managing Trees in Proximity to Buildings*, International Society of Arboriculture, Illinois, USA, pp. 132-142.
- Bradshaw, Hunt & Walmsley (1995), *Trees in the Urban Landscape*, E & FN Spon, London.
- Fakes J (2005), *Arboriculture Notes*, Ryde Tafe, NSW.
- Fakes J (2004), *Introduction to Arboriculture*, Ryde Tafe, NSW.
- Gilman E (1997), *Trees for Urban and Suburban Landscapes: An Illustrated Guide to Pruning*, Delmar, USA.
- Hadlington & Johnston (1988), *Australian Trees: Their Care & Repair*, UNSW Press, Sydney.
- Harris, Clark & Matheny (1999), *Arboriculture: Integrated Management of Landscape Trees, Shrubs And Vines*, Prentice Hall, New Jersey.
- Matheny & Clark (1994), *A Photographic Guide to the Evaluation of Hazard Trees in Urban Areas*, International Society of Arboriculture, USA.
- Mattheck & Breloer (1994), *The Body Language of Trees: A Handbook for Failure Analysis*, The Stationary Office, London.
- Simon, Dormer & Hartshorne (1973), *Lowson's Botany*, Bell & Hyman, London.
- Standards Australia (2003), *Composts, Soil Conditioners and Mulches AS-4454*.
- Standards Australia (2009), *Protection of Trees on Development Sites AS-4970*.
- Standards Australia (2007), *Pruning of Amenity Trees AS-4373*.

Appendix 1: Methodology

- This report was determined as a result of a comprehensive site inspection during February 2010. The comments and recommendations in this report are based on findings from this site inspection.
- The subject trees were visually assessed from the ground using the standard visual tree assessment criteria and notes. The inspection was limited to a visual examination of the subject trees from ground level without dissection, probing or coring. No woody tissue testing was undertaken as part of this assessment. Trees outside the subject site were assessed from the property boundaries only.
- Tree height and canopy spread were estimated only.
- The location of the subject trees was determined from the Site Survey (Ref: Ch4331.057) attached as **Appendix 3**. A number of trees were not shown on this plan. Their approximate location has been plotted on this plan.
- Details of the proposed development were determined from the Landscape Master Plan (Option 1, Dwg No. 100/C) attached as **Appendix 4**.
- Tree Protection Measures, Tree Protection Zones and Sensitive Construction Methods for the subject trees were based on methods outlined in *Australian Standard 4970-2009 Protection of Trees on Development Sites*. **Refer to Appendix 5**.
- Tree health was determined by assessing:-
 - I. Foliage size and colour
 - II. Pest and disease infestation
 - III. Extension growth
 - IV. Canopy density
 - V. Percentage of deadwood
 - VI. Presence of epicormic growth
- Tree structure was assessed by:-
 - I. Visible evidence of structural defects or instability
 - II. Evidence of previous pruning or physical damage
- The Remaining Life Expectancy Range (RLER) is an estimate of the longevity of the subject trees in their existing growing conditions. This was calculated by estimating the expected lifespan of the species, less the subject trees' estimated current age. The trees have been allocated one of the following Remaining Life Expectancy Ranges:
 - I. 40 years +
 - II. 15-40 years
 - III. 5-15 years
 - IV. Less than 5 years
 - V. Dead or Immediate Removal
- Landscape Significance was determined by assessing the combination of the cultural, environmental and aesthetic values of the subject trees. Whilst these values are subjective, a rating of high, moderate, low or insignificant has been allocated to the trees. This provides a relative value of the trees' Landscape Significance which aid in determining their Retention Value.

Landscape Significance	Description
High	The subject tree is listed as a Heritage Item under the <i>Local Environmental Plan</i> with a local or state level of significance.
	The subject tree is listed as a Heritage Item under the <i>Local Environmental Plan</i> with a local or state level of significance.
	The subject tree forms part of the curtilage of a heritage item.
	The subject tree creates a 'sense of place' or is considered 'landmark' tree.
	The subject tree is of local, cultural or historical importance or is widely known.
	The subject tree is listed on Council's Significance Tree Register.
	The subject tree is scheduled as a Threatened Species or Threatened Plant Community under the <i>Threatened Species Conservation Act</i> (1995).
	The subject tree is a remnant tree.
	The subject tree is a locally indigenous species and is representative of the original vegetation of the area.
	The subject tree provides habitat to a threatened species.
	The subject tree is an excellent representative of the species in terms of aesthetic value.
Moderate	The subject tree makes a positive contribution to the visual character or amenity of the area.
	The subject tree provides a specific function such as screening or minimising the scale of a building.
	The subject tree has a known habitat value.
	The subject tree is a good representative of the species in terms of aesthetic value.
Low	The subject tree is an environmental pest species or is exempt under the provisions of the local Council's Tree Preservation Order.
	The subject tree makes little or no contribution to the amenity of the locality.
	The subject tree is a poor representative of the species in terms of aesthetic value.
Insignificant	The subject tree is declared a Noxious Weed under the Noxious Weeds Act

NOTE: If the tree can be categorised into more than one value, the higher value should be allocated.

- Retention Value was based on the subject tree's Remaining Life Expectancy Range and Landscape Significance. The Retention Value was modified where necessary to take in consideration the subject tree's health, structure and site suitability. The subject trees have been allocated one of the following Retention Values:-

- I. Priority for Retention
- II. Consider for Retention
- III. Consider for Removal
- IV. Priority for Removal

RLER	LANDSCAPE SIGNIFICANCE			
	High	Moderate	Low	Insignificant
40 years +	PRIORITY FOR RETENTION		CONSIDER FOR REMOVAL	PRIORITY FOR REMOVAL
15-40 years	PRIORITY FOR RETENTION	CONSIDER FOR RETENTION	CONSIDER FOR REMOVAL	
5-15 years	CONSIDER FOR RETENTION		CONSIDER FOR REMOVAL	
Less than 5 years	PRIORITY FOR REMOVAL			
Dead/Immediate Removal				

Appendix 2: Tree Assessment Schedule

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
1	<i>Lophostemon confertus</i> (Brush Box)	300	8	5	Fair	Good	Suppressed. Phototrophic lean due to suppression.	Moderate	5-15	Consider for Retention	3600	No works within TPZ.
2	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	8400	No works within TPZ.
3	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Branches touching roof. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	8400	No works within TPZ.
4	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	6000	No works within TPZ.
5	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	8400	No works within TPZ.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
6	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	8400	No works within TPZ.
7	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	8400	No works within TPZ.
8	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	6000	No works within TPZ.
9	<i>Schinus molle</i> var. areira (Peppercorn Tree)	400	9	8	Good	Good	Normal deadwood.	High	5-15	Consider for Retention	4800	No works within TPZ.
10	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500 (Co dominant @ 800)	12	10	Fair	Fair	Co-dominant inclusion. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	6000	No works within TPZ.
11	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500 (Co dominant @ 800)	12	10	Fair	Fair	Co-dominant inclusion. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	6000	No works within TPZ.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
12	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	600 (Co dominant @ 800)	12	10	Fair	Fair	Co-dominant inclusion. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	7200	No works within TPZ.
13	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	8400	No works within TPZ.
14	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	400	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	4800	No works within TPZ.
15	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	300 (Co dominant @ 1.5)	12	10	Fair	Fair	Co-dominant inclusion. Small diameter deadwood. Reduced canopy cover 60%. Celtis at base.	High	5-15	Consider for Retention	3600	No works within TPZ.
16	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	300	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	3600	No works within TPZ.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
17	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	6000	No works within TPZ.
18	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	6000	No works within TPZ.
19	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	12	10	Fair	Fair	Previously lopped. Mature epicormic growth. Recent branch failure/s. Wound with possible decay. Small diameter deadwood. Reduced canopy cover 60%.	High	5-15	Consider for Retention	9600	No works within TPZ.
20	<i>Ficus macrophylla</i> (Moreton Bay Fig)	2500	13	20	Fair	Poor	Heritage tree. Canopy comprises mainly of epicormic growth. Small and large diameter deadwood. Wounds with possible decay. Mechanical damage to roots.	High	5-15	Consider for Retention	15000	Landscape treatment within TPZ.
21	<i>Celtis sinensis</i> (Nettle Tree)	100	7	4	Fair	Good	Suppressed.	Low	15-40	Consider for removal	1200	Landscape treatment within TPZ.
22	<i>Agonis flexuosa</i> (Willow Myrtle)	200	7	5	Good	Poor	Wound with possible decay. Major trunk/branch inclusions.	Low	5-15	Consider for removal	2400	Landscape treatment within TPZ.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
23	<i>Celtis sinensis</i> (Nettle Tree)	100	7	4	Fair	Good	Suppressed.	Low	15-40	Consider for removal	1200	Landscape treatment within TPZ.
24	<i>Celtis sinensis</i> (Nettle Tree)	100	7	4	Fair	Good	Suppressed.	Low	15-40	Consider for removal	1200	Landscape treatment within TPZ.
25	<i>Cinnamomum camphora</i> (Camphor Laurel)	1800	15	12	Fair	Poor	Wound with possible decay. Mature epicormic growth. Small and large diameter deadwood. Reduced canopy cover 70%. Ficus elastic in stem.	High	< 5	Consider for Removal	21600	Landscape treatment within TPZ.
26	<i>Celtis sinensis</i> (Nettle Tree)	150	7	4	Fair	Good	Suppressed.	Low	15-40	Consider for removal	1800	Landscape treatment within TPZ.
27	<i>Celtis sinensis</i> (Nettle Tree)	1000 (Multi x 3 @ grade)	15	15	Good	Poor	Co-dominant inclusion. Wound with possible decay.	Moderate	5-15	Consider for Retention	12000	Landscape treatment within TPZ.
28	<i>Lophostemon confertus</i> (Brush Box)	400	9	8	Good	Fair	Previously lopped. Mature epicormic growth. Sign in stem.	High	15-40	Priority for Retention	4800	Landscape treatment within TPZ.
29	<i>Lophostemon confertus</i> (Brush Box)	600	10	8	Fair	Poor	Wounds with possible decay. Mature epicormic growth. Small diameter deadwood. Undertake internal diagnostic test if retained.	High	< 5	Priority for Removal	7200	Landscape treatment within TPZ.
30	<i>Washingtonia</i> sp. (Fan Palm)	600	12	6	Good	Good	Superficial wound.	High	15-40	Priority for Retention	4000	Landscape treatment within TPZ.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
31	<i>Celtis sinensis</i> (Nettle Tree)	400	10	10	Good	Fair	Girdled roots. Restricted soil volume.	Low	< 5	Priority for Removal	4800	Landscape treatment within TPZ.
32	<i>Schinus molle</i> var. <i>areira</i> (Peppercorn Tree)	600 (Co dominant @ grade)	6	10	Good	Good	Mature epicormic growth. Previous failure. Normal deadwood.	High	5-15	Consider for Retention	7200	Landscape treatment within TPZ.
33	<i>Lophostemon confertus</i> (Brush Box)	400	9	8	Good	Fair	Previously lopped. Mature epicormic growth.	High	15-40	Priority for Retention	4800	Landscape treatment within TPZ.
34	<i>Lophostemon confertus</i> (Brush Box)	400	9	8	Good	Fair	Previously lopped. Mature epicormic growth.	High	15-40	Priority for Retention	4800	Landscape treatment within TPZ.
35	<i>Lophostemon confertus</i> (Brush Box)	700	15	15	Good	Good		High	15-40	Priority for Retention	8400	Landscape treatment within TPZ.
36	<i>Cinnamomum camphora</i> (Camphor Laurel)	1200 (Multi x 5+ @ 1000)	15	15	Good	Fair	Multiple branch attachments. Mature epicormic growth. Small diameter deadwood.	High	5-15	Consider for Retention	14400	Landscape treatment within TPZ.
37	<i>Celtis sinensis</i> (Nettle Tree)	600 (Multi x 4 @ grade)	10	10	Good	Poor	Co-dominant inclusion. Multiple branch attachments.	Moderate	< 5	Priority for Removal	7200	Within footprint (building). Remove.
38	<i>Lophostemon confertus</i> (Brush Box)	800	12	12	Good	Fair	Mature epicormic growth. Previously lopped.	High	15-40	Priority for Retention	9600	Landscape treatment within TPZ.
39	<i>Lophostemon confertus</i> (Brush Box)	800	12	12	Good	Fair	Mature epicormic growth. Previously lopped.	High	15-40	Priority for Retention	9600	Landscape treatment within TPZ.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
40	<i>Lophostemon confertus</i> (Brush Box)	600	12	12	Good	Fair	Mature epicormic growth. Previously lopped.	High	15-40	Priority for Retention	7200	Landscape treatment within TPZ.
41	<i>Lophostemon confertus</i> (Brush Box)	600	12	12	Good	Fair	Mature epicormic growth. Previously lopped.	High	15-40	Priority for Retention	7200	Landscape treatment within TPZ.
42	<i>Lophostemon confertus</i> (Brush Box)	600	12	12	Good	Fair	Mature epicormic growth. Previously lopped.	High	15-40	Priority for Retention	7200	Landscape treatment within TPZ.
43	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	900	15	15	Good	Fair	Co-dominant inclusion. Wound with possible decay.	High	5-15	Consider for Retention	10800	Landscape treatment within TPZ.
44	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	15	10	Fair	Fair	Co-dominant inclusion. Wound with possible decay. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
45	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	15	10	Fair	Fair	Co-dominant inclusion. Wound with possible decay. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
46	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	15	10	Fair	Fair	Co-dominant inclusion. Wound with possible decay. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ..
47	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	15	10	Fair	Fair	Co-dominant inclusion. Wound with possible decay. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
48	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	15	10	Fair	Poor	Immediate remove. Wound with possible decay. Splits. Reduced canopy cover 70%. Small diameter deadwood.	High	< 5	Priority for Removal	6000	Landscape treatment within TPZ.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
49	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	15	10	Fair	Fair	Co-dominant inclusion. Wound with possible decay. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
50	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	15	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	9600	Landscape treatment within TPZ.
51	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
52	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Wound with possible decay. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
53	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
54	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
55	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
56	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Within footprint (vehicular entry). Remove.
57	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	15	12	Good	Poor	Immediate Removal. Co-dominant inclusion. Major trunk/branch inclusions. Wound with possible decay.	High	< 5	Priority for Removal	8400	Within footprint (vehicular entry). Remove.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
58	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Within footprint (vehicular entry). Remove.
59	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Within footprint (vehicular entry). Remove.
60	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Within footprint (vehicular entry). Remove.
61	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	12	12	Fair	Fair	Co-dominant inclusion. Small diameter deadwood.	High	5-15	Consider for Retention	9600	Landscape treatment within TPZ.
62	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	500	11	10	Fair	Fair	Co-dominant inclusion. Reduced canopy cover 70%. Small diameter deadwood.	High	5-15	Consider for Retention	6000	Landscape treatment within TPZ.
63	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	12	12	Fair	Fair	Co-dominant inclusion. Small diameter deadwood.	High	5-15	Consider for Retention	9600	Landscape treatment within TPZ.
64	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	12	12	Fair	Fair	Co-dominant inclusion. Small diameter deadwood.	High	5-15	Consider for Retention	9600	Landscape treatment within TPZ.
65	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	12	12	Fair	Fair	Restricted soil volume. Small diameter deadwood. Co-dominant inclusion.	High	5-15	Consider for Retention	9600	Landscape treatment within TPZ.
66	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	12	12	Fair	Fair	Co-dominant inclusion. Small diameter deadwood.	High	5-15	Consider for Retention	9600	Landscape treatment within TPZ.
67	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800	12	12	Fair	Fair	Co-dominant inclusion. Small diameter deadwood.	High	5-15	Consider for Retention	9600	Within footprint (building). Remove.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
68	Acacia spp (Wattle) Group of 7	75	4	3	Fair	Fair	Major trunk/branch inclusions. Small diameter deadwood.	Low	< 5	Priority for Removal	900	Within footprint (vehicular entry). Remove.
69	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	700	12	10	Good	Fair	Splits. Superficial Wound.	High	5-15	Consider for Retention	8400	Landscape treatment within TPZ.
70	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800 (Co dominant @ grade)	13	12	Good	Poor	Co-dominant inclusion.	High	< 5	Priority for Removal	9600	Landscape treatment within TPZ.
71	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800 (Co dominant @ grade)	13	12	Good	Poor	Co-dominant inclusion.	High	< 5	Priority for Removal	9600	Landscape treatment within TPZ.
72	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	900 (Multi x 5+ @ grade)	9	6	Good	Fair	Multiple branch attachments.	High	5-15	Consider for Retention	10800	Landscape treatment within TPZ.
73	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	800 (Co dominant @ grade)	13	12	Good	Poor	Co-dominant inclusion.	High	< 5	Priority for Removal	9600	Landscape treatment within TPZ.
74	<i>Ficus microcarpa</i> var. 'Hillii' (Hills Weeping Fig)	1200	13	12	Good	Poor	Co-dominant inclusion.	High	< 5	Priority for Removal	14400	Landscape treatment within TPZ.
75	<i>Corymbia citriodora</i> (Lemon-scented Gum)	700	15	12	Good	Good		High	15-40	Priority for Retention	8400	Major encroachment.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
76	<i>Corymbia citriodora</i> (Lemon-scented Gum)	700	15	12	Good	Good		High	15-40	Priority for Retention	8400	Major encroachment.
77	<i>Corymbia citriodora</i> (Lemon-scented Gum)	700	15	12	Good	Good	Large diameter deadwood.	High	15-40	Priority for Retention	8400	Major encroachment.
78	<i>Corymbia citriodora</i> (Lemon-scented Gum)	700	15	12	Fair	Good	Reduced canopy cover 70%.	High	5-15	Consider for Retention	8400	Major encroachment.
79	<i>Eucalyptus</i> sp. (Gum Tree)	800 (Co dominant @ 400)	9	8	Good	Good	Normal deadwood.	High	5-15	Consider for Retention	9600	Major encroachment.
80	<i>Corymbia citriodora</i> (Lemon-scented Gum)	700	15	12	Fair	Good	Reduced canopy cover 70%.	High	5-15	Consider for Retention	8400	Major encroachment.
81	<i>Corymbia citriodora</i> (Lemon-scented Gum)	700	15	12	Good	Good		High	15-40	Priority for Retention	8400	Major encroachment.
82	<i>Corymbia citriodora</i> (Lemon-scented Gum)	1000	15	12	Good	Good		High	15-40	Priority for Retention	12000	Major encroachment.
83	<i>Eucalyptus</i> sp. (Gum Tree)	800 (Co dominant @ 400)	9	8	Good	Good	Normal deadwood.	High	5-15	Consider for Retention	9600	Major encroachment. Existing building may have impeded root spread.

Tree No.	Botanical Name	DBH	Height (m)	Spread (m)	Health Rating	Structure Rating	Comments	L/Significance	R/L/E/R	Retention Value	TPZ (mm)	Implication
84	<i>Corymbia citriodora</i> (Lemon-scented Gum)	700	15	12	Good	Good		High	15-40	Priority for Retention	8400	Major encroachment. Existing building may have impeded root spread.
85	<i>Callistemon viminalis</i> (Bottle Brush)	300 (Co dominant @ 200)	4	4	Good	Fair	Previously lopped. dominant inclusion.	Moderate	5-15	Consider for Retention	3600	No works within TPZ.
86	<i>Callistemon viminalis</i> (Bottle Brush)	300 (Co dominant @ 200)	4	4	Good	Fair	Previously lopped. dominant inclusion.	Moderate	5-15	Consider for Retention	3600	No works within TPZ.
87	<i>Callistemon viminalis</i> (Bottle Brush)	300 (Co dominant @ 200)	4	4	Good	Fair	Previously lopped. dominant inclusion.	Moderate	5-15	Consider for Retention	3600	No works within TPZ.

Appendix 3: Site Survey

Appendix 4: Landscape Plan

© 2010 Site Image (NSW) Pty Ltd. All rights reserved.
No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means (graphic, electronic or mechanical including photocopying, recording, or by any information storage or retrieval system) without prior written permission from Site Image (NSW) Pty Ltd. and the copyright owner.

This contractor shall check and verify all work on site including work by others. The contractor shall be responsible for the accuracy of the information and data provided to the Project Manager or Landscape Architect prior to commencing work. Do not scale this drawing. Any required dimensions not shown shall be referred to the Landscape Architect for confirmation.

Revised	Revised Description	Drawn	Checked	Date
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

LEGEND

Extent of Works

- Existing Heritage Brick Paving to be retained
- Heritage Brick Paving to be retained
- Unit Paver Banding
- Iron Concrete Paving
- Timber Deck
- Steel Edge
- Rendered Blockwork
- Wall/Bench Seat
- Feature Sculpture
- 2 Bikes Per Rack
- Rubbish Bins
- Removable Bollard
- Fixed Bollard
- Bench Seat

Building Outline

- Existing Trees to be Retained
- Existing Trees to be Retained
- Tree Planting
- Tree Planting
- Shrub Planting
- Groundcover / Grass Planting
- Accent Planting
- Hedge Planting
- Spill Garden
- Turf Planting



Client: **AMP capital**
Project Manager: **Bovis**
Land Lease


Project: **MARRICKVILLE METRO**
Client: **Melfio**



PART 3A

Drawing Name:
Landscaping Master Plan

Scale: 1:500 @ A1
Drawing Number: **SS10 - 2128**
Sheet: **100**
C



Appendix 5: Notes on AS: 4970 (2009)

In August 2009, *Australian Standard 4970-2009: Protection of Trees on Development Sites* was released. This document describes the best practices for the planning and protection of trees on development sites (AS-4970, 2009).

Clause 3.2 of the Australian Standard outlines that the Tree Protection Zone (TPZ) should be calculated as a radial measurement based on twelve (12) times the Diameter at Breast Height (DBH). A TPZ should not be less than 2 m nor greater than 15 m (except where crown protection is required). The TPZ of palms, other monocots, cycads and tree ferns should not be less than 1 m outside the crown projection. However, in some cases it may be possible to encroach into or make variations to the standard TPZ

A *Minor Encroachment* is less than 10% of the area of the TPZ and is outside the Structural Root Zone (SRZ). The area lost to this encroachment should be compensated for elsewhere and contiguous with the TPZ (AS-4970, 2009).

A *Major Encroachment* is greater than 10% of the TPZ or inside the SRZ. In this situation the project arborist must demonstrate that the tree(s) would remain viable. This may require root investigation by non-destructive methods. The area lost to this encroachment should be compensated for elsewhere and contiguous within the TPZ (AS-4970, 2009).

Clause 3.3.4 of Standard also discusses additional factors such as tree and site characteristics, and sensitive construction methods which should be considered when determining the potential impacts of an encroachment on a tree.

Figure A: EXAMPLE TPZ, SRZ & CROWN




Figure B: EXAMPLES OF MINOR ENCROACHMENT

Integrated Vegetation Management Pty Ltd- reproduced under copyright Licence number 1009-c029

Appendix 6: General Tree Protection Specification

1.0 Appointment of Site Arborist

A Site Arborist shall be appointed prior the commencement of works on- site. The Site Arborist shall monitor the trees to be retained and supervise the tree protection measures. The Site Arborist shall have a minimum qualification equivalent (using the Australian Qualifications Framework) of NSW TAFE Certificate Level 5 or above in Arboriculture.

1.1 Inspection Points

Give 5 working days notice to allow inspections to be undertaken at the following stages:-

INSPECTION POINT	INSPECTION PERSONNEL
Installation of Tree Protection Zone including Tree Protection Fencing, Silt Fencing and signage	Site Arborist
Modification of the Tree Protection Zone	Site Arborist
Works with the Tree Protection Zone	Site Arborist
Completion of the construction works	Site Supervisor Site Arborist

1.2 Education

Contractors and site workers shall receive a copy of these specifications a minimum of 3 working days prior to commencing work on-site. Contractors and site workers undertaking works within the Tree Protection Zones shall sign the site log confirming they have read and understand these specifications, prior to undertaking works on-site.

1.3 Tree Protection Zone

The trees to be retained shall be protected prior and during construction from activities that may result in an adverse effect on their health or structure. The area within the Tree Protection Zones shall exclude the following activities, unless otherwise stated:-

- Modification of existing soil levels
- Excavations and trenching
- Cultivation of the soil
- Mechanical removal of vegetation
- Soil disturbance
- Movement of natural rock
- Storage of materials, plant or equipment
- Erection of site sheds
- Affixing of signage or hoarding to the trees
- Preparation of building materials
- Disposal of waste materials and chemicals
- Movement of pedestrian or vehicular traffic
- Temporary or permanent location of services, or the works required for their installation
- Any other activities that may cause damage to the tree

NOTE: If access, encroachment or incursion into the Tree Protection Zones is deemed essential, prior authorisation is required by the Site Arborist.

1.4 Tree Protection Fencing

Where deemed necessary by the Site Arborist, Tree Protection Fencing shall be installed at the perimeter of the Tree Protection Zone. As a minimum, the Tree Protection Fence shall consist of 1.8m high temporary chain wire panels supported by steel stakes. They shall be fastened together and supported to prevent sideways movement. The fence must have a lockable opening for access. The trees' woody roots shall not be damaged during the installation of the Tree Protection Fencing.

Refer to **Appendix 7: Typical Tree Protection Fencing Detail**

Where deemed necessary by the Site Arborist, shade cloth material shall be attached to the outer surface of the Tree Protection Fence. The shade cloth material shall be transparent to provide visibility into the Tree Protection Zones.

The Tree Protection Fence shall be erected prior to the commencement of works on-site and shall be maintained in good condition for the duration of the development period. The Tree Protection Fence shall only be removed, altered, or relocated with the authorization from the Site Arborist.

1.5 Signage

Tree Protection Signage shall be attached to the Tree Protection Zones and displayed in a prominent position. The signs shall be repeated at 10m intervals or closer where the fence changes direction. The signage shall be installed prior to the commencement of works on-site and shall be maintained in good condition for the duration of the development period.

The lettering for each sign shall be a minimum 72 point font size. The signs shall be a minimum size of 600 x 500mm. Each sign shall advise the following details:-

- This fence has been installed to prevent damage to the tree and its growing environment. **Access is restricted.**
- If access, encroachment or incursion into this Tree Protection Zone is deemed essential, prior authorisation is required by the Site Arborist.
- Name, address, and telephone number of the developer

1.6 Mulching

Where deemed necessary by the Site Arborist, the area within the Tree Protection Zones shall be mulched with Horticultural Grade Pine Bark as certified to *AS4454: Composts, Soil Conditioners and Mulches* (1997) and shall be maintained at a depth of 70mm for the duration of the project. The mulch shall be spread by hand to avoid soil disturbance and compaction within the root zone. The mulch shall be installed prior to the commencement of works on-site. Mulch shall not be stock piled within the Tree Protection Zones.

1.7 Site Management

Materials and waste storage, site sheds and temporary services shall not be located within the specified Tree Protection Zones. Where deemed necessary by the Site Arborist, a silt fence shall be installed down slope from the storage points. Storage points shall be covered when not in use. The height of the storage points shall be less than 2m.

1.8 Access

Pedestrian and vehicular movement shall not occur within the specified Tree Protection Zones.

1.9 Works within the Tree Protection Zones

The Tree Protection Zones may need to be modified during the construction phase to allow access between the trees to be retained and the construction works. The Tree Protection Zones shall remain intact as specified in Section 1.4 until these works are due to commence. If access, encroachment or incursion into the Tree Protection Zones is deemed essential, prior authorization is required by the Site Arborist.

The modification of the Tree Protection Zones may necessitate the dismantling of sections of the Tree Protection Fencing. The Tree Protection Fence shall only be removed, altered, or relocated with the authorization from the Site Arborist.

1.10 Trunk & Branch Protection

Where deemed necessary by the Site Arborist, trunk and branch protection shall be provided. Trunk protection shall be installed by wrapping 2 layers of carpet underlay around the trunk to a minimum height of 2m or as the lower branches permit. The trunk shall further be protected with 2m lengths of timbers (75 x 50 x 200mm) spaced at 100mm centres, secured by wire rope. Branch protection shall be installed by wrapping 2 layers of carpet underlay around the branch, secured by wire rope. The wire rope shall not be fixed to the tree in any way.

1.11 Scaffolding

Scaffolding shall not be located within the specified Tree Protection Zones and shall be installed to minimize branch conflict. Where branch conflict is unavoidable, branches shall be tied back. In some cases, branch pruning may be required. Pruning shall be specified by the Site Arborist in accordance with AS 4373 (consent may be required).

Ground below the scaffolding should be protected by scaffold board or plywood sheeting. Where access is required, a board walk or other surface material should be installed to minimize soil compaction. Boarding shall be placed over a layer of mulch and impervious sheeting to prevent soil contamination. The boarding shall be left in place until the scaffolding is removed.

1.12 Soil Protection

Where deemed necessary by the Site Arborist, the ground surface within the Tree Protection Zones shall be protected by laying geo-textile over the existing mulch cover. Large diameter (up to 70mm) recycled railway ballast (true basalt) shall be placed over the geo-textile material to a depth of 100mm. Where deemed necessary by the Site Arborist, rumble boards shall be used.

1.13 Completion of Works within the Tree Protection Zones

Upon completion of the works within the Tree Protection Zones, the Tree Protection Fencing shall be reinstated as specified in Section 1.4. Where the construction of new structures does not provide sufficient area for the specified Tree Protection Zones, the Tree Protection Zones shall be modified by the Site Arborist.

1.14 Irrigation

In the event of prolonged dry periods, the trees to be retained shall be deep-watered at least once a week. The need for such watering shall be determined by the Site Arborist. In the event of disrupted ground or surface water flows, an irrigation system may be installed within the Tree Protection Zones. The need, type, volume, frequency of such an irrigation system shall be determined by the Site Arborist.

1.15 Tree Damage

In the event of the trees to be retained becoming damaged during the development period, the Site Arborist shall be informed to inspect and provide advice on remedial action.

1.16 Monitoring

The Site Arborist shall monitor the site fortnightly throughout the development period to ensure these specifications are maintained. A site log shall record the details of the site inspections for review by the Principal Certifying Authority prior to the release of the Compliance Certificate.


Any changes to the design will require additional arboricultural assessment.

1.17 Post Construction Maintenance

Upon the completion of construction works, a final assessment of the trees shall be undertaken by the Site Arborist. Inspection items shall include:-

- Damage to the trees' root system
- Damage to the trees' trunk, branches or canopy
- Changes in levels, soil structure, erosion, or loss of organic matter
- Changes to wind loading in the crown and effects of new structures
- Pest and disease infestation
- Drought stress
- Requirement for decompaction works
- Requirement for pruning works
- Requirement for ongoing maintenance such as watering

Appendix 7: Typical Tree Protection Fencing Detail



NOT TO SCALE