



STORMWATER MANAGEMENT & TRUNK
DRAINAGE STRATEGY
LOT A BURLEY ROAD
HORSLEY PARK EMPLOYMENT PRECINCT

August 2010

Report No. X10135-01

Prepared for Jacfin Pty Ltd



BROWN CONSULTING

Engineers & Managers

PEOPLE & PROJECTS

COMMERCIAL IN CONFIDENCE

All intellectual property rights, including copyright, in designs developed and documents created by the group of companies listed below remain the property of those companies. Any use made of such design or document without the prior written approval of the Group will constitute an infringement of the rights of the companies which reserves all legal rights and remedies in respect of any such infringement.

The information, including any intellectual property, contained in this report is confidential and proprietary to the Group. It may only be used by the person to whom it is provided for the stated purpose for which it is provided and must not be imparted to any third person without the prior written approval of the Group. The Group reserves all legal rights and remedies in relation to any infringement of its rights in respect of its confidential information.

©

Brown Consulting (NSW) Pty Ltd

August 2010

DOCUMENT CONTROL

XI0135-01

Issue	Date	Issue Details	Author	Checked	Approved
A	27 July 2010	Client Review	NWB/SC	RP/TT	
B	12 August 2010	Client Review	NWBSC	RP/TT	
C	16 August 2010	Client Review	NWBSC	RP/TT	
D	17 August 2010	Client Review	NWBSC	RP/TT	
E	25 August 2010	Client Review	NWB/SC	RP/TT	
F	25 November 2010	Client Review	NWB/SC	RP/TT	

Brown Consulting (NSW) Pty Ltd

Engineers & Managers ABN 30 109 434 513

Telephone 02 8808 5000 Facsimile 02 8808 5099

Level 2, 2 Burbank Place Norwest Business Park PO Box 8300 Baulkham Hills BCNSW 2153

E-mail sydney@brownconsulting.com.au Website www.brownconsulting.com.au

Brown Consulting (NSW) Pty Ltd

Engineers & Managers ABN 30 109 434 513

Telephone 02 8808 5000 Facsimile 02 8808 5099

Level 2, 2 Burbank Place Norwest Business Park PO Box 8300 Baulkham Hills BCNSW 2153

E-mail sydney@brownconsulting.com.au Website www.brownconsulting.com.au

STORMWATER MANAGEMENT & TRUNK DRAINAGE STRATEGY

LOT A BURLEY ROAD HORSLEY PARK EMPLOYMENT PRECINCT

TABLE OF CONTENTS

1	INTRODUCTION.....	1
1.1	Site Description.....	1
1.1.1	Ropes Creek Catchment.....	2
1.1.2	Soil Types.....	5
1.2	Stormwater Objectives Overview.....	7
1.3	Background – State Environmental Planning Policy (Western Sydney Employment Area) 2009	7
1.4	Project Overview.....	8
2	DRAINAGE DESIGN CRITERIA.....	10
2.1	State Environmental Planning Policy (Western Sydney Employment Area) 2009 ..	10
2.2	<i>Penrith Development Control Plan 2006</i>	10
2.3	<i>Penrith City Council – Erskine Park Employment Area Development Control Plan 2002</i>	10
2.4	Growth Centres Development Code (DEC 2006)	11
2.5	Penrith City Council Guidelines for Engineering Works for Subdivisions and Developments – Part 1 – Design (1997).....	11
2.6	Penrith City Council Stormwater Management for Developments 2009 (DRAFT) ..	11
2.7	Other Relevant Specifications.....	11
3	PRE-DEVELOPMENT FLOW RATES.....	16
3.1	Methodology	16
3.1.1	Ropes Creek XP-RAFTS Hydrological Model	16
3.1.2	Hydrological Model Parameters.....	17
3.1.3	Hydrological Survey Sources.....	17
3.1.4	Pre-developed Flow Rates	17
3.1.5	Calibration/Validation	19
3.1.6	Post-developed Flow Rates.....	19

4	FLOODING ANALYSIS.....	21
4.1	Methodology	21
4.1.1	Survey Sources.....	22
4.1.2	Roughness	22
4.2	Existing Flood Extents	22
4.3	Preliminary Developed Flood Extents	25
4.4	Flood Planning Levels & Road Levels	25
5	CONCEPT DRAINAGE DESIGN	28
5.1	Lot Drainage Design	28
5.2	Trunk Drainage Design	28
6	STORMWATER BASIN DESIGN.....	29
6.1	Detention Requirements	29
6.2	Detention Basin Design	30
6.3	Water Quality Requirements.....	32
6.3.1	Gross Pollutant Traps	32
6.3.2	Bioretention Basins.....	32
7	STAGE 1 PROJECT APPLICATION.....	34
7.1	Detention Requirements	34
7.2	Water Quality Requirements.....	34
7.3	RainWater Harvesting Requirements.....	35
8	SOIL & WATER MANAGEMENT DURING CONSTRUCTION.....	36
8.1	Soil and Water Management Plan	36
8.2	Dust Management Plan	37
9	CONCLUSION.....	38
10	REFERENCES	39
11	GLOSSARY OF TERMS	40
12	APPENDICES.....	44

LIST OF APPENDICES

Appendix A Drawings

LIST OF TABLES

Table 1	Design Criteria	13
Table 1 (cont)	Design Criteria	14
Table 1 (cont)	Design Criteria	15
Table 2	Existing Condition Peak Flows and Total Catchment Areas	18
Table 3	Horsley Park Employment Precinct <i>XP-RAFTS</i> & PRM Runoff Calculations	19
Table 4	Developed Conditions Peak Flows	20
Table 5	100 year ARI Peak Flows at Detention Basin locations	29
Table 6	Detention Basins requirements	30

LIST OF FIGURES

Figure 1	Study location	3
Figure 2	Ropes Creek Catchment	4
Figure 3	Soil Landscapes	6
Figure 4	Indicative Layout Plan	9
Figure 5	XP RAFTS Model Layout Plan	16
Figure 6	Schematic Representation of the Integrated 1D/2D SOBEK Hydraulic Model	21
Figure 7	100 ARI Peak Flood Extents – Existing Conditions	23
Figure 8	100 ARI Hazard – Existing Conditions	24
Figure 9	100 ARI Peak Flood Extents – Developed Conditions	26
Figure 10	100 ARI Hazard – Developed Conditions	27
Figure 11	Indicative Detention Basin Locations	31

STORMWATER MANAGEMENT & TRUNK DRAINAGE STRATEGY

LOT A BURLEY ROAD HORSLEY PARK EMPLOYMENT PRECINCT

1 INTRODUCTION

This Stormwater Management and Trunk Drainage Strategy has been prepared by Brown Consulting (NSW) Pty Ltd for Jacfin Pty Ltd to support the Proposed Concept and Project Application for the Horsley Park Employment Precinct within Precinct 8 of the Western Sydney Employment Area (WSEA). The proposed development site is located within the Penrith local government area as shown in Figure 1.

The study specifically describes the proposed stormwater quantity and quality management system using Water Sensitive Urban Design (WSUD) principles.

1.1 SITE DESCRIPTION

The site of Lot A Burley Road, shown on Figure 1, has historically been utilised as a rural farming area, showing evidence of tillage and soil improvements. The topography of the Site is gently sloping to the west, with gradients ranging from 1% to 7%. The main soil type is clay, originating from Wianamatta Shale, with approximately 200-300 millimetres of overlying topsoil. The site is devoid of significant vegetation (trees and shrubs) on the upper and lower slopes of the site, with the larger trees, including introduced species lining Ropes Creek and the E2 Conservation Area extending into the site.


The northern portion of the site falls to the north, draining to Ropes Creek through the Goodman development area located across Burley Road. The central of the site area falls to the E2 Conservation Area surrounding the small Ropes Creek tributary. A small section of approximately 8 hectares at the south eastern end of the site drains through private property to the south east.

The northern section of the site is bordered to the east by a PGH brickworks facility owned by CSR Limited. The southern section of the site is bordered to the east by large lot rural residential

subdivisions. Land use to the south and west of the site is primarily rural farming land. Ropes Creek is located to the west of the site boundary.

1.1.1 Ropes Creek Catchment

Ropes Creek is a tributary of South Creek, part of the Hawkesbury Nepean River system, shown on Figure 2. Ropes Creek flows in a northerly direction to the confluence with South Creek approximately 13.5 kilometres north-north-west of the site in the suburb of Ropes Crossing. The catchment area of Ropes Creek at the location of Lot A Burley Road is 186.5 hectares. The land use catchment consists mainly of grassed paddocks and large lot rural subdivisions.



Legend

SITE

CADASTRE

SUBURB BOUNDARY

Details		
Issue	Amendment	Date
A	CLIENT REVIEW	JULY 2010

Project
**HORSLEY PARK
INDUSTRIAL SUBDIVISION**


Drawing Title
**FIGURE I
SITE OVERVIEW**

Scale	I:10000 @A3
Drawn	TWC
Checked	SC
Job No.	X10135
Drawing No.	FIGURE 01



Legend

- CATCHMENTE EXTENTS
- SITE EXTENTS
- CADASTRE



Details		
Issue	Amendment	Date
A	CLIENT REVIEW	JULY 2010

Project
**HORSLEY PARK
INDUSTRIAL SUBDIVISION**

Drawing Title
**FIGURE 2
CATCHMENT PLAN**

Scale	NTS
Drawn	TWC
Checked	SC
Job No.	X10135
Drawing No.	FIGURE 02
Issue	
A	

1.1.2 Soil Types

Soil types in the Ropes Creek catchment were mapped from the *Soil Landscapes of the Penrith 1:100,000 Sheet*, shown on Figure 3. The three main soil landscapes present on the site are:

- **South Creek Soil Landscape (sc)** – a fluvial soil landscape developed in floodplains, valley flats and drainage depressions with erosion channels. The South Creek soils are developed on alluvium derived from Wianamatta Group shales and are often very deep-layered sediments over bedrock or relict soils. Landscape limitations include flood hazard, waterlogging (seasonal or localised), permanently high water tables (localised) and high erosion hazard.
- **Blacktown Soil Landscape (bt)** – a residual soil landscape developed on gently undulating rises with local relief to 30 metres and slopes of less than 5% gradient. The Blacktown soils are derived from Wianamatta and Hawkesbury shales and are shallow to moderately deep. Crests, upper slopes and well drained areas are typically red and brown podzolic soils, with deep yellow podzolic soils located on lower areas of poor drainage. Limitation of these soils are that they are highly plastic, moderately reactive, of low fertility, poor soil drainage, localised salinity and moderate erodibility.
- **Luddenham Soil Landscape (lu)** – an erosional soil landscape developed on undulating to rolling hills with local relief of 50 to 80 metres with slopes of 10 to 20%. Luddenham soils are shallow and derived from Wianamatta Group shales, often associated with resistant sandstone beds. Crests and upper slopes are typically dark podzols and massive earthy clays, with lower slopes and drainage lines moderately deep yellow podzols. Limitations are the highly plastic subsoils of moderate reactivity, low to moderate shrink-swell potential, low to moderate soil fertility and moderate erodibility.



Legend

- SITE EXTENTS
- CADASTRE
- CATCHMENT EXTENTS
- SOIL LANDSCAPE
 - BLACKTOWN
 - SOUTH CREEK
 - LUDDENHAM
 - DISTURBED TERRAIN
 - PICTON
 - BERKSHIRE PARK

Details		
Issue	Amendment	Date
A	CLIENT REVIEW	JULY 2010

Project
**HORSLEY PARK
INDUSTRIAL SUBDIVISION**

Drawing Title
**FIGURE 3
SOIL LANDSCAPE PLAN**

Scale	NTS
Drawn	TWC
Checked	SC
Job No.	X10135
Drawing No.	FIGURE 03

1.2 STORMWATER OBJECTIVES OVERVIEW

The aim of this study is to establish a stormwater & trunk drainage strategy based on WSUD principles. The key objectives of this study include:

- Potential impact from the development with respect to stormwater quantity, quality and flooding on-site and downstream of the site;
- Linking water infrastructure effectively to minimise the impacts of development upon runoff;
- Protecting downstream receiving waters (e.g. riparian corridors) from increased flow rates and water quality degradation; and
- Protect assets and the subdivision from flooding.

The specific objectives of the Concept/Project Plan with regards to stormwater quantity management include:

- Attenuate peak storm flows for the 20 and 100 year ARI to existing flow rates
- Incorporate safety considerations into the design of batter slopes, ponding depths and other design requirements
- Minimise potential for damages resulting from flooding

1.3 BACKGROUND – STATE ENVIRONMENTAL PLANNING POLICY (WESTERN SYDNEY EMPLOYMENT AREA) 2009

This Policy aims to protect and enhance the Western Sydney Employment Area for employment purposes. The Policy aims to ensure that development occurs in a logical, environmentally sensitive and cost-effective manner and only after a development control plan (including specific development controls) has been prepared for the land concerned.

This Stormwater Management and Trunk Drainage Strategy furthers the provisions of SEPP 59 by developing design criteria, indicative layouts and diagrams relating to the development of land within the Horsley Park Employment Precinct. This Strategy incorporates the provisions of relevant Penrith City Council planning policies into the concept design, integrating the aims, objectives and controls to achieve the outcomes required for consideration in the determination of the development application.

1.4 PROJECT OVERVIEW

The proposal involves the development of Lot A Burley Road for industrial and employment purposes, including the subdivision of the lot, construction of roads and drainage infrastructure and the construction of industrial and employment buildings. An indicative lot and road layout is shown in Figure 4.



Figure 4 - Indicative Layout Plan

2 DRAINAGE DESIGN CRITERIA

This section outlines the planning context and design criteria relevant to the Horsley Park Employment Precinct. The section provides a brief description of relevant Western Sydney Employment Area and Penrith City Council publications and concludes with a table that summarises the applicable design criteria. All the documents listed in this section address the key issues of the Director-General's requirements for the project relevant to Stormwater Management and Drainage Strategy.

2.1 STATE ENVIRONMENTAL PLANNING POLICY (WESTERN SYDNEY EMPLOYMENT AREA) 2009

Part 5 of the State Environmental Planning Policy (SEPP59 - WSEA) 2009 specifies the principal development standards. Section 5 of Schedule 4 outlines provisions for flooding.

2.2 *PENRITH DEVELOPMENT CONTROL PLAN 2006*

Part 2, Section 2.10 of the Penrith DCP outlines aims and objectives to reduce the impact of flooding and flood liability on individual owners and occupiers. Part B of this DCP provides guidance for development within land designated by Penrith Council as being "Flood liable land". Relevant sections of Section 3 of Part B are:

- 3.4 Industrial Commercial New Development
- 3.9 Subdivision
- 3.11 Filling of Flood Liable Land

2.3 *PENRITH CITY COUNCIL – ERSKINE PARK EMPLOYMENT AREA DEVELOPMENT CONTROL PLAN 2002*

This DCP relates to land in the Erskine Park Employment Area, located to the west of the site, across Ropes Creek. This DCP does not directly relate to the Horsley Park Employment Precinct but has been assessed as part of this investigation for completeness and in order to provide guidance as to Penrith Council's requirements.

2.4 GROWTH CENTRES DEVELOPMENT CODE (DEC 2006)

The Development Code by the then Department of Environment and Conservation (DEC) provides the basis for the planning and design of precincts and neighbourhoods. It is intended to be a reference work, to stimulate ideas and provide a guide to best practice.

The Code is a guide for Precinct Planning in the Growth Centres. It is the link to the State Environmental Planning Policy (SEPP) and the Structure Plan principles and design elements set at the high level to improve the built environment. Sections of the Development Code specifically relevant to the design of the Horsley Park Employment Precinct are:

- B-2 Water Sensitive Urban Design and Stormwater Management (pg B-16); and
- B-3 Riparian Corridors (pg B-31).

2.5 PENRITH CITY COUNCIL GUIDELINES FOR ENGINEERING WORKS FOR SUBDIVISIONS AND DEVELOPMENTS – PART 1 – DESIGN (1997)

This document outlines Penrith City Council's recommended practice for drainage design. Section 3 of these guidelines specifies drainage design procedures and sets relevant design criteria for design of drainage infrastructure.

2.6 PENRITH CITY COUNCIL STORMWATER MANAGEMENT FOR DEVELOPMENTS 2009 (DRAFT)

This specification contains technical design data for the calculation of flows, flood elevations and velocities along with technical standards for the design of drainage structures. The hydrologic parameters include rainfall intensity charts and runoff parameters for flow estimation. The handbook also outlines hydraulic parameters and design requirements for pits, culverts and pipes.

2.7 OTHER RELEVANT SPECIFICATIONS

The documents outlined above are to be read in conjunction with the following.

- AS/NZ3500.3 'Plumbing and Drainage - Stormwater Drainage;
- Australian Rainfall & Runoff (Engineers Australia);
- Australian Runoff Quality (Engineers Australia);
- 'Technical Note: Interim Recommended Parameters for Stormwater Modelling – North-West and South-West Growth Centres';

- Building Code of Australia Housing Provisions (current edition);
- Penrith City Council's Local Environmental Plan;
- Relevant Penrith City Council Development Control Plans;
- Managing Urban Stormwater - Soils and Construction (current edition);
- Water Sensitive Urban Design in the Sydney Region Resource Kit (2003);
- Water Sensitive Urban Design Technical Guidelines for Western Sydney (2004);
- NSW Floodplain Development Manual (2005);
- Floodplain Risk Management Guideline – Practical Consideration of Climate Change (DECC) and
- Designing Safer Subdivisions – Guidance on Subdivision Design in Flood Prone Areas -
Hawkesbury-Nepean Floodplain Management Strategy Steering Committee, Parramatta, (June 2006)

Table I summarises the design criteria applicable to development of the Horsley Park Employment Precinct, outlines the source of the criteria and provides any comments or departures from the criteria where applicable.

Table 1 Design Criteria

Parameter	Requirement			Source/Reference	Comments/Departures
IFD data	2 year 1 hour		29.4	Appendix 5 PCC 1997	Nil
	2 year 12 hour		6.6		
	2 year 72 hour		1.9		
	50 year 1 hour		59.8		
	50 year 12 hour		12.8		
	50 year 72 hour		4.3		
	F2		4.29		
	F50		15.79		
	skew		0		
Recurrence interval year (% AEP)	Minor	20 year (5% AEP)		Section 3.3 PCC 1997	All roads to be above 100 year level
	Major	100 year(1% AEP)			
	Main Roads	10 year (10% AEP)			
	Building pad levels		500 year (0.2% AEP)	Industrial insurance requirement	
XP RAFTS hydrologic modelling parameters	Initial Loss	Pervious	25 mm		Nil
		impervious	1 mm		
	Continuing	Pervious	2.5 mm		
		impervious	0 mm		
	Roughness	Pervious	0.035		
	impervious	0.015			
DRAINS hydrologic modelling parameters	Paved initial storage		1 mm	Table I Section 3.5.2 PCC 1997	Not used in this report – parameters are set for detailed design stage
	Paved continuing storage		0mm/hr		
	Grassed initial storage		5-10mm		
	Grassed continuing storage		2-5mm/hr		
	Soil Type		3		
	MAC		3		
	Kinematic Roughness coefficient n*				
	Road/Paved Area		0.01		
	Parkland/grassed		0.15		
Rational Method hydrologic parameters	Region B			Section 3.3	C ₁₀ calculated according to Section 3.5.3
	C ₁₀		0.845	PCC 1997	
	FF ₁		0.80	ARR 1987	
	FF ₂		0.85		
	FF ₅		0.95		
	FF ₁₀		1.00		
	FF ₂₀		1.05		
	FF ₅₀		1.15		
	FF ₁₀₀		1.20		

Table 1 (cont) Design Criteria

Parameter	Requirement	Source/Reference	Comments/Departures
HGL	< 150mm below Kerb level for minor (5 year) peak	Section 3.6 PCC 1997	Nil
Impervious Percentages	90% for Industrial Area	Table 3 Section 3.5.3 PCC 1997	Nil
Blockage factor	Pipe inlet 50% headwall 50% lowpoint 100%		Nil
Minimum Pipe size	300 mm within commercial or industrial lots 375 mm within roadways	Section 5.4 PCC2009 Section 3.9.1a PCC1997	Nil
Minimum gradient (pipe)	1:100 (desirable) 1:200	Section 3.9.1e PCC1997 Section 5.4 PCC 2007	1:100 to be used
Pit spacing	Maximum spacing 75 metres	Section 3.7.1.4 PCC 1997	Nil
Velocity depth product	< 0.4 m ² /s in road gutter for the 20 year event < 0.4 m ² /s in road gutter for the 100 year event	Section 3.7.1.2 PCC 1997 NSW Floodplain Development Manual	Nil
Gutter flow width	< 2.5m for 20 year event (or < 80 litres/second)	Section 3.7.1.1 PCC 1997	Nil
Pipe Cover	RCP 0.6m to collar		RCP 1.0m to be used
Minimum Pavement Grade	1:100 concrete 1:50 brick paved 1:30 bitumen seal	Section 6.2 PCC 2009	Nil
Inlet pit location - Intersection	Gutter flows < 1m width or 20 l/s (20 year) adjacent to upstream kerb return tangent point	Section 3.7.1.5 PCC 1997	Nil
Freeboard	500mm above 100 year flood 200mm for 100 year flood level to basin embankment Building pad levels above 500 year (0.2% AEP)	Section 3.4 PCC DCP 2006 Section 5.4.2 PCC 2009 Industrial insurance requirement	Nil

Table 1 (cont) Design Criteria

Parameter	Requirement	Source/Reference	Comments/Departures
Batter slopes (grassed)	1 V:6H for retention/detention basins	Section 6.3 PCC 2009	Nil
Basin slope (minimum)	floor 2%	Section 6.3 PCC 2009	Nil
Basin Fencing	Childproof fencing with lockable gate	Section 6.3 PCC 2009	Nil
<i>MUSIC</i> water quality modelling parameters			
Water Quality	Gross Pollutants	90	GCC 2006 PCC do not have parameters set
Pollutant Removal	Total Suspended Solids	85	
Targets (% removal)	Total Phosphorous	65	
	Total Nitrogen	45	
Rainwater Tanks	Required for development to be approved by the Director-General	Part 5 Section 22 SEPP	Nil

3 PRE-DEVELOPMENT FLOW RATES

3.1 METHODOLOGY

The hydrologic modelling software *XP-RAFTS* (Version 9) was used for hydrological analysis of the site, including the wider Ropes Creek catchment. An *XP-RAFTS* model was developed of the existing catchment to obtain pre-development flows in order to set discharge limits for the developed catchment.

3.1.1 Ropes Creek *XP-RAFTS* Hydrological Model

The *XP-RAFTS* hydrological model of the entire Ropes Creek catchment was used to develop flow rates for existing conditions and for analysis of developed conditions. The layout of the model is presented on Figure 5.




Figure 5 – *XP-RAFTS* Model Layout Plan

The Horsley Park Employment Precinct is located within this catchment wide model and contains three small subcatchments, one draining the area to the north of the site, one to the west and a third to the south eastern corner.

3.1.2 Hydrological Model Parameters

The parameters used in the modelling of Ropes Creek and the catchment including the Horsley Park Employment Precinct are provided in Table 1. These parameters have been determined by Brown Consulting in accordance with the procedures contained within Australian Rainfall and Runoff. Brown Consulting has used these parameters in *XP-RAFTS* models developed for catchments within Western Sydney and specifically within the Western Sydney Employment Area that have been approved by the Growth Centres Commission.

Manning values used in the catchments were 0.015 for the impervious fraction and 0.035 for the pervious fraction, representing urban and well grazed pasture landuses. The impervious fractions used for each landuse included 5% for open space areas and 90% for industrial/commercial areas.

3.1.3 Hydrological Survey Sources

A digital elevation model was developed for the Ropes Creek catchment, including the Horsley Park Employment Precinct, using 5 metre grided LIDAR data provided by the NSW Department of Lands.

3.1.4 Pre-developed Flow Rates

Flow rates for existing conditions were developed in the *XP-RAFTS* hydrologic modelling program using the parameters specified in Table 1. Storm durations from 5 minutes to 72 hours were analysed, with the results of total runoff from the Horsley Park Employment Precinct for the 20 and 100 year recurrence interval presented in Table 2.

Table 2 Existing Condition Peak Flows and Total Catchment Areas			
Node	Total Catch. Area (ha)	Peak Flow (m³/s)	
		20 year	100 year
T11 - East Boundary (Node 77.01)	12.6	1.5	2.1
T1 – Nort East Boundary (Node 78.01)	14.2	1.8	2.7
T1 – u/s of the dam (Node 77.02)	39.5	4.8	7
T1 – d/s of the dam (Node 77.03)	56.2	6.6	9.9
South Boundary (Node 50.01)	25.7	2.5	3.4
South West Boundary (Node 73.01)	33.1	3.1	4
T12 - East Boundary (Node 80.01)	20.9	2.2	3.1
North Boundary (Node 91.03)	74.6	4.2	5.8
T1 – West Boundary (Outlet Node 77.04)	95.7	10.2	14.8

The results in Table 2 show that the pre-development critical storm for the 20 year ARI storms are 18 and 4.5 hour durations and for the 100 year ARI storms 2 and 4.5 hour durations, within the Horsley Park site. These peak flow rates in Tables 2 will be used as the permissible site discharge rate for the design of the stormwater management system for the Horsley Park Employment Precinct.

3.1.5 Calibration/Validation

The runoff parameters specified by Brown Consulting were applied to the *XP-RAFTS* model to estimate flows from the catchment for the 20 and 100 year ARI peak storm events. For the calibration, the Probabilistic Rational Method was used to estimate the flow for comparison to flows calculated using the *XP-RAFTS* model. The results of the flow calculations for the peak storm events for the total 95.7 hectare area at node 77.04 of the Horsley Park Employment Precinct are presented in Table 3.

Table 3 Horsley Park Employment Precinct *XP-RAFTS* & PRM Runoff Calculations

<i>Average Recurrence Interval (years)</i>	<i>XP-RAFTS Hydrologic Model Flow (m³/s)</i>	<i>Probabilistic Rational Method Flow (m³/s)</i>
20	10.2	2.7
100	14.8	11.5

The results in Table 3 indicate that using the runoff parameters specified by Brown Consulting in the *XP-RAFTS* model generates larger flow estimates as using the Probabilistic Rational Method with Penrith City Council specified parameters, for the same time of concentration (2 hour for the 100 year and 18 hour for the 20 year ARI storm events). Therefore at this stage, as a conservative approach, it is appropriate to use the *XP-RAFTS* results, for all hydrologic calculations undertaken in the design of drainage and detention infrastructure for the Horsley Park Employment Precinct.

3.1.6 Post-developed Flow Rates

Flow rates for developed conditions were calculated in the *XP-RAFTS* hydrologic modelling program and are based on the Concept Plan. Sub-catchments were modelled using imperviousness between 40% and 90%. Storm durations from 5 minutes to 72 hours were analysed, with the results of total runoff from the Ropes Creek Employment Precinct for the 100 year recurrence interval presented in Table 4.

Table 4		Developed Conditions Peak Flows	
Node	Peak Flow (m³/s)		
	20 year	100 year	
T11 - East Boundary (Node 77.01)	4.9	6	
T1 – Nort East Boundary (Node 78.01)	2.5	5.1	
T1 – u/s of the dam (Node 77.02)	12	16.9	
T1 – d/s of the dam (Node 77.03)	17.6	21.7	
South Boundary (Node 50.01)	4.6	6	
South West Boundary (Node 73.01)	4.9	6.4	
T12 - East Boundary (Node 80.01)	4.3	5.6	
North Boundary (Node 91.03)	4.9	7	
T1 – West Boundary (Outlet Node 77.04)	21	27	

The results in Table 4 show that post-development peak flows for both 20 and 100 ARI storm event are from 1.5 hour and 2 hour critical duration storms. From the results presented in Table 2 and 4, detention is required to bring the post development flows to pre development levels. This is discussed in section 6.1 of this report.

4 FLOODING ANALYSIS

An analysis of flooding in the Horsley Park Employment Precinct and Ropes Creek was undertaken to assess the constraints caused by flooding and to develop flood planning levels (FPL) and road levels. Flow rates in Ropes Creek and tributaries were developed utilising parameters from modelling undertaken for investigations that have previously been submitted to the Growth Centres Commission, as discussed in Section 3.1.2. The hydraulic modelling software *SOBEK* was used to map flood extents for the 100 year ARI storm event.

4.1 METHODOLOGY

The hydraulic modelling the local tributaries of Ropes Creek through the Horsley Park Employment Precinct has been undertaken in *SOBEK* (Version 2.11.002) developed by Delft Hydraulics. This model enables efficient integration between river hydraulics, where flow can be considered 1D, and the floodplain where flows and associated storage effects are best described by a 2D model. Figure 6 shows the river and floodplain elements as treated by *SOBEK*. The 1D element is represented by a cross section which bisects the 2D surface, which is represented by a raster surface (often referred to as a Digital Elevation Model – DEM). *SOBEK* allows stacked raster grids of varying resolution to derive a surface detailed with the required accuracy.




Figure 6 - Schematic Representations of the Integrated 1D/2D SOBEK Hydraulic Model

4.1.1 Survey Sources

Survey for the study area included ground survey from RPS which was used to form a TIN (triangular irregular network) from which a digital elevation model with 5 metre grid spacing was imported into SOBEK using the *12d* software package. The survey included spot levels taken across the floodplain along with relevant hydraulic features such as embankments, changes in bank and bed levels, and floodplain elevation.

4.1.2 Roughness


A uniform Manning's roughness value was described across the entire Horsley Park Employment Precinct model for the flood estimation. This coefficient of 0.035 for overbank/floodplain roughness and channel roughness was used based on values presented in Table 1.

4.2 EXISTING FLOOD EXTENTS

The existing 100 year flood extents, flood depth and flood surface elevations were calculated using SOBEK hydraulic modelling program. The 100 year flood extents of the tributaries of Ropes Creek within the Horsley Park Employment Precinct are presented in Figure 7, with preliminary flood hazard mapped on Figure 8.

The SOBEK modelling has shown that the 100 year ARI flood levels vary from RL 71.5 m AHD in the location of the existing farm dam, to RL 65 m AHD at the downstream western boundary of the site. Flood depths in the area of the Horsley Park Employment Precinct for pre-development conditions range over the site.

The results show that the 100 year flood within the Ropes Creek tributaries extends onto the proposed location of the lots in the Horsley Park Employment Precinct.



CATCHMENTS
CADASTRE

100Y ARI PEAK EXTENTS
100Y ARI PEAK FLOOD DEPTH

Depth in Metres

0.00 - 0.20

0.50	0.30	0.20
0.30	0.20	0.10

05:00 - 17:00

0.51 - 1.00

1.01 - 1.50

1.51 - 2.00

201 - 300

10.5	10.7
------	------

3.01 - 13.21

Details		
Issue	Amendment	Date
A	CLIENT REVIEW	JULY 2010

Project

**HORSLEY PARK
INDUSTRIAL SUBDIVISION**

Drawing Title

FIGURE 8
100 YEAR ARI PEAK
FLOOD EXTENTS
EXISTING CONDITIONS

Scale
1:8000@A3

Drawn TWC


Checked SC

Job No. X10135

Drawing No. **FIGURE 07**

1555

A



Legend

- CATCHMENTS
- CADASTRE

100Y ARI PEAK HAZARD

Velocity Depth Product

- < 0.40
- 0.41 - 0.60
- 0.61 - 2.45

Details

Issue	Amendment	Date
A	CLIENT REVIEW	JULY 2010

Project

HORSLEY PARK
INDUSTRIAL SUBDIVISION

Drawing Title

FIGURE 8
100 YEAR ARI PEAK
FLOOD HAZARD
EXISTING CONDITIONS

Scale	1:8000@A3
Drawn	TWC
Checked	SC
Job No.	X10135
Drawing No.	FIGURE 08

Issue

A

4.3 PRELIMINARY DEVELOPED FLOOD EXTENTS

The 100 year flood extents of the tributary of Ropes Creek within the Horsley Park Employment Precinct are presented in Figure 9, with preliminary flood hazard mapped on Figure 10.

The flood extents are contained within the E2 Conservation zone, with the 100 year ARI flood levels same as for the existing conditions. The area of the creek next to the existing farm dam will be reggraded to form part of the proposed dam de-commissioning works.

4.4 FLOOD PLANNING LEVELS & ROAD LEVELS

The minimum habitable floor level of buildings will be 500 millimetres above the 100 year ARI flood level. All roads will be located above the 100 year ARI flood level. Preliminary road levels are presented on drawing set X10135.000-402.

Legend

 CREEK REGRADING AREA

 BASIN

 FUTURE ROAD

 LOTS

 BUILDINGS

 RIPARIAN ZONE

 CREEK - Ropes

 100Y ARI PEAK EXTENTS

 100Y ARI PEAK FLOOD DEPTH

 0.00 - 0.20

 0.21 - 0.50

 0.51 - 1.00

 1.01 - 1.50

 1.51 - 2.00

 2.01 - 3.00

 3.01 - 4.53 max

 PEAK WSEL CONTOUR .25m

Details		Amendment	Date
Issue	A	CLIENT REVIEW	JULY 2010
	A	CLIENT REVIEW	NOV 2010

Project

HORSLEY PARK
INDUSTRIAL SUBDIVISION

Drawing Title

FIGURE 9

100 YEAR ARI PEAK
FLOOD EXTENTS
DEVELOPED CONDITIONS

Scale1:8000@A3

DrawnTWC


CheckedSC

Job No.X10135

Drawing No.FIGURE 09

Issue

B



Legend

BASIN

FUTURE ROAD

LOTS

BUILDINGS

RIPARIAN ZONE

CREEK - Ropes

100Y ARI PEAK HAZARD

< 0.40

0.41 - 0.60

0.61 - 1.03 max

Details		Amendment	Date
Issue	A	CLIENT REVIEW	JULY 2010
	B	CLIENT REVIEW	NOV 2010

Project

HORSLEY PARK

INDUSTRIAL SUBDIVISION

Drawing Title

FIGURE 10

100 YEAR ARI PEAK

FLOOD HAZARD

DEVELOPED CONDITIONS

Scale

1:8000@A3

Drawn

TWC

Checked

SC

Job No.


X10135

Drawing No.

FIGURE 10

Issue

B



5 CONCEPT DRAINAGE DESIGN

5.1 LOT DRAINAGE DESIGN

Runoff from the development area for storms up to the 20 year ARI will be collected by the following systems:

- For the car and truck parking/manoeuvring areas, a combination pit and pipe and swale system discharging to a number of bioretention basins around the site. This water is then discharged into swale drains and then into the creek around the site.
- The roof water will be directed to detention basins and from there will be discharged to the creek system.

5.2 TRUNK DRAINAGE DESIGN

Major flows are considered those flows in excess of the 20 year ARI peak flow, in accordance with Penrith City Council Guidelines for Engineering Works for Subdivisions and Developments (1997), presented in Table 1. Such flows from the parking and manoeuvring areas will be directed overland using the internal access-ways and swales (where appropriate). From here the flows are conveyed to the bioretention basins, where detention is provided to reduce the peak flows to pre development levels.

Stormwater flows from the roof areas will be directed to the detention basin within the site. The downpipes and drainage network for this system need to be sized to convey the 100 year ARI flows to the basin.

It is proposed to provide an overland flowpath for the upstream site along the northern section of the eastern boundary of the site. This system will consist of a pipe system sized to convey the 20 year ARI flow and a swale to convey additional flows up to the 100 year ARI to the creek system.

The floor levels of the buildings will be set a minimum of 500 mm above the 100 year ARI flood level.

6 STORMWATER BASIN DESIGN

Section 4 of this report has determined that stormwater detention basins are required to mitigate the floods from the proposed development. The basins have been designed with a bioretention system in the base, with extended detention above, and the base detention basin storage volume above the extended detention. This arrangement minimises space requirements of the basin while meeting pollutant removal performance targets. Bioretention basin and the pollutant removal performance is discussed in more details in Section 6.3. The basins were designed to treat flow from 100 hectares of area of the Horsley Park Employment Precinct.

6.1 DETENTION REQUIREMENTS

The detention strategy requires that individual lot detention basins manage 2 year ARI flows, with large scale community basins with managing 100 year ARI flows to pre-development rates from the catchment. This arrangement ensures no increase in peak flows at Ropes Creek upstream or downstream of the Horsley Park Employment Precinct. The design requirements of the basins are required to limit flows to peak flow rates for the 100 year events as presented in Table 1.

The master stormwater layout for the Horsley Park Employment Precinct incorporates seven basins. The concept basin detentions are modelled in *DRAINS* to determine the effectiveness of the basins to limit flows to pre-development levels of this development. The *DRAINS* outputs are detailed in Table 5 and Table 6.

Table 5 100 year ARI Peak Flows at Detention Basin locations

Basin No.	Exs.Con.	Dev.Con.	Dev.with Basin
	(m³/s)	(m³/s)	(m³/s)
Basin 1	2.46	3.05	2.18
Basin 2	4.84	5.90	4.66
Basin 3	12.60	15.40	12.20
Basin 4	8.46	10.40	7.40
Basin 5	7.19	8.82	7.06
Basin 6	3.66	4.49	3.59
Basin 7	3.97	4.87	3.96

Table 6 Detention Basins requirements				
Basin No.	Surf.Area (m2)	Bioret.Area (m2)	Catch.Area (ha)	Volume (m3)
Basin 1	2,150	1,040	5.7	840
Basin 2	3,400	2,000	11.1	1,500
Basin 3	7,600	5,250	28.8	3,900
Basin 4	5,500	3,540	19.4	3,350
Basin 5	5,000	3,000	16.5	2,200
Basin 6	2,500	1,500	8.4	1,200
Basin 7	2,800	1,700	9.1	1,300

Indicative size of surface area of bioretention filter media for seven detention basins, presented in Table 6 has been determined to meet the water quality targets outlined in Table 1 from the Growth Centres Development Code (DEC 2006). These areas would be readily incorporated in the base of the proposed larger basin areas as presented in Table 6.

6.2 DETENTION BASIN DESIGN

The detention basins have been designed to maximise the storage volume available within the constraints of the road, the riparian buffer zone and the location of the sewage pumping station. A batter slope of 1V:6H and maximum ponding depth of 1.0 metres above the extended detention will be required for the basin.

The outlet of the basin was sized to meet Penrith Council design requirements of attenuating the 100 year flows. This outlet will be sized using the *DRAINS* hydrologic modelling program using parameters specified in Table 1. Preliminary basin locations are presented on Figure 11 and sizing in Section 6.1 of this report.

Legend

CREEK - Ropes

FLOW DIRECTION

DIVERSION CHANNEL

BASIN

FUTURE ROAD

LOTS

BUILDINGS

RIPARIAN ZONE

STORMWATER COLLECTION AREAS

Basin 1 - 5.7ha

Basin 2 - 11.1ha

Basin 3 - 28.8ha

Basin 4 - 19.4ha

Basin 5 - 16.5ha

Basin 6 - 8.4ha

Basin 7 - 9.1ha

Details		Amendment	Date
Issue	A	CLIENT REVIEW	JULY 2010
	B	CLIENT REVIEW	NOV 2010

Project
**HORSLEY PARK
INDUSTRIAL SUBDIVISION**

Drawing Title
**FIGURE 11
PRELIMINARY BASIN LOCATIONS
& STORMWATER MASTERPLAN**

Scale
1:8000@A3


Drawn
TWC

Checked
SC

Job No.
X10135

Drawing No.
FIGURE 11

Issue
B



6.3 WATER QUALITY REQUIREMENTS

The then Department of Environment and Conservation (DEC), now the NSW Office of Water under the Department of Environment, Climate Change and Water (DECCW) has established stormwater management targets as part of the Development Code under the State Environmental Planning Policy “Growth Centres”. The targets are outlined in Table I and are slightly different to those commonly that have been adopted throughout NSW. The targets in Table I are in-line with current best practice nutrient level reductions.

6.3.1 Gross Pollutant Traps

Gross pollutant traps (GPT) are typically placed in-line with the drainage system prior to discharge into a bioretention basin. These capture litter, debris, coarse sediment, oils and greases. While the pollutant capture efficiency of various traps may vary, as a conservative measure for modelling purposes the GPT is assumed to be capable of removing the following annual load:

- Gross Pollutants 90%
- Suspended Sediments 0%
- Total Phosphorous 0%
- Total Nitrogen 0%

It is proposed to install GPTs at the inlets of the detention basins for litter control.

6.3.2 Bioretention Basins

Bioretention basins will be utilised to perform the majority of the water treatment from the site. Bioretention basins consist of shallow areas over most of their surface area to incorporate macrophytes for nutrient uptake.

The bioretention basins have been conceptually designed on the basis of a 1m deep filter medium with a maximum depth of ponding of 0.55m and a 48 hour drawdown.

Suitable wetland macrophyte species for the bioretention basin, would include species such as; *baumea articulata*, *carex appressa*, *cyperus difformis*, *cyperus polystachyos*, *eleocharis sphacelata*, *eleocharis cylindrostachys*, *cyperus flaccidus*, *juncus prisatocarpus*, *juncus remotiflorus*, *juncus usitatus*, *lomandra longifolia*, *phragmites australis* and *phragmites lanuginosum*. All these species exhibit good nutrient

removal rates and are hardy. Landscape drawings will be provided at Project Plan stage to detail the actual species mix to be used in the basin.

Plantings within the bioretention basins must be complementary to the adjacent local native plant communities of the riparian corridor and be able to withstand periods of inundation and some long dry periods between rain events. Suitable littoral or transitional plant species (DLWC 1998) for the bioretention basin would include species such as: *Baumea juncea*, *Carex appressa*, *Carex fascicularis*, *Cyperus exaltatus*, *Carex polystachyus*, *Gahnia sieberana*, *Juncus prismatocarpus*, *Juncus usitatus*, *Lomandra longifolia*, *Paspalum distichum*, and *Schoenus brevifolius*. This is subject to further detailed landscape design.

It is recommended that the bioretention basin filter media be installed after 80% of development is completed within the catchment in order to prevent the filter from being clogged prematurely from construction run off. Prior to installation of the filter media, the bioretention basin will be turfed with *Paspalum distichum*.

Sizing of the bioretention basins has been undertaken using the WSUD Technical Guidelines for Western Sydney and results are presented in Section 6.1.

7 STAGE 1 PROJECT APPLICATION

The proposed developed area and general site layout of Stage I of the development of Horsley Park Employment Precinct are presented on drawings X10135-000 and X10135-001. The layout of the drainage infrastructure of Stage I of the development of Horsley Park Employment Precinct is presented on drawing X10135-102.

7.1 DETENTION REQUIREMENTS

The implementation of the large scale community basins will be staged with each project application to ensure the detention and water quality objectives are met with each development. This arrangement ensures no increase in peak flows at Ropes Creek upstream or downstream of the Horsley Park Employment Precinct.

The concept basin detention of Basin No.6 for Stage I was modelled in *DRAINS* to determine the size and effectiveness of the basins to limit flows to pre-development levels of this Stage I development. The *DRAINS* outputs are detailed in Table 5 and Table 6 in Section 6.1.

7.2 WATER QUALITY REQUIREMENTS

The then Department of Environment and Conservation (DEC), now the NSW Office of Water under the Department of Environment, Climate Change and Water (DECCW) has established stormwater management targets as part of the Development Code under the State Environmental Planning Policy “Growth Centres”. The targets are outlined in Table I and are slightly different to those commonly adopted throughout NSW. The targets in Table I are in-line with current best practice nutrient level reductions and will be used for the design of the Stage I detention basin.

Providing the surface area of bioretention filter media as presented in Table 6 in Section 6.1 for Basin No.6 for the Stage I, will ensure that the treated water meets the required GCC water quality requirements.

7.3 RAINWATER HARVESTING REQUIREMENTS

The roof water will be directed to rainwater harvesting tanks, to detention basins and from there will be discharged to the creek system. These rainwater tanks will be designed to accommodate the non-potable water used within the development. The size of rainwater tank required for the proposed Stage I development have been calculated to be 25 kL.

8 SOIL & WATER MANAGEMENT DURING CONSTRUCTION

8.1 SOIL AND WATER MANAGEMENT PLAN

A Soil and Water Management Plan (SWMP) will be prepared and implemented to minimise potential impacts on hydrology and water quality during the construction period. This plan will incorporate the design and installation of erosion controls in accordance with the requirements *Managing Urban Stormwater: Soils and Construction* published by Landcom (colloquially known as the “Blue Book”).

The plan will include the following:

- At the vegetation clearing stage, cleared vegetation will be mulched and spread over disturbed area to provide a natural erosion barrier
- Prior to commencement of earthworks, a range of measures will be put in place including:
 - Construction of cut-off drains to prevent clean water from upstream of the corridor flowing onto and eroding disturbed areas
 - The diversion of site discharge points to erosion control measures such as silt fences and sedimentation basins in order to control dirty water areas
 - The stabilisation of exposed areas as soon as practical following the construction of each section of works
- Controls outside the specific work area would be put in place including:
 - Refuelling of plant and machinery within bunded areas or off site in appropriate locations
 - Minimisation of disturbed areas so that the potential export of sediment is minimised
 - The establishment and maintenance of stabilised construction compounds to reduce the overall disturbance area for the Project.
- Temporary sediment basins will be constructed to capture water and sediment before it can leave the site or enter the receiving water bodies. Conceptual design of the temporary sediment basins will be included in the SWMP and follow the methodology outlined in the “Blue Book” with the following features:
 - Sediment basins are to be located at points near where dirty water would discharge to receiving waters or leave the site
 - Basins are to be designed for Type F/D soils, as outlined in Section 6.3.4 of the Blue Book, in accordance with the soil type classifications
 - The minimum depth of the basins will be 0.6 metres with an average depth of 1 metre.

A surface water quality monitoring program for the construction period will be developed to monitor water quality upstream and downstream of the construction areas. Construction period monitoring will be carried out periodically and after rainfall events as part of the assessment of the operation of water quality mitigation measures. Monitoring during the construction phase of the project would examine the following indicators:

- pH
- Electrical conductivity
- Turbidity
- Dissolved oxygen

8.2 DUST MANAGEMENT PLAN

A Dust Management Plan will be prepared and implemented to provide best management strategies for dust control and an approved monitoring program for identified key issues and areas of concern, to achieve target dust deposition and minimise adverse impacts and complaints relating to dust emissions.

The sources of dust and emissions during construction include the following:

- Wind-blown sand and dust due to large exposed areas during reclamation
- Earthworks activities
- Stockpiling sand on reclamation
- Loading and unloading materials
- Transport of sand and other spoil
- Use of haul roads

Dust Control Measures include:

- Dust monitoring conducted both prior and during construction activities (installing dust deposition gauges at identified locations; daily and weekly visual surveillance of dust emissions, dust controls, plant emissions; meteorological daily data collection such as wind speed, rain, temperature, humidity etc.)
- Where possible, minimise disturbed and exposed areas
- Locate stockpiles as far away from public and residential areas as possible

- Dust control on short-term stockpiles (≤ 3 months) will be controlled using water sprays, drift fencing and daily inspections and long-term (≥ 3 months) progressive vegetation and bitumen emulsions
- Construct wind-breaks or drift fences made of geo-fabric screens at regular intervals around stockpiles and erodible areas
- Apply a thin layer of bitumen or grass in completed reclamation areas
- Inspect equipment and vehicles exhaust emissions at start up and during construction and do not leave machinery and vehicles running when not in use
- Cement will be delivered to site in sealed tankers and pumped to silos, providing a closed system to prevent dust emissions
- Restrict construction traffic to defined areas and speed limits
- Wherever possible, seal internal construction-related roads
- Cover unsealed roads with road base rock and gravel and keep moist
- Operate a water spray system over any gravel stockpiles
- During dry and windy conditions spray water over the road surfaces to prevent wind erosion

The volume of water required for dust suppression will vary according to prevailing climatic conditions, the extent of haul road development and the usage of the haul roads. It is considered that on days that the daily rainfall exceeds evaporation it is unlikely that dust suppression will be required. As such the yearly rate for haul road watering has been calculated using the effective evaporation for the site multiplied by the area of haul road to be watered (assumed width of 30 m) and multiplied by a factor of 1.4 to allow for increased evaporation due to vehicle movements on the haul road. Based on this calculation, the typical annual water demand for haul dust suppression will range from 13 ML/km to 16 ML/km of haul road for a wet rainfall year and dry rainfall year respectively.

9 CONCLUSION

The hydrological and hydraulic modelling has shown that the proposed subdivision and supporting roads of the Horsley Park Employment Precinct can be constructed while meeting Penrith City Council, DECCW and NSW Office of Water requirements for stormwater quantity and quality management.

The objectives and performance targets (quantity and quality) are achieved by using a mix of water sensitive urban design (WSUD) components throughout the subdivision, including rainwater tanks and bio-retention basins with detention storage.

10 REFERENCES

Faculty for Advancing Water Biofiltration (FAWB) (2009). *Adoption Guidelines for Stormwater Biofiltration Systems*, Faculty for Advancing Water Biofiltration, Monash University, June 2009.

Institution of Engineers Australia 2001. *Australian Rainfall & Runoff*.

NSW Department of Environment and Conservation (DEC, now DECCW) 2006, *Growth Centres Development Code*

NSW Department of Land and Water Conservation 1998, *The Constructed Wetland Manual*

Penrith Council 2009, Engineering Design Specification

Penrith Development Control Plan 2006

Penrith City Council – Erskine Park Employment Area Development Control Plan 2002

Penrith City Council Guidelines for Engineering Works for Subdivisions and Developments – Part I – Design (1997)

Penrith City Council Stormwater Management for Developments 2009 (DRAFT)

11 GLOSSARY OF TERMS

Afflux	The rise in water level upstream of a hydraulic structure such as a bridge or culvert, caused by losses incurred from the hydraulic structure.
Australian Height Datum	National survey datum corresponding approximately to mean sea level.
Annual Exceedance Probability	The chance of a flood of a given size or larger occurring in any one year, generally expressed as percentage probability. For example, a 100 year ARI flood is a 1% AEP flood. An important implication is that when a 1% AEP flood occurs, there is still a 1% probability that it could occur the following year.
Average Recurrence Interval	Is the long term average number of years between the occurrence of a flood as big as, or larger than the selected flood event.
Catchment	The catchment at a particular point is the area of land which drains to that point.
Design floor level	The minimum (lowest) floor level specified for a building.
Design flood	A hypothetical flood representing a specific likelihood of occurrence (for example the 100 year or 1% probability flood). The design flood may comprise two or more single source dominated floods.
Development	Existing or proposed works which may or may not impact upon flooding. Typical works are filling of land, and the construction of roads, floodways and buildings.
Discharge	The rate of flow of water measured in terms of volume over time. It is not the velocity of flow which is a measure of how fast the water is moving rather than how much is moving. Discharge and flow are interchangeable.
Digital Terrain Model	A three-dimensional model of the ground surface that can be represented as a series of grids with each cell representing an elevation (DEM) or a series of interconnected triangles with elevations (TIN).
Effective warning time	The available time that a community has from receiving a flood warning to when the flood reaches their location.
Flood	Above average river or creek flows which overtop banks and inundate floodplains.
Flood awareness	An appreciation of the likely threats and consequences of flooding and an understanding of any flood warning and evacuation procedures. Communities with a high degree of flood awareness respond to flood warnings promptly and efficiently, greatly reducing the potential for damage and loss of life and limb. Communities with a low degree of flood awareness may not fully appreciate the importance of flood warnings and

	flood preparedness and consequently suffer greater personal and economic losses.
Flood behaviour	The pattern / characteristics / nature of a flood.
Flooding	The State Emergency Service uses the following definitions in flood warnings: <i>Minor flooding:</i> causes inconvenience such as closing of minor roads and the submergence of low level bridges <i>Moderate flooding:</i> low-lying areas inundated requiring removal of stock and/or evacuation of some houses. Main traffic bridges may be covered. <i>Major flooding:</i> extensive rural areas are flooded with properties, villages and towns isolated and/or appreciable urban areas are flooded.
Flood frequency analysis	An analysis of historical flood records to determine estimates of design flood flows.
Flood fringe	Land which may be affected by flooding but is not designated as a floodway or flood storage.
Flood hazard	The potential threat to property or persons due to flooding.
Flood level	The height or elevation of flood waters relative to a datum (typically the Australian Height Datum). Also referred to as “stage”.
Flood liable land	Land inundated up to the probable maximum flood – flood prone land.
Floodplain	Land adjacent to a river or creek which is inundated by floods up to the probable maximum flood that is designated as flood prone land.
Flood Planning Levels	Are the combinations of flood levels and freeboards selected for planning purposes to account for uncertainty in the estimate of the flood level.
Flood proofing	Measures taken to improve or modify the design, construction and alteration of buildings to minimise or eliminate flood damages and threats to life and limb.
Floodplain Management	The coordinated management of activities which occur on flood liable land.
Floodplain Management Manual	A document by the NSW Government (2001) that provides a guideline for the management of flood liable land. This document describes the process of a floodplain risk management study.
Flood source	The source of the flood waters.
Floodplain Management Standard	A set of conditions and policies which define the benchmark from which floodplain management options are compared and assessed.
Flood standard	The flood selected for planning and floodplain management activities. The flood may be an historical or design flood. It should be based on an understanding of the flood behaviour and the associated flood hazard. It should also take into account social, economic and ecological considerations.

Flood storages	Floodplain areas which are important for the temporary storage of flood waters during a flood.
Floodways	Those areas of the floodplain where a significant discharge of flow occurs during floods. They are often aligned with naturally defined channels. Floodways are areas that, even if they are partially blocked, would cause significant redistribution of flood flows, or a significant increase in flood levels.
Freeboard	A factor of safety usually expressed as a height above the flood standard. Freeboard tends to compensate for the factors such as wave action, localised hydraulic effects and uncertainties in the design flood levels.
Geographical Information System	A form of computer software developed for mapping applications and data storage. Useful for generating terrain models and processing data for input into flood estimation models.
High hazard	Danger to life and limb; evacuation difficult; potential for structural damage, high social disruption and economic losses. High hazard areas are those areas subject to a combination of flood depth and flow velocity that are deemed to cause the above issues to persons or property.
Historical flood	A flood which has actually occurred – Flood of Record.
Hydraulic	The term given to the study of water flow in rivers, estuaries with coastal systems.
Hydrograph	A graph showing how a river or creek's discharge changes with time.
Hydrology	The term given to the study of the rain-runoff process in catchments.
Low hazard	Flood depths and velocities are sufficiently low that people and their possessions can be evacuated.
Management plan	A clear and concise document, normally containing diagrams and maps, describing a series of actions that will allow an area to be managed in a coordinated manner to achieve defined objectives.
Map Grid Australia	A national coordinate system used for the mapping of features on a representation of the earth's surface. Based on the geographic coordinate system 'Geodetic Datum of Australia 1994'.
Peak flood level, flow or velocity	The maximum flood level, flow or velocity occurring during a flood event.
Probable Maximum Flood	An extreme flood deemed to be the maximum flood likely to occur at a particular location.
Probable Maximum Precipitation	The greatest depth of rainfall for a given duration meteorologically possible over a particular location. Used to estimate the probable maximum flood.
Probability	A statistical measure of the likely frequency or occurrence of flooding.

Riparian Zone	Areas that are located adjacent to watercourses. Their definition is vague and can be characterised by landform, vegetation, legislation or their function.
Runoff	The amount of rainfall from a catchment which actually ends up as flowing water in the river or creek.
Stage hydrograph	A graph of water level over time.
Velocity	The speed at which the flood waters are moving. Typically, modelled velocities in a river or creek are quoted as the depth and width averaged velocity, i.e. the average velocity across the whole river or creek section.
Water Sensitive Urban Design	An approach to planning and design of urban development that aims to minimise the negative impacts on the natural water cycle. This design philosophy aims to protect the health of aquatic ecosystems by integrating “natural” features into the stormwater, water supply and sewage management of a development.

12 APPENDICES

Appendix A

Drawings

APPENDIX A

DRAWINGS

LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT

ROAD AND BULK EARTHWORK CONCEPT STAGE 1

DRAWING LIST

GENERAL	
000	COVER SHEET
001	GENERAL LAYOUT PLAN
ENGINEERING PLANS	
101	ENGINEERING PLAN SHEET 1 OF 2
102	ENGINEERING PLAN SHEET 2 OF 2
ROADWORKS	
201	ROAD No.02 LONGSECTION SHEET 1 OF 2
202	ROAD No.02 LONGSECTION SHEET 2 OF 2
301	ROAD No.02 CROSS SECTIONS SHEET 1 OF 3
302	ROAD No.02 CROSS SECTIONS SHEET 2 OF 3
303	ROAD No.02 CROSS SECTIONS SHEET 3 OF 3
SITE REGRADING	
401	SITE REGRADING SECTIONS



LOCALITY PLAN
N.T.S.

LGA BLACKTOWN COUNCIL

JACFIN PTY LTD


[Brown Consulting \(NSW\) Pty Ltd](#)

Level 2, 2 Burbank Place, Norwest Business Park
Baulkham Hills NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099

© 2010

LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1
JOB No: X10135

DRAWING	REVISION
000	A



GENERAL LAYOUT PLAN

Drawn by: A.Mc	Scale(A1): 1:5000
Design by: M.N.	
Project No: X10135	
Drawing No: 001	Revision

A	12/08/2010	PROJECT PLAN DESIGN	MN BY	PF VER	TT APP	
REV	DATE	DESCRIPTION				
		REVISIONS				

Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE
BY SUPERINTENDENT PRIOR TO
CONSTRUCTION. USE WRITTEN
DIMENSIONS ONLY. DO NOT SCALE.



 Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099

BROWN



Sydney
Canberra
Brisbane
Melbourne
Singapore

APPROVAL	
BY:	TOBY TAMES BE (Hons) GradDipMgt CPESC CPEng MIEAust Director
SIGN:	
DATE:	12/08/2010

Client:	JACFIN PTY LTD
Project:	LOT 4 BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT ROAD AND BULK EARTHWORK CONCEPT STAGE 1

Drawing:	GENERAL LAYOUT PLAN	Drawn by:	Scale(A1): 1:5000
		Design by:	
		Project No:	
		Drawing No: 001	

FOR CONTINUATION REFER TO DRAWING No. 102



ROAD No.02 TYPICAL SECTION
Scale: 1:200

PRELIMINARY

\\sbs\hdd\projects\1010135 - Horsley Park Industrial Subdivision\Drawings\CD\1010135-01.dwg
Saved: 12/08/2010 By: mchase\mchase

REVISIONS			BY		
REV	DATE	DESCRIPTION	BY	VER	APP
A	12/08/2010	PROJECT PLAN DESIGN	MN	PF	TT

Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE
BY SUPERINTENDENT PRIOR TO
CONSTRUCTION. USE WRITTEN
DIMENSIONS ONLY, DO NOT SCALE.

© Brown Consulting (NSW) Pty Ltd



Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099

Sydney
Canberra
Brisbane
Melbourne
Singapore

APPROVAL
BY: TOBY TAMES
BE (Hons) GradDipMgt CPESC CPEng MIEAust
Director
SIGN:
DATE: 12/08/2010


Client:
JACFIN PTY LTD

Project:
LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1

Drawing:
**ENGINEERING PLAN
SHEET 1 OF 2**


Drawn by:
A.Mc
Design by:
M.N.
Project No:
X10135
Drawing No:
101
Revision:
A

Scale(A1):
1:1000



FOR CONTINUATION REFER TO DRAWING No. 101

PRELIMINARY



REV	DATE	DESCRIPTION	BY	VER	APP
A	12/08/2010	PROJECT DESIGN PLAN	MN	PF	TT
REVISIONS					

Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE
BY SUPERINTENDENT PRIOR TO
CONSTRUCTION. USE WRITTEN
DIMENSIONS ONLY, DO NOT SCALE.



Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099

APPROVAL
BY: TOBY TAMES
BE (Hons) GradDipMgt CPESC CPEng MIEAust
Director
SIGN:
DATE: 12/08/2010


Client:
JACFIN PTY LTD
Project:
LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1

Drawing:
ENGINEERING PLAN SHEET 2 OF 2

Drawn by:
A.Mc
Design by:
M.N.
Project No:
X10135
Drawing No:
102
Revision:
A




1 of 14



LONGSECTION ROAD NO.02

Scale: 1:500(H) 1:100(V)



LONGSECTION ROAD NO.02 CONT'D

Scale: 1:500(H) 1:100(V)

PRELIMINARY

Saved: 12/08/2010 By: michael.norman
H:\10.0\10.035 - Horsley Park Industrial Subdivision Drawings\Civil\10.035-201.dwg

05101520253035404550 SCALE 1:500 (A1)			012345678910 SCALE 1:100 (A1)			012345678910 SCALE 1:200 (A3)		
						Disclaimer and Copyright: ALL DIMENSIONS TO BE CHECKED ON SITE BY SUPERINTENDENT PRIOR TO CONSTRUCTION. USE WRITTEN DIMENSIONS ONLY, DO NOT SCALE.		




Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099
Sydney
Canberra
Brisbane
Melbourne
Singapore


APPROVAL
BY: TOBY TAMES
BE (Hons) GradDipMgt CPESC CPEng MIEAust
Director
SIGN:
DATE: 12/08/2010

Client:
JACFIN PTY LTD
Project:
LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1


Drawing:
ROAD No.02 LONGSECTION
SHEET 1 OF 2
Drawn by: A.Mc
Design by: M.N.
Project No: X10135
Drawing No: 201
Revision: A



LONGSECTION ROAD NO.02 CONT'D
Scale: 1:500(H) 1:100(V)




LONGSECTION ROAD NO.04
Scale: 1:500(H) 1:100(V)




ROAD NO.04 TYPICAL SECTION
Scale: 1:200

PRELIMINARY



REV	DATE	DESCRIPTION	BY	VER	APP
A	12/08/2010	PROJECT PLAN DESIGN	MN	PF	TT
REVISIONS					

Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE
BY SUPERINTENDENT PRIOR TO
CONSTRUCTION. USE WRITTEN
DIMENSIONS ONLY, DO NOT SCALE.



Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099

Sydney
Canberra
Brisbane
Melbourne
Singapore

APPROVAL
BY: TOBY TAMES
BE (Hons) GradDipMgt CPESC CPEng MIEAust
Director
SIGN:
DATE: 12/08/2010


Client:
JACFIN PTY LTD
Project:
LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1

Drawing:
ROAD No.02 LONGSECTION
SHEET 2 OF 2


Drawn by:
A.Mc
Design by:
M.N.
Project No:
X10135
Drawing No:
202
Revision:
A

Scale(A1):
AS NOTED


----- REPRESENTS EARTHWORKS ONLY




CH 700




CH 650




CH 600




CH 850




CH 800



CH 750



CH 900



Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE
BY SUPERINTENDENT PRIOR TO
CONSTRUCTION. USE WRITTEN
DIMENSIONS ONLY, DO NOT SCALE.

© Brown Consulting (NSW) Pty Ltd



Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099




APPROVAL
BY: **TOBY TAMES**
BE (Hons) GradDipMgt CPESC CPEng MIEAust
Director
SIGN:
DATE: 12/08/2010

Client:
JACFIN PTY LTD
Project:
LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1

Drawing:
**ROAD No.02 CROSS SECTIONS
SHEET 1 OF 3**
Drawn by:
A.Mc
Design by:
M.N.
Project No:
X10135
Drawing No:
301
Revision:
A

PRELIMINARY

Scale(A1):
1:200



REV	DATE	DESCRIPTION	BY	VER	APP
A	12/08/2010	PROJECT PLAN DESIGN	MN	PF	TT
REVISIONS					

Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE
BY SUPERINTENDENT PRIOR TO
CONSTRUCTION. USE WRITTEN
DIMENSIONS ONLY, DO NOT SCALE.

© Brown Consulting (NSW) Pty Ltd



Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099

Sydney
Canberra
Brisbane
Melbourne
Singapore

APPROVAL
BY: TOBY TAMES
BE (Hons) GradDipMgt CPESG CPEng MIEAust
Director
SIGN:
DATE: 12/08/2010







Client:
JACFIN PTY LTD

Project:
LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1


Drawing:
**ROAD No.02 CROSS SECTIONS
SHEET 3 OF 3**

Drawn by: A.Mc
Design by: M.N.
Project No: X10135
Drawing No: 303
Revision: A


Scale(A1):
1:200




1 of 14




SECTION 1
Scale: 1:1000(H) 1:500(V)




SECTION 2
Scale: 1:1000(H) 1:500(V)



SECTION 3
Scale: 1:1000(H) 1:500(V)



SECTION 4
Scale: 1:1000(H) 1:500(V)



PRELIMINARY

REV	DATE	DESCRIPTION	BY	VER	APP
A	12/08/2010	PROJECT PLAN DESIGN	MN	PF	TT
REVISIONS					

Disclaimer and Copyright:
ALL DIMENSIONS TO BE CHECKED ON SITE
BY SUPERINTENDENT PRIOR TO
CONSTRUCTION. USE WRITTEN
DIMENSIONS ONLY, DO NOT SCALE.



Brown Consulting (NSW) Pty Ltd
Level 2, 2 Burbank Place Norwest Business Park NSW Australia 2153
Telephone: 02 8808 5000 Facsimile: 02 8808 5099

APPROVAL
BY: TOBY TAMES
BE (Hons) GradDipMgt CPESC CPEng MIEAust
Director
SIGN:
DATE: 12/08/2010

Client:
JACFIN PTY LTD
Project:
LOT A BURLEY ROAD, HORSLEY PARK EMPLOYMENT PRECINCT
ROAD AND BULK EARTHWORK CONCEPT STAGE 1

Drawing:
SITE REGRADING SECTIONS
Drawn by: A.Mc
Design by: M.N.
Project No: X10135
Drawing No: 401
Revision: A